

AD A068546

DDC FILE COPY

LEVEL II


UPPER HUDSON RIVER BASIN

(20)
MD

CONKLINGVILLE DAM

**SARATOGA COUNTY, NEW YORK
INVENTORY NUMBER NY 146**

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED
CONTRACT NO. DACW-51-78-C-0025

DDC
RECEIVED
MAY 15 1979
C

Prepared by

**L. ROBERT KIMBALL and ASSOCIATES
615 W. Highland Ave. Ebensburg, Pa.**

Prepared For

**DEPARTMENT OF THE ARMY
NEW YORK DISTRICT, CORPS OF ENGINEERS
NEW YORK, NEW YORK**

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report Conklingville Dam Upper Hudson River Basin, Saratoga County, N.Y. Inventory No. N.Y. 146		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) <u>10</u> R. Jeffrey/Kimball/P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS L. Robert Kimball and Associates 615 W. Highland Avenue Ebensburg, Pennsylvania		8. CONTRACT OR GRANT NUMBER(s) <u>15</u> DACW-51-78-C-0025
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation/ 50 Wolf Road Albany, New York 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS <u>17</u>
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza/ New York District, CofE New York, New York 10007		12. REPORT DATE 31 July 1978
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited. <u>12</u> <u>233p.</u>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) <u>1</u> <u>20</u> <u>N.Y.</u> National Dam Safety Program, Conklingville Dam, Upper Hudson River Basin, Saratoga County, New York (NY-146). Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Saratoga County Sacandaga River Conklingville Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Conklingville Dam was judged to be safe, although evaluation of the embankment under seismic loading was recommended.		

Table of Contents

	Page No.
General	1
Overview Photograph	
Site Location Map	2
Section 1: Project Information	3
Section 2: Engineering Data	7
Section 3: Visual Inspection	8
Section 4: Operational Procedures	9
Section 5: Hydraulic/Hydrologic	10
Section 6: Structural Stability	13
Section 7: Assessment/Remedial Measures	14
Appendices:	
A. Geology	
B. Hydrologic Computations	
C. Photographs	
D. Pertinent Correspondence and Reports	
E. Construction Drawings	
F. Visual Check List	
G. Engineering Data Check List	

A 23
GA

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Conklingville Dam (Great Sacandaga Lake)

State Located: New York

County Located: Saratoga

Stream: Sacandaga River

Date of Inspection: June 16, 1978

ASSESSMENT

The inspection and review of data of Conklingville Dam did not reveal any problems which require immediate emergency action. The dam appears to be stable, well maintained, and safely operated.

The reservoir and spillway are adequate to control the PMF with eight (8) feet of freeboard remaining.

The hydraulic fill (puddle core) type construction in a moderate seismic zone and the lack of information on construction, embankment materials, and stability analysis dictate that evaluation of the embankment under seismic loading be completed in the future.

Replacement of rock rip rap at the downstream end of the principal spillway discharge should be completed to prevent further erosion during peak discharge periods.

Approved by

R. Jeffrey Kimball
R. Jeffrey Kimball, P.E.

L. ROBERT KIMBALL & ASSOCIATES

Registration No. PA 26275E

Approved by

Clark H. Benn
CLARK H. BENN

Colonel, Corps of Engineers

District Engineer


Date:


31 July 1978



OVERVIEW OF DAM FROM
LOOKOUT ON LEFT ABUTMENT

William E. Casler
DESIGNING ENGINEER





STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
CONKLINGVILLE DAM
ISOMETRIC VIEW

100' 0' 100'

SEPT 1927

[Handwritten signature]

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
CONKLINGVILLE DAM ID #146

SECTION 1: PROJECT INFORMATION

1.1 General:

- a. Authority: Authority is provided by the National Dam Inspection Act Public Law 92-367.
Contract Number DACW51-78-C-0025
- b. Purpose of Project: Evaluation of non-Federal dams to identify dams which are a threat to life and property.

1.2 Description of Project:

- a. Description of Dam and Appurtenances: The Conklingville Dam (Great Sacandaga Lake) is a zoned earth and rock fill dam. The embankment is 96 feet high constructed with upstream and downstream rock toes and random earth zones with a central puddle core. The impounded lake is currently used for flow regulation in the Hudson River, recreation and hydropower production.

The emergency spillway system is an ogee weir 400 feet long. The spillway is located at the left abutment downstream of the dam axis. Water enters the spillway through a channel at the left abutment. This channel also feeds the principal spillway, the siphon spillways and the powerhouse.

The siphon spillways, two 8' x 18' openings, can be considered part of the emergency spillway system as they are designed to prime with 2' of head over the emergency spillway crest elevation. This condition has not been experienced and the siphons not utilized.

The principal spillway system, day to day, regulating controls, is a two part system. The portion designed with the dam consists of three 8 foot diameter steel pipes with controls located in the gate house at the left abutment along the emergency spillway channel.

The second portion of the principal outlet works is the hydropower station located at the end of the emergency spillway channel. Water from the dam feeds two turbines at the average rate of 4,000 CFS 15 hours a day. The powerhouse normally serves as the regulating facility with the three 8 foot diameter pipes used on an as needed basis.

c. Elevations (Feet above MSL):

Top of Dam : 795.0'

Maximum Pool Design Surcharge: 778.95

Emergency Spillway Crest: 771.0

Streambed at Centerline of Dam: 699.0

Maximum Tailwater: Approximately 710

d. Reservoir:

Length of Normal Pool: Elevation 771 - 27 miles

Length of Maximum Pool: Elevation 794.5 - 28 miles

e. Storage:

Normal Pool: Elevation 771 - estimated 1.16 million acre-feet

Design Pool: Elevation 778.95 - estimated 1.36 million acre-feet

Top of Dam: estimated 1.81 million acre-feet

f. Reservoir Surface Area: (Acres)

Top of Dam: 28,800

Normal Pool: 25,200

g. Dam:

Type: Earth and rock fill

Length: 1,100 feet

Height: 96 feet

Top Width: 43 feet

Side Slope: Upstream 3:1 to 4:1
Downstream 2.5:1 to 4.25:1

Zoning: Sluiced Core with earth zones and rock zones

Impervious Core: Sluiced core

SECTION 4: OPERATIONAL PROCEDURES

- 4.1 Procedures: Conklingville Dam is maintained and operated by a full-time staff stationed at the dam with support from other dam staffs of the agency.

The dam is operated for several purposes. The primary purpose is regulation of flow in the Hudson River and flood control. Secondary uses are power production and recreation.

Under normal conditions flow is discharged to the Hudson River via the Stewarts Bridge Reservoir through the hydropower station at an optimum rate of 4,000 CFS. A flow of 3,000 CFS must be maintained to the river. However, the power plant is regularly not operated around the clock or every day.

As necessary, during flood seasons the principal spillways are used to lower the reservoir level in a controlled manner. The average low water level in winter is elevation 744' (27 feet below the spillway). The average high in spring is elevation 767' (4 feet) below the spillway. The maximum water level to date is 770.75'.

- 4.2 Maintenance of Dam: The dam is well maintained by a conscientious staff. Mowing, and other maintenance are performed as needed.
- 4.3 Maintenance of Operating Facilities: Maintenance of the principal spillway structure is conducted as needed, and the gates are operated regularly.
- 4.4 Warning Systems: No formal warning system is in use.
- 4.5 Evaluation: The dam and appurtenant structures are well maintained. Periodic inspections are made of the entire structure and reports prepared. Detailed operational and maintenance records, and rainfall and discharge records are kept.

Cutoff: Cutoff or sluiced core approximately 20 feet deep.

Crout Curtain: Asphalt grouted in 1933.

- h. Diversion and Regulating Tunnel: During construction river flow passed by an open channel at control house. The three 8' diameter pipes eventually installed in the open channel.

Type: Three 8' diameter steel flanged pipes

Length: 62 feet

Closure: Operable by three valves with electric motors.

Access: Valves operated in control house. If motors fail the valves can be operated manually in valve chamber.


Regulating Facilities: Valves only opened during flooding.

- i. Spillway:

	<u>Emergency Spillway</u>	<u>Siphon Spillway</u>
Type:	Concrete ogee	Concrete ogee
Length of Weir:	400'	36'
Crest Elevation:	771.0'	773.0'
Gates:	None	None
U/S Channel:	Rock cut with concrete retaining walls	
D/S Channel:	Outlet channel 30' wide then to Sacandaga River	70' drop to Sacandaga River

- j. Regulating Outlets: Combination of three 8' diameter pipes and gates at powerhouse.

Form 66, 6-6-41-1000



SECTION 3: VISUAL INSPECTION

3.1 Findings:

- a. General: Conklingville Dam was inspected by personnel of L. ROBERT KIMBALL & ASSOCIATES and the Hudson River - Black River Regulating District on June 16, 1978.
- b. Dam: The dam appears to conform closely to the construction drawings. In general the dam appeared to be well constructed and well maintained. The dam did not appear to be in distress and no settlement or seepage zones were noted at the time of our inspection. Some heavy rock has been washed out near the outlet channel.
- c. Appurtenant Structures: All spillways, gates, valves, and control house appeared to be in good condition and well maintained.
- d. Reservoir Area: The dam retains the waters of the Sacandaga River. The valley bottoms are generally covered with thick glacial sediment and the valley sides are covered with a thinner layer of soil.
- e. Downstream Channel: The downstream channel is wide and open. Stewarts Bridge Dam is approximately three miles downstream and tailwater of this dam will backup to Conklingville Dam.

- 3.2 Evaluation: Visual inspection revealed that the dam appears to be stable and in good condition. However no stability information was available for review. No seepage or settlement was noted during our inspection. The downstream berm appeared to have been modified during construction (the berm widened and steepened). Some washout of the heavy rock near the outlet channel was noted.

SECTION 3: VISUAL INSPECTION

3.1 Findings:

- a. General: Conklingville Dam was inspected by personnel of L. ROBERT KIMBALL & ASSOCIATES and the Hudson River - Black River Regulating District on June 16, 1978.
- b. Dam: The dam appears to conform closely to the construction drawings. In general the dam appeared to be well constructed and well maintained. The dam did not appear to be in distress and no settlement or seepage zones were noted at the time of our inspection. Some heavy rock has been washed out near the outlet channel.
- c. Appurtenant Structures: All spillways, gates, valves, and control house appeared to be in good condition and well maintained.
- d. Reservoir Area: The dam retains the waters of the Sacandaga River. The valley bottoms are generally covered with thick glacial sediment and the valley sides are covered with a thinner layer of soil.
- e. Downstream Channel: The downstream channel is wide and open. Stewarts Bridge Dam is approximately three miles downstream and tailwater of this dam will backup to Conklingville Dam.

- #### 3.2 Evaluation:
- Visual inspection revealed that the dam appears to be stable and in good condition. However no stability information was available for review. No seepage or settlement was noted during our inspection. The downstream berm appeared to have been modified during construction (the berm widened and steepened). Some washout of the heavy rock near the outlet channel was noted.

SECTION 4: OPERATIONAL PROCEDURES

- 4.1 Procedures: Conklingville Dam is maintained and operated by a full-time staff stationed at the dam with support from other dam staffs of the agency.

The dam is operated for several purposes. The primary purpose is regulation of flow in the Hudson River and flood control. Secondary uses are power production and recreation.

Under normal conditions flow is discharged to the Hudson River via the Stewarts Bridge Reservoir through the hydropower station at an optimum rate of 4,000 CFS. A flow of 3,000 CFS must be maintained to the river. However, the power plant is regularly not operated around the clock or every day.

As necessary, during flood seasons the principal spillways are used to lower the reservoir level in a controlled manner. The average low water level in winter is elevation 744' (27 feet below the spillway). The average high in spring is elevation 767' (4 feet) below the spillway. The maximum water level to date is 770.75'.

- 4.2 Maintenance of Dam: The dam is well maintained by a conscientious staff. Mowing, and other maintenance are performed as needed.
- 4.3 Maintenance of Operating Facilities: Maintenance of the principal spillway structure is conducted as needed, and the gates are operated regularly.
- 4.4 Warning Systems: No formal warning system is in use.
- 4.5 Evaluation: The dam and appurtenant structures are well maintained. Periodic inspections are made of the entire structure and reports prepared. Detailed operational and maintenance records, and rainfall and discharge records are kept.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Hydrologic Evaluation of Features:

- a. Design Data: Some discussion of the spillway design is available in old reports on the dam. These reports indicate a 600 foot long spillway was originally contemplated for a maximum design peak of 50,000 CFS and a maximum water level of 7 to 8 feet allowing for 16 feet of freeboard.

No design information is available on the as built spillway.

- b. Experience Data: Reservoir water level and discharge records are kept. To date the maximum discharge at the site is estimated at 10,000 CFS, from flow to the powerhouse and two of the three 8' diameter principal spillway pipes. To date no flow has been recorded over the ogee weir, therefore no flow into the siphon. Only two of the three principal spillway pipes have been opened at one time.

The "Upper Hudson and Mohawk River Basin Hydrologic Flood Routing Models" study prepared by the Corps of Engineers, New York District modeled the 1948, June 1972, SPF, and transposed Agnes floods for the watershed. Hydrologic parameters developed in this study were used to develop the SPF and PMF for this study.

- c. Visual Observations: At the time of the inspection discharge was to the powerhouse only (approximately 4,000 CFS) and the water level was at elevation 766.15 approximately 5 feet below the spillway weir.

The rock slope below the spillway was gunnited and has an appearance of weathered rock. The gunnite has deteriorated but not to a point where it will affect spillway function. The gatehouse and mechanical equipment are in good condition.

- d. Overtopping Potential: To determine the overtopping potential for Conklingville Dam, flood routing was conducted.

This potential was investigated through the development of the probable maximum flood (PMF) for the watershed and the subsequent routing of the PMF through the reservoir system. The PMF is that hypothetical flow induced by the most critical combination of precipitation, minimum infiltration losses, and concentration of run-off at a specific location, that is considered reasonably possible for a particular drainage area.

The drainage area contributing to Conklingville Dam (Sacandaga Lake)

is approximately 1,050 square miles. Snyder and Clark coefficients were developed through watershed modeling done by the Corps to define the basic hydrologic working tools, the unit hydrograph. Using hydrometeorological Report No. 33, the PMF index rainfall was determined to be 18.0 inches for a 24 hour duration, 200 square mile basin. The percentages of the index rainfall applied to other durations were interpolated from the plot of drainage area versus percent of 24 hours, 200 square miles. The computed PMF peak flow was 268,000 CFS. After routing the PMF through the impounded storage, the peak flow was reduced to 105,000 CFS. A plot of the PMF inflow and outflow hydrographs is included in the Appendix. Assumptions made concerning the discharge-storage capacity of the dam were:

1. The reservoir pool was assumed to be at elevation 771.0' (spillway crest).
2. It was assumed that the power station and principal inlets were closed in developing a discharge rating. This condition is possible and leads to a slightly conservative analysis.
3. A weir coefficient of 3.8 was assumed accurate for the spillway. A total spillway length of 395' was used, scaling the length from construction drawings.
4. Elevation - Storage data was calculated using U.S.G.S topographic maps.
5. Hydrologic parameters developed by the Corps were assumed correct.

The ability of the Conklingville Dam to discharge the standard project flood (SPF) was also evaluated. The SPF peak flow of 141,000 CFS was routed through the impounded storage and reduced to 48,000 CFS. The SPF outflow is indicative of a pool elevation of 780.9 feet above MSL, 9.9 feet above the spillway crest. The PMF outflow of 105,000 CFS is equivalent to 15.8 feet above the spillway crest.

Summary of Flood Routing Conklingville Dam

Elevation Top of Dam = 795.0'

Elevation Crest of Spillway = 771.0'

PMF Routing

PMF Peak = 268,000 CFS

PMF After Routing through Reservoir = 105,000 CFS

Elevation of Routed PMF corresponding to 105,000 CFS - 786.8 feet above MSL

Freeboard Remaining = 8.2 feet

Spillway Surcharge = 15.8 feet

SPF Routing

SPF Peak = 141,000 CFS

SPF After Routing through Reservoir = 48,000 CFS

Elevation of routed SPF corresponding to 48,000 CFS = 780.9 feet above MSL

Freeboard Remaining = 14.1 feet

Spillway Surcharge = 9.9 feet

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability:

- a. Visual Observations: No distress, settlement, movement or erosion was noted during the inspection. In general the embankment and spillway walls appeared to be in a stable condition.
- b. Design and Construction Data: No design data was available on the structure. In addition no soils testing information was available. Some stability calculations were made on a portion of the concrete weir retaining wall.
- c. Operating Records: The dam is not operated in a way that would adversely affect the embankment stability.
- d. Post-construction Changes: There have been no post construction changes which should affect the stability of the structure.
- e. Seismic Stability: Seismic stability computations are not available. The reservoir is located in seismic zone 2. Since Conklingville Dam was constructed using a sluiced puddle core and no information is available on this material or how it was constructed a seismic stability analysis should be conducted.

SECTION 7: ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment:

- a. Safety: The Conklingville Dam does not appear to present an immediate danger to life and property.
- b. Adequacy of Information: The available information is not adequate to conduct a complete analysis of the structure. No data relative to embankment stability is available.

The information available to complete the hydrologic analysis is adequate.

The validity of available information appears to be good.

- c. Urgency: The condition of Conklingville Dam is considered to be a non-emergency situation not requiring immediate action to protect downstream development.
- d. Necessity for Future Studies: The hydraulic fill (puddle core) type construction in a moderate seismic zone, and the lack of information on construction, embankment materials and stability analysis dictate that evaluation of the embankment under seismic loading be completed in the future.

7.2 Recommendations:

1. Embankment stability analysis should be conducted.
2. The owner should continue his excellent maintenance and operating program.
3. In the future some surface maintenance to the spillway structure will be necessary.
4. Replacement of rock rip rap at the end principal spillway channel (toe of dam) should be completed to prevent progressive erosion or erosion during peak discharge periods.

APPENDIX A

GEOLOGY

Conklingville Dam and Sacandaga Lake

The bedrock in the vicinity of the Conklingville Dam is of Precambrian age. It is composed mostly of granitic gneiss. The oldest of the geotectonic cycles recognized in this belt is commonly referred to as the Grenville Orogeny. There were a number of sequences within this orogeny. Most geologists believe that the Adirondack Mountains were formed by the domical uplift of the crustal basement. But to explain the metasedimentary rocks within the region, other geologists believe that the present Adirondacks are due to an isostatic uplift of a very ancient peneplained mountain chain. This is illustrated by the fault blocks or horst and grabens of the southern Adirondacks (See cross-sections).

The Adirondacks are still mildly, seismic. This is due to both isostatic uplifting and glacial rebound. Many faults transverse through the reservoir and are easily exposed by using landsat information.

APPENDIX B
HYDROLOGIC COMPUTATIONS

SACANDAGA RESERVOIRPRECIPITATION

SPILLWAY IS LOCATED AT $73^{\circ}55'30''$
LONGITUDE AND $43^{\circ}15'$ LATITUDE.

FROM HYDROMETEOROLOGICAL REPORT #33
 $PMP = 18''$

DEPTH - AREA RELATIONSHIPS

6 HR - 50%

12 HR - 68%

24 HR - 77%

48 HR - 86%

FROM DRAFT EM 1110-2-1411

$SP5 = 9''$

DEPTH - AREA RELATIONSHIP

24 HR - 82%

$9''(.82) = 7.38''$

DRAINAGE AREA

AREA = 1050 SQ. MI.

SACANDAGA RESERVOIRELEVATION - STORAGE RELATIONSHIP

ELEV FT.	SURFACE AREA ACRES	Δ ELEV FT.	TOTAL STORAGE AC - FT
771	25,178		0
		1.0	
772	25,381		25,280
		1.0	
773	25,583		50,762
		1.0	
774	25,786		76,446
		1.0	
775	25,989		102,334
		1.0	
776	26,191		129,424
		1.0	
777	26,394		154,716
		1.0	
778	26,597		181,212
		1.0	
779	26,799		207,910
		1.0	
780	27,002		234,810
		1.0	
781	27,122		261,872
		1.0	
782	27,241		289,054
		1.0	
783	27,361		316,354
		1.0	
784	27,482		343,775
		1.0	
785	27,600		371,315
		1.0	
786	27,719		399,974

1122

L. ROBERT KIMBALL

SUBJECT

BY

DATE

Consulting Engineers

SHEET NO.

OF

JOB NO.

SACANDAGA RESERVOIR

ELEVATION - STORAGE RELATIONSHIP

ELEV FT	SURFACE AREA ACRES	Δ ELEV FT	TOTAL STORAGE AC - FT
		1.0	
737	27,839		426,754
		1.0	
738	27,958		454,652
		1.0	
739	28,078		482,670
		1.0	
740	28,198		510,808
		1.0	
741	28,317		539,066
		1.0	
742	28,437		567,442
		1.0	
743	28,556		595,939
		1.0	
744	28,676		624,555
		1.0	
745	28,795		653,290
		1.0	
746	28,915		682,146
		1.0	
747	29,034		711,120
		1.0	
748	29,154		740,214
		1.0	
749	29,273		769,428
		1.0	
800	29,393		798,760

L. ROBERT KIMBALL
Consulting Engineers

SUBJECT

BY

DATE

SHEET NO.

OF

JOB NO.

SACANDAGA RESERVOIR

ELEVATION - DISCHARGE RELATIONSHIP
(IGNORING PRINCIPLE SPILLWAY AND POWERHOUSE FLOW)

ELEV. FT	EMERGENCY SPILLWAY		SIDEWALL SPILLWAY		TOTAL DISCHARGE
	H FT	Q CFS	H FT	Q CFS	Q CFS
771	0	0			0 ✓
772	1.0	1500			1500
773	2.0	4245	0	0	4245
774	3.0	7800	1.0	140	7940 ✓
775	4.0	12,010	2.0	390	12,400
776	5.0	16,780	3.0	710	17,490
777	6.0	22,040	4.0	1090	23,130
778	7.0	27,500	5.0	1530	29,030
779	8.0	33,940	6.0	2,010	35,950
780	9.0	40,530	7.0	2,530	43,060
781	10.0	47,470	8.0	3,100	50,570
782	11.0	54,760	9.0	3,690	58,450
783	12.0	62,400	10.0	12,320	74,720 ✓
784	13.0	70,360	11.0	12,430	82,790
785	14.0	78,630	12.0	12,530	91,160
786	15.0	87,200	13.0	12,640	99,840

L. ROBERT KIMBALL
Consulting Engineers

SUBJECT

BY DATE

SHEET NO OF

JOB NO.

SACANDAGA RESERVOIR

ELEVATION - DISCHARGE RELATIONSHIP

ELEV FT	EMERGENCY SPILLWAY	SIGNAL SPILLWAY		OVERTOP		TOTAL
	H FT	Q CFS	H FT	Q CFS	Q CFS	Q CFS
797	16.0	96,060	14.0	12,740		108,800
798	17.0	105,210	15.0	12,840		118,050
799	18.0	113,630	16.0	12,940		127,570
790	19.0	124,310	17.0	13,040		137,350
791	20.0	134,250	18.0	13,140		147,390
792	21.0	144,450	19.0	13,240		157,690
793	22.0	154,890	20.0	13,340		168,230
794	23.0	165,570	21.0	13,440		179,010
795	24.0	176,490	22.0	13,540	0	190,030
796	25.0	187,630	23.0	13,630	3080	204,340
797	26.0	199,990	24.0	13,730	8710	224,730
798	27.0	210,580	25.0	13,820	16,000	240,400
799	28.0	222,390	26.0	13,920	24,640	260,950
790	29.0	234,410	27.0	14,010	34,440	282,860

L. ROBERT KIMBALL
Consulting Engineers

SUBJECT _____

BY _____ DATE _____

SHEET NO. _____ OF _____

JOB NO. _____

SACANDAGA RESERVOIR
ELEVATION - DISCHARGE RELATIONSHIPS

EMERGENCY SPILLWAY:

$$Q = CLH^{3/2}$$

$$C = 3.8$$

$$L = 355'$$

SIPHON SPILLWAYS:

TO ELEV 782'

$$Q = CLH^{3/2}$$

$$C = 3.8$$

$$L = 36'$$

AFTER ELEV 782'

$$Q = C B D \sqrt{2g H}$$

$$C = 0.70$$

$$B = 36'$$

$$D = 8'$$

$$H = 43' + H$$


VERTICAL:

$$Q = CLH^{3/2}$$


$$C = 3.8$$


$$L = 1100'$$

SANDHILL RESERVOIR
ELEVATION VS STORAGE



STORAGE - AC-FT





6.4 Upper Hudson Basin to Confluence with Sacandaga River

The Upper Hudson River to the Sacandaga River confluence drains an area of 2722 square miles. This area is sparsely populated; the only city in the area is Warrensburg. Major tributaries to the Hudson include Cedar River, Indian River, Schroon River and Sacandaga River. Two reservoirs, Indian Lake and Great Sacandaga Lake, lie in the basin also. Numerous natural lakes dot the area, the largest being Schroon and Brant Lakes, both in the Schroon River Subbasin.

The Upper Hudson Basin was divided into 15 subbasins (Figure 6.16) and connected as shown in the schematic in Figure 6.17. Gauges on the main stem of the Hudson are at Newcomb, Gooley, North Creek and Hadley, and tributary gauges include the Cedar River below Chain Lakes, the East Branch of the Sacandaga River at Griffin, the Schroon River at Riverbank, and the Sacandaga River near Hope. The remaining two gauges lie just below the outlets of the two reservoirs.

Tables 6.20 through 6.22 present the subbasin characteristics while Table 6.23 presents the routing parameters. Tables 6.24 and 6.25 give the data for Indian Lake and Great Sacandaga Lake.

Tables 6.26 and 6.28 present the results of the simulation runs. Figures 6.18 through 6.29 show the comparisons of computed and observed hydrographs for the two historic events. Lastly, Table 6.29 shows the SPF hydrographs at key locations in the basin.





Figure 6.11: Subdivision of Upper Hudson Basin to Confluence with Sacandaga River



Key



Subbasin



Reservoir/Lake



Routing Reach



Node

Figure 6.17

Schematic of Hudson Basin to Confluence With
Sacandaga River

The observed and computed hydrographs for this basin showed good agreement except for the shape of the hydrographs for the 1948 event at Riverbank on the Schroon River (Figure 6.22) and the 1972 event at Newcomb on the Hudson River (Figure 6.26). The response of the Schroon Basin appears to be damped significantly by natural lake storage. However, in view of the lack of detailed data on this basin it was impossible to determine a better structure to model this basin. The response of the Hudson River above Newcomb is quite different for the 1948 and 1972 events (Figures 6.18 and 6.26). Attempts to find unit hydrograph parameters that would accurately reproduce both events proved unsuccessful.

The effect of Schroon, Brant, Loon, and Friends Lakes is to delay and attenuate the runoff from the Schroon Basin. This is apparent from the SPF and Transposed Agnes events as well as a review of the historic record at Riverbank, USGS Gauge 3170 which shows much lower peak discharges/area ratios than the rest of the Upper Hudson Basin. Sacandaga Reservoir also has a major effect on the runoff from the Sacandaga River Basin, significantly reducing the peak flows even though the initial stage was at the spillway elevation.

The Transposed Agnes event had higher discharges than the SPF event in the Upper Hudson Basin except for the upper Sacandaga River Basin. A comparison of the SPF and Transposed Agnes results versus maximum recorded peaks for the entire Upper Hudson Basin is presented in Section 6.6.

Table 6.21
UPPER HUDSON BASIN TO CONFLUENCE WITH SACANDAGA RIVER
SUBBASIN 3-HOUR UNIT HYDROGRAPHS

Time (hrs)	36	37	38	39	40	41	242	142	42	43	44	45
3	214	200	163	417	149	360	296	370	441	536	392	313
6	793	738	597	1488	548	1306	1063	1360	1564	1925	1397	1129
9	1591	1479	1156	2834	1074	2548	2034	2701	2921	3715	2648	2175
12	2460	2260	1610	3921	1526	3730	2813	4130	3932	5410	3632	3056
15	3187	2874	1768	4332	1734	4476	3093	5494	4072	6470	3956	3445
18	3603	3179	1605	3878	1632	4580	2757	6338	3378	6611	3470	3173
21	3627	3079	1322	2969	1381	4000	2141	6623	2416	5720	2608	2535
24	3292	2718	1089	2203	1164	3173	1644	6191	1725	4396	1919	1962
27	2872	2359	898	1535	982	2516	1263	5313	1232	3347	1412	1518
30	2505	2048	739	1213	828	1996	970	4484	879	2548	1039	1175
33	2186	1777	609	900	699	1583	745	3784	628	1940	765	909
36	1907	1543	502	668	589	1255	572	3193	448	1477	563	704
39	1664	1339	413	496	497	996	439	2695	320	1124	414	545
42	1451	1162	341	368	419	790	337	2274	229	856	305	422
45	1265	1009	281	273	354	626	259	1919	163	652	224	326
48	1105	876	231	203	298	497	199	1620	117	496	165	253
51	964	760	190	150	251	394	153	1367	83	378	121	195
54	841	660	157	112	212	312	117	1153	59	288	89	151
57	733	573	129	83	179	248	90	973	42	219	66	117
60	640	497	106	61	151	197	69	821	167	167	48	91
63	558	432	88	45	127	156	53	693	127	127	36	70
66	487	375	72		107	124	41	585	97	97	54	42
69	425	325	60		91	98	31	417	74	74		
72	371	282	49		76	78		352				
75	323	245	40		64	62		297				
78	282	213	33		54	49		250				
81	246	185	27		46	39		211				
84	215	160	23		39			178				
87	187	139	19		33			151				
90	163	121	15		27			127				
93	143	105			23			107				
96	124	91			20			90				
99	103	79			16			76				
102	95	69			14			64				
105	83	59						54				
108	72	52										
111	63	45										
114	55	39										
117	48	34										
120	42	29										
123	36	25										
126	32											
129	28											

All flows in cfs/unit rainfall

Table 6.21
UPPER HUDSON BASIN TO CONFLUENCE WITH SACANDAGA RIVER
SUBBASIN 3-HOUR UNIT HYDROGRAPHS

Time (hrs)	36	37	38	39	40	41	242	142	42	43	44	45
3	214	200	163	417	149	360	296	370	441	536	392	313
6	793	738	597	1488	548	1306	1063	1360	1564	1925	1397	1129
9	1591	1479	1156	2834	1074	2548	2034	2701	2921	3715	2648	2175
12	2460	2260	1610	3921	1526	3730	2813	4130	3932	5410	3632	3056
15	3187	2874	1768	4332	1734	4476	3093	5494	4072	6470	3956	3445
18	3603	3179	1605	3878	1632	4580	2757	6338	3378	6611	3470	3173
21	3627	3079	1322	2969	1381	4000	2141	6623	2416	5720	2608	2535
24	3292	2718	1089	2203	1164	3173	1644	6191	1725	4396	1919	1962
27	2872	2359	898	1535	982	2516	1263	5313	1232	3347	1412	1518
30	2505	2048	739	1213	828	1996	970	4484	879	2548	1039	1175
33	2186	1777	609	900	699	1583	745	3784	628	1940	765	909
36	1907	1543	502	668	589	1255	572	3193	448	1477	563	704
39	1664	1339	413	496	497	996	439	2695	320	1124	414	545
42	1451	1162	341	368	419	790	337	2274	229	856	305	422
45	1265	1009	281	273	354	626	259	1919	163	652	224	326
48	1105	876	231	203	298	497	199	1620	117	496	165	253
51	964	760	190	150	251	394	153	1367	83	378	121	195
54	841	660	157	112	212	312	117	1153	59	288	89	151
57	733	573	129	83	179	248	90	973	42	219	66	117
60	640	497	106	61	151	197	69	821	167	167	48	91
63	558	432	88	45	127	156	53	693	127	127	36	70
66	487	375	72		107	124	41	585	97	97	54	42
69	425	325	60		91	98	31	417	74	74		
72	371	282	49		76	78		352				
75	323	245	40		64	62		297				
78	282	213	33		54	49		250				
81	246	185	27		46	39		211				
84	215	160	23		39			178				
87	187	139	19		33			151				
90	163	121	15		27			127				
93	143	105			23			107				
96	124	91			20			90				
99	103	79			16			76				
102	95	69			14			64				
105	83	59						54				
108	72	52										
111	63	45										
114	55	39										
117	48	34										
120	42	29										
123	36	25										
126	32											
129	28											

All flows in cfs/unit rainfall

Table 6.21 (Cont'd)

Time (hrs)	45	47	48
3	268	693	99
6	998	2527	223
9	2016	4970	179
12	3185	7638	80
15	4358	10129	36
18	5304	11876	16
21	5893	12631	7
24	6378	12328	3
27	5742	10799	
30	5132	8811	
33	4574	7183	
36	4077	5855	
39	3634	4773	
42	3239	3891	
45	2887	3171	
48	2573	2565	
51	2293	2107	
54	2044	1718	
57	1822	1400	
60	1624	1141	
63	1447	930	
66	1290	758	
69	1150	618	
72	1025	504	
75	913	411	
78	814	335	
81	726	273	
84	647	223	
87	576	181	
90	514	148	
93	458	121	
96	408		
99	364		
102	324		
105	289		
108	258		
111	230		
114	205		
117	182		
120	163		
123	145		

All flows in cfs/unit rainfall

TABLE 6.22
UPPER HUDSON RIVER TO CONFLUENCE WITH SACANDAGA RIVER
INITIAL FLOW AND INFILTRATION PARAMETERS

Subbasin No.	December, 1948			June, 1972			SPS and Transposed Agnes		
	Initial Flow (cfs)	Initial Loss (in)	Constant Loss (in/hr)	Initial Flow (cfs)	Initial Loss (in)	Constant Loss (in/hr)	Initial Flow (cfs)	Initial Loss (in)	Constant Loss (in/hr)
36	102	.50	.03	755	.20	.07	340	1.0	.075
37	123	.50	.03	270	.10	.06	270	1.0	.075
38	35	.50	.04	95	.20	.06	95	1.0	.075
39	75	1.00	.03	240	.10	.06	240	1.0	.075
40	35	.50	.03	110	.10	.06	110	1.0	.075
41	100	.50	.03	290	.20	.15	290	1.0	.075
242	54	2.50	.05	152	1.00	.15	152	2.0	.075
142	220	2.50	.04	600	.50	.10	600	2.0	.075
42	65	2.50	.05	180	1.00	.10	180	2.0	.075
43	150	1.00	.07	400	.20	.15	400	1.0	.075
44	70	1.00	.07	185	.20	.12	185	1.0	.075
45	50	1.00	.02	180	.10	.035	180	1.0	.075
46	230	.80	.02	745	1.30	.04	745	1.0	.075
47	445	.80	.04	1200	.80	.04	1200	1.0	.075
48	3	1.00	.05	5	.50	.06	5	1.0	.075

Table 6.23
UPPER HUDSON RIVER TO CONFLUENCE WITH SACANDAGA RIVER
ROUTING REACH CHARACTERISTICS

Reach No.	Length (mi)	Slope (ft/mi)	Muskingum Parameters		
			NSTEPS	K (hrs.)	X (-)
1036-1038	10.2	10.6	3	1.3	.3
1037-1038	4.0	25.5	1	1.0	.3
1038-1040		**	DUMMY LINK	**	
1039-1040	6.6	27.1	1	1.6	.3
1040-1041	17.0	25.3	2	2.1	.2
1041-1043	21.4	18.2	3	2.1	.2
1142-1042	11.1	9.6	3	1.5	.1
1042-1043	16.3	6.1	5	1.6	.3
1043-1044	13.5	3.0	6	1.6	.2
1044-1048		**	DUMMY LINK	**	
1045-1046	11.5	31.8	2	1.3	.3
1046-1147	8.5	13.0	2	1.5	.3
1147-1047	Great Sacandaga Lake (reservoir routing)				
1047-1048		**	DUMMY LINK	**	

Table 6.24
INDIAN LAKE
Storage-Discharge Relationship

<u>Elevation</u> (ft. above MSL)	<u>Storage</u> (acre-ft)	<u>Discharge</u> (cfs)
1651.3	106560	0
1653	114350	700
1654	118250	1440
1655	123060	2340
1656	128100	3370
1657	134060	4525
1658	138460	5785
1661.3	153045	10000

Initial Storage Level
(acre-ft)

December 1948	(not simulated)
June 1972	(not simulated)
SPF and Transposed Agnes	106560

Table 6.25
GREAT SACANDAGA LAKE
Storage-Discharge Relationship

<u>Elevation</u> (ft. above MSL)	<u>Storage</u> (acre-ft)	<u>Discharge</u> (cfs)
745	267208	6358
749.3	352375	6680
758	435941	7275
767	655418	7848
769	707300	7970
770	733700	8029
771.2	765610	8220
773	814279	11971
774	841598	23187
778	941230	41164
781.1	1017912	55000

Initial Storage Level
(acre-ft)

December 1948	(not simulated)
June 1972	733700
SPF and Transposed Agnes	760302

Table 5.26

UPPER HUDSON BASIN TO CONFLUENCE WITH SACANDAGA RIVER
SUBBASIN RAINFALL AND PEAK FLOWS

Subbasin	December, 1948			June, 1972			SPF		Transposed Agnes		
	Rainfall (in)	Excess	Peak Flow (cfs)	Rainfall (in)	Excess	Peak Flow (cfs)	Total	Rainfall (in)	Total	Excess	Peak Flow (cfs)
36	4.78	2.59	7157	3.22	1.10	2825	11.8	11.8	13.1	10.3	32082
37	5.44	3.23	6663	2.80	1.02	2367	12.0	12.0	12.6	9.3	22979
38	4.91	2.31	2561	3.29	1.49	1806	12.6	12.6	13.5	10.2	12315
39	5.02	2.62	5784	3.72	1.57	3191	12.1	12.1	12.1	9.0	26033
40	5.60	3.40	3646	2.53	1.04	1307	12.6	12.6	13.5	10.2	12451
41	5.60	3.36	9576	3.13	0.81	2921	11.9	11.9	14.0	10.5	36588
242	4.98	1.36	3399	3.08	0.83	2178	12.4	12.4	14.4	10.5	23460
142	4.83	1.39	8302	2.84	0.59	2106	11.3	11.3	11.6	7.9	43826
42	5.70	1.81	4925	3.00	0.30	1585	12.2	12.2	12.7	8.9	25830
43	7.36	2.98	12679	3.35	0.42	2463	11.7	11.7	13.9	10.7	51898
44	7.50	3.18	7662	3.58	1.02	2298	12.2	12.2	14.6	11.5	30357
45	7.14	5.02	9153	3.55	1.85	3128	12.2	12.2	14.5	11.4	27056
46	5.51	3.76	14561	4.99	2.55	8530	11.2	11.2	11.4	6.9	30092
47	6.83	4.11	32431	4.10	2.16	12858	10.8	10.8	12.0	9.2	93639
48	7.50	4.03	434	3.98	2.25	220	13.6	13.6	14.8	11.6	1252

Table 6.27
UPPER HUDSON RIVER TO CONFLUENCE WITH SACANDAGA RIVER
SIMULATED PEAK FLOWS AT CONTROL POINTS
(All Flows in cfs)

Control Point	Description	December 1948	June 1972	SPF	Transposed Agnes	Drainage Area (mi ²)
1036	Hudson R. at Newcomb USGS 3120	7157	2825	29883	32082	192
1037	Cedar R. below Chain Lakes USGS 3135	6663	2367	26307	22979	160
1038	Hudson R. at Gooley USGS 3140	15922	6524	59916	65224	419
1039	Indian R. below Indian Lake Dam USGS 3150	453R	1884R	9272	8983	132
1040	Hudson R. below Indian R.	19480	9489	72808	83664	623
1041	Hudson R. at North Creek USGS 3155	27562	11867	93217	110792	792
1142	Schroon R. below Trout Br.	5023	2926	27807	30284	412
1042	Schroon R. at Riverbank USGS 3170	6592	3187	33426	38480	527
1043	Hudson R. below Schroon R.	40768	16503	129779	173149	1546
1044	Hudson R. at Hadley USGS 3185	42256	17131	128420	175978	1664
1045	E. Br. Sacandaga R. at Griffin USGS 3190	9153	3128	28632	27056	114
1046	Sacandaga R. near Hope USGS 3210	23504	10220	66646	48928	491
1147	Total Inflow Into Sacandaga Reservoir	55543	23026	146398	139307	1055
1047	Sacandaga R. below Conklingville Dam, USGS 3250	5130R	9353	44739	52441	1055
1048	Hudson R. below Sacandaga R.	42344	26209	154540	225877	2722

R = Assumed Regulated Discharge

Table 6.28
UPPER HUDSON BASIN TO CONFLUENCE WITH SACANDAGA RIVER
COMPARISONS OF OBSERVED VS COMPUTED HYDROGRAPHS*

Gauge No. RAI	USGS	Gauge Name	December 1948			June 1972		
			Peak (cfs)	Volume (acre-ft)	Timing (hrs)	Peak (cfs)	Volume (acre-ft)	Timing (hrs)
1035	3120	Hudson R. near Newcomb	Computed Observed Difference	7157 7430 -3.7%	31/23 32/8 -9	2825 2279 +24.0%	14757 21252 -30.6%	24/10 25/10 -24
1037	3135	Cedar River below Chain Lakes	Computed Observed Difference	6663 7360 -9.5%	31/23 31/23 0	(Gauge not active)		
1038	3140	Hudson R. at Gooley	Computed Observed Difference	15922 15000 +6.1%	32/1 32/6 -5	(Gauge not active)		
1041	3155	Hudson R. at North Creek	Computed Observed Difference	27562 28900 -4.6%	32/1 31/20 +5	(Gauge not active)		
1042	3170	Schroon R. at Riverbank	Computed Observed Difference	6592 6780 -2.8%	32/4 33/9 -29	(Gauge not active)		
1044	3185	Hudson R. at Hadley	Computed Observed Difference	42256 42700 -1.0%	32/13 32/2 +11	17131 14805 +15.7%	102861 121016 -15.0%	25/2 25/0 +2
1045	3190	E. Br. Sacandaga R. at Griffin	Computed Observed Difference	9153 10700 -14.5%	31/20 31/16 +4	3128 3140 -0.4%	13786 17966 -23.3%	24/5 24/12 -7
1046	3210	Sacandaga R. near Hope	Computer Observed Difference	23504 31100 -24.4%	32/0 31/17 +7	10220 11400 -10.4%	67401 78705 -14.4%	24/9 24/4 +5

*Gauges immediately below reservoirs not included.

Table 6.29
SPF HYDROGRAPHS FOR UPPER HUDSON BASIN TO CONFLUENCE WITH SACANDAGA RIVER
AT CONTROL POINT 1038 HUDSON R. AT GOOLEY, USGS 3140

687.	683.	675.	665.	653.	638.	623.	607.	592.	576.
562.	547.	533.	519.	506.	493.	480.	467.	455.	443.
432.	421.	410.	399.	389.	379.	369.	359.	350.	341.
332.	324.	315.	307.	299.	291.	284.	277.	272.	264.
329.	415.	540.	703.	900.	1126.	1374.	1635.	1898.	2158.
2407.	2636.	2840.	3009.	3145.	3260.	3363.	3457.	3562.	3670.
3333.	4108.	4592.	5449.	6874.	8953.	11083.	15016.	18868.	23126.
27653.	32324.	35959.	41442.	45635.	49408.	52664.	55315.	57322.	58732.
59593.	59916.	59697.	58932.	57698.	56102.	51220.	52139.	49954.	47750.
45587.	43500.	41502.	39598.	37786.	36062.	34421.	32860.	31372.	29955.
28602.	27339.	26071.	24886.	23758.	22678.	21643.	20652.	19702.	18793.
17924.	17092.	16298.	15540.	14817.	14128.	13471.	12845.	12249.	11680.
11136.	10822.	10133.	9679.	9246.	8833.	8442.	8075.	7723.	7389.
7067.	6750.	6469.	6203.	5958.	5725.	5505.	5304.	5125.	4964.
4813.	4668.	4532.	4406.	4288.	4176.	4067.	3961.	3858.	3758.

AT CONTROL POINT 1041 HUDSON R. AT NORTH CREEK, USGS 3155

1078.	1071.	1063.	1055.	1044.	1032.	1017.	1000.	982.	962.
942.	921.	900.	879.	858.	838.	818.	798.	779.	761.
743.	725.	708.	691.	675.	659.	644.	629.	614.	600.
587.	573.	560.	548.	535.	523.	511.	500.	492.	506.
560.	552.	780.	947.	1156.	1407.	1699.	2028.	2385.	2752.
3116.	3460.	3794.	4092.	4356.	4586.	4777.	4926.	5057.	5201.
5418.	5801.	6452.	7596.	9424.	11973.	15262.	19296.	24084.	29600.
35766.	42446.	49439.	56504.	63412.	69976.	76026.	81391.	85887.	89365.
91727.	92941.	93217.	92942.	91965.	90660.	88946.	86968.	84475.	81826.
78936.	76026.	73612.	70003.	67042.	64161.	61379.	58706.	56144.	53694.
51355.	49121.	46938.	44951.	43001.	41131.	39342.	37635.	36004.	34447.
32952.	31537.	30179.	28983.	27645.	26534.	25500.	24510.	23560.	22671.
21613.	20991.	20203.	19449.	18729.	18043.	17390.	16769.	16181.	15628.
15107.	14616.	14146.	13701.	13277.	12875.	12497.	12141.	11804.	11487.
11190.	10912.	10651.	10404.	10170.	9945.	9730.	9522.	9321.	9126.

Table 6.29 (Cont'd)
AT CONTROL POINT 1044 HUDSON R. AT HADLEY, USGS 3185

2556.	2551.	2547.	2542.	2538.	2533.	2529.	2523.	2517.	2509.
2506.	2489.	2477.	2464.	2459.	2434.	2418.	2394.	2379.	2357.
2334.	2309.	2282.	2254.	2224.	2193.	2161.	2129.	2096.	2063.
2029.	1998.	1963.	1931.	1898.	1867.	1835.	1804.	1775.	1767.
1794.	1847.	1917.	1997.	2006.	2185.	2296.	2415.	2537.	2659.
2784.	2911.	3042.	3174.	3316.	3482.	3671.	3878.	4102.	4375.
4781.	5398.	6091.	7288.	9015.	11194.	13704.	16443.	19380.	22434.
25654.	26884.	32354.	35768.	39203.	42605.	46141.	49634.	53141.	56727.
60601.	64929.	69745.	74999.	80584.	86377.	92235.	98010.	103556.	108738.
113448.	117600.	121132.	123997.	126166.	127622.	128366.	128420.	127819.	126016.
129808.	122659.	120055.	117131.	113970.	110681.	107236.	103772.	100338.	96919.
93545.	90241.	87025.	83911.	80909.	78027.	75270.	72642.	70143.	67772.
55521.	53353.	51349.	59411.	57552.	55799.	54116.	52511.	50980.	49520.
48128.	46600.	45532.	44320.	43160.	42049.	40981.	39956.	38969.	38018.
37103.	36220.	35370.	34550.	33750.	32999.	32265.	31568.	30877.	30220.

AT CONTROL POINT 1047 SACANDAGA R. BELOW CONKLINGVILLE DAM, USGS 3250

8165.	8142.	8179.	8176.	8173.	8170.	8167.	8164.	8160.	8157.
8154.	8151.	8148.	8144.	8141.	8138.	8134.	8131.	8128.	8125.
8121.	8118.	8114.	8111.	8108.	8104.	8101.	8098.	8094.	8091.
8087.	8084.	8081.	8077.	8074.	8070.	8067.	8063.	8060.	8057.
8053.	8050.	8047.	8043.	8041.	8038.	8035.	8033.	8031.	8029.
8026.	8023.	8020.	8017.	8014.	8011.	8007.	8004.	8001.	7998.
7995.	7992.	7989.	7986.	7983.	7980.	7977.	7974.	7971.	7968.
7965.	7962.	7959.	7956.	7953.	7950.	7947.	7944.	7941.	7938.
7935.	7932.	7929.	7926.	7923.	7920.	7917.	7914.	7911.	7908.
7905.	7902.	7899.	7896.	7893.	7890.	7887.	7884.	7881.	7878.
7875.	7872.	7869.	7866.	7863.	7860.	7857.	7854.	7851.	7848.
7845.	7842.	7839.	7836.	7833.	7830.	7827.	7824.	7821.	7818.
7815.	7812.	7809.	7806.	7803.	7800.	7797.	7794.	7791.	7788.
7785.	7782.	7779.	7776.	7773.	7770.	7767.	7764.	7761.	7758.
7755.	7752.	7749.	7746.	7743.	7740.	7737.	7734.	7731.	7728.
7725.	7722.	7719.	7716.	7713.	7710.	7707.	7704.	7701.	7698.
7695.	7692.	7689.	7686.	7683.	7680.	7677.	7674.	7671.	7668.
7665.	7662.	7659.	7656.	7653.	7650.	7647.	7644.	7641.	7638.
7635.	7632.	7629.	7626.	7623.	7620.	7617.	7614.	7611.	7608.
7605.	7602.	7599.	7596.	7593.	7590.	7587.	7584.	7581.	7578.
7575.	7572.	7569.	7566.	7563.	7560.	7557.	7554.	7551.	7548.
7545.	7542.	7539.	7536.	7533.	7530.	7527.	7524.	7521.	7518.
7515.	7512.	7509.	7506.	7503.	7500.	7497.	7494.	7491.	7488.
7485.	7482.	7479.	7476.	7473.	7470.	7467.	7464.	7461.	7458.
7455.	7452.	7449.	7446.	7443.	7440.	7437.	7434.	7431.	7428.
7425.	7422.	7419.	7416.	7413.	7410.	7407.	7404.	7401.	7398.
7395.	7392.	7389.	7386.	7383.	7380.	7377.	7374.	7371.	7368.
7365.	7362.	7359.	7356.	7353.	7350.	7347.	7344.	7341.	7338.
7335.	7332.	7329.	7326.	7323.	7320.	7317.	7314.	7311.	7308.
7305.	7302.	7299.	7296.	7293.	7290.	7287.	7284.	7281.	7278.
7275.	7272.	7269.	7266.	7263.	7260.	7257.	7254.	7251.	7248.
7245.	7242.	7239.	7236.	7233.	7230.	7227.	7224.	7221.	7218.
7215.	7212.	7209.	7206.	7203.	7200.	7197.	7194.	7191.	7188.
7185.	7182.	7179.	7176.	7173.	7170.	7167.	7164.	7161.	7158.
7155.	7152.	7149.	7146.	7143.	7140.	7137.	7134.	7131.	7128.
7125.	7122.	7119.	7116.	7113.	7110.	7107.	7104.	7101.	7098.
7095.	7092.	7089.	7086.	7083.	7080.	7077.	7074.	7071.	7068.
7065.	7062.	7059.	7056.	7053.	7050.	7047.	7044.	7041.	7038.
7035.	7032.	7029.	7026.	7023.	7020.	7017.	7014.	7011.	7008.
7005.	7002.	6999.	6996.	6993.	6990.	6987.	6984.	6981.	6978.
6975.	6972.	6969.	6966.	6963.	6960.	6957.	6954.	6951.	6948.
6945.	6942.	6939.	6936.	6933.	6930.	6927.	6924.	6921.	6918.
6915.	6912.	6909.	6906.	6903.	6900.	6897.	6894.	6891.	6888.
6885.	6882.	6879.	6876.	6873.	6870.	6867.	6864.	6861.	6858.
6855.	6852.	6849.	6846.	6843.	6840.	6837.	6834.	6831.	6828.
6825.	6822.	6819.	6816.	6813.	6810.	6807.	6804.	6801.	6798.
6795.	6792.	6789.	6786.	6783.	6780.	6777.	6774.	6771.	6768.
6765.	6762.	6759.	6756.	6753.	6750.	6747.	6744.	6741.	6738.
6735.	6732.	6729.	6726.	6723.	6720.	6717.	6714.	6711.	6708.
6705.	6702.	6699.	6696.	6693.	6690.	6687.	6684.	6681.	6678.
6675.	6672.	6669.	6666.	6663.	6660.	6657.	6654.	6651.	6648.
6645.	6642.	6639.	6636.	6633.	6630.	6627.	6624.	6621.	6618.
6615.	6612.	6609.	6606.	6603.	6600.	6597.	6594.	6591.	6588.
6585.	6582.	6579.	6576.	6573.	6570.	6567.	6564.	6561.	6558.
6555.	6552.	6549.	6546.	6543.	6540.	6537.	6534.	6531.	6528.
6525.	6522.	6519.	6516.	6513.	6510.	6507.	6504.	6501.	6498.
6495.	6492.	6489.	6486.	6483.	6480.	6477.	6474.	6471.	6468.
6465.	6462.	6459.	6456.	6453.	6450.	6447.	6444.	6441.	6438.
6435.	6432.	6429.	6426.	6423.	6420.	6417.	6414.	6411.	6408.
6405.	6402.	6399.	6396.	6393.	6390.	6387.	6384.	6381.	6378.
6375.	6372.	6369.	6366.	6363.	6360.	6357.	6354.	6351.	6348.
6345.	6342.	6339.	6336.	6333.	6330.	6327.	6324.	6321.	6318.
6315.	6312.	6309.	6306.	6303.	6300.	6297.	6294.	6291.	6288.
6285.	6282.	6279.	6276.	6273.	6270.	6267.	6264.	6261.	6258.
6255.	6252.	6249.	6246.	6243.	6240.	6237.	6234.	6231.	6228.
6225.	6222.	6219.	6216.	6213.	6210.	6207.	6204.	6201.	6198.
6195.	6192.	6189.	6186.	6183.	6180.	6177.	6174.	6171.	6168.
6165.	6162.	6159.	6156.	6153.	6150.	6147.	6144.	6141.	6138.
6135.	6132.	6129.	6126.	6123.	6120.	6117.	6114.	6111.	6108.
6105.	6102.	6099.	6096.	6093.	6090.	6087.	6084.	6081.	6078.
6075.	6072.	6069.	6066.	6063.	6060.	6057.	6054.	6051.	6048.
6045.	6042.	6039.	6036.	6033.	6030.	6027.	6024.	6021.	6018.
6015.	6012.	6009.	6006.	6003.	6000.	5997.	5994.	5991.	5988.
5985.	5982.	5979.	5976.	5973.	5970.	5967.	5964.	5961.	5958.
5955.	5952.	5949.	5946.	5943.	5940.	5937.	5934.	5931.	5928.
5925.	5922.	5919.	5916.	5913.	5910.	5907.	5904.	5901.	5898.
5895.	5892.	5889.	5886.	5883.	5880.	5877.	5874.	5871.	5868.
5865.	5862.	5859.	5856.	5853.	5850.	5847.	5844.	5841.	5838.
5835.	5832.	5829.	5826.	5823.	5820.	5817.	5814.	5811.	5808.
5805.	5802.	5799.	5796.	5793.	5790.	5787.	5784.	5781.	5778.
5775.	5772.	5769.	5766.	5763.	5760.	5757.	5754.	5751.	5748.
5745.	5742.	5739.	5736.	5733.	5730.	5727.	5724.	5721.	5718.
5715.	5712.	5709.	5706.	5703.	5700.	5697.	5694.	5691.	5688.
5685.	5682.	5679.	5676.	5673.	5670.	5667.	5664.	5661.	5658.
5655.	5652.	5649.	5646.	5643.	5640.	5637.	5634.	5631.	5628.
5625.	5622.	5619.	5616.	5613.	5610.	5607.	5604.	5601.	5598.
5595.	5592.	5589.	5586.	5583.	5580.	5577.	5574.	5571.	5568.
5565.	5562.	5559.	5556.	5553.	5550.	5547.	5544.	5541.	5538.
5535.	5532.	5529.	5526.	5523.	5520.	5517.	5514.	5511.	5508.
5505.	5502.	5499.	5496.	5493.	5490.	5487.	5484.	5481.	5478.
5475.	5472.	5469.	5466.	5463.	5460.	5457.	5454.	5451.	5448.
5445.	5442.	5439.	5436.	5433.	5430.	5427.	5424.	5421.	5418.
5415.	5412.	5409.	5406.	5403.	5400.	5397.	5394.	5391.	5388.
5385.	5382.	5379.	5376.	5373.	5370.	5367.	5364.	5361.	5358.
5355.	5352.	5349.	5346.	5343.	5340.	5337.	5334.	5331.	5328.
5325.	5322.	5319.	5316.	5313.	5310.	5307.	5304.	5301.	5298.
5295.	5292.	5289.	5286.	5283.	5280.	5277.	5274.	5271.	5268.
5265.	5262.	5259.	5256.	5253.	5250.	5247.	5244.	5241.	5238.
5235.	5232.	5229.	5226.	5223.	5220.	5217.	5214.	5211.	5208.
5205.	5202.	5199.	5196.	5193.	5190.	5187.	5184.	5181.	5178.
5175.	5172.	5169.	5166.	5163.	5160.	5157.	5154.	5151.	5148.
5145.	5142.	5139.	5136.	5133.	5130.	5127.	5124.	5121.	5118.
5115.	5112.	5109.	5106.	5103.	5100.	5097.	5094.	5091.	5088.
5085.	5082.	5079.	5076.	5073.	5070.	5067.	5064.	5061.	5058.
5055.	5052.	5049.	5046.	5043.	5040.	5037.	5034.	5031.	5028.
5025.	5022.	5019.	5016.	5013.	5010.	5007.	5004.	5001.	4998.
4995.	4992.	4989.	4986.	4983.	4980.	4977.	4974.	4971.	4968.
4965.	4962.	4959.	4956.	4953.	4950.	4947.	4944.	4941.	4938.
4935.	4932.	4929.	4926.	4923.	4920.	4917.	4914.	4911.	4908.
4905.	4902.	4899.	4896.	4893.	4890.	4887.	4884.	4881.	4878.
4875.	4872.	4869.	4866.	4863.	4860.	4857.	4854.	4851.	4848.
4845.	4842.	4839.	4836.	4833.	4830.	4827.	4824.	4821.	4818.
4815									

Table 6.29 (Cont'd)

AT CONTROL POINT 1042 HUDSON R. BELOW SACANDAGA R.

10746.	10738.	10730.	10723.	10715.	10708.	10700.	10691.	10681.	10670.
10658.	10644.	10628.	10612.	10594.	10576.	10555.	10533.	10510.	10485.
10458.	10429.	10399.	10367.	10334.	10300.	10264.	10229.	10192.	10156.
10119.	10062.	10046.	10010.	9974.	9939.	9904.	9869.	9837.	9826.
9854.	9907.	9972.	10040.	10105.	10170.	10244.	10328.	10417.	10507.
10602.	10700.	10801.	10904.	11018.	11155.	11315.	11494.	11689.	11929.
12273.	12793.	13576.	14825.	16556.	18935.	21465.	24080.	26711.	29378.
32154.	35055.	38044.	41095.	44324.	47692.	51142.	54915.	58748.	62811.
68359.	74339.	80362.	87725.	95608.	103566.	111110.	117805.	124205.	130173.
135607.	140428.	144582.	148031.	150753.	152739.	153993.	154540.	154417.	153677.
152376.	150597.	148404.	145870.	143081.	140145.	137062.	133899.	130712.	127511.
124327.	121164.	118100.	115093.	112174.	109354.	106640.	104033.	101533.	99138.
96842.	94639.	92523.	90490.	88536.	86657.	84850.	83112.	81440.	79830.
78280.	76764.	75341.	73945.	72594.	71284.	70013.	68778.	67577.	66410.
65273.	64167.	63089.	62040.	61019.	60025.	59057.	58115.	57198.	56305.

Category	Amount	Percentage
1. General	100.00	100.00
2. Special	100.00	100.00
3. Total	200.00	200.00

1994

6-1-2000
2000-01-06
2000-01-06

24225
-02
24225

100

新報

1
TOTAL VOLUME
3017750
16.22
92593.

RECEIVED
1952
1956
95235.

RECEIVED
1952
1956
72355.

RECEIVED
1952
1956
24355.

RECEIVED
1952
1956
22350.

RECEIVED
1952
1956
AC-FT

51175

[illegible]

● ●
; ;

、
、
、
、
、

EXHIBIT A-1

2005 X

;

— 25 —

2
2
2
2

7007 Y 557

7-60

2

— 55 —

10

• X
• Y
• Z

THE UNIVERSITY OF CHICAGO

5

مجلس

200

[illegible]

10

100

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 84

2.4

553
X
X
X

— **SECRET —**

CC-0

xx, y: 55

22

5X6Y7Z8A9B

1

•

122

• 97 •

X

—

[illegible]

2000

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841

[illegible]

20.

1. **Introduction**

DOI: 10.1002/9781118619146.ch1

Fig. 6 **Effect of temperature**

1000

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

27
28
29
30
31
32
33
34
35
36

٥٥٦

● ● ● ● ●

1000

10

25

Abstract

200

● ● ● ● ●

• 8551

10

—

111
TCT

1

100

•

4

1
2
3
4

—

1
2
3
4
5

1

1
2
3
4

7

1

2

100

5
6
7
8
9
10
11
12

1994

→

0-4412

10

...

1. The following are the names of the people who were present at the meeting:

2

2

100

— 108 —

INFLUENCE OF COTTON ON SUBSIDIZED RICE

[illegible]

23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

10

ADJN*

SUB-AREA KUNOFF COMPUTATION

SUBAREA 46

| ISTAD | ICOMP | IECCO | ITYPE | JPTI | JPRI | INAME |
|-------|-------|-------|-------|------|------|-------|
| 2 | 0 | 0 | 0 | 0 | 0 | 1 |

HYDROGRAPH DATA

| IMHGS | IMH9 | IMH6 | IMH3 | IMH0 | IRSPC | KATIO | ISLOD | IRAME | ECOCAL |
|-------|------|--------|------|---------|-------|-------|-------|-------|--------|
| 1 | 0 | 377.00 | 0.0 | 1055.00 | 0.0 | 0.0 | 0 | 0 | 0 |

PRECIP DATA

| SPRE | PMS | K2 | K24 | K48 | K72 | K96 |
|------|-------|-------|-------|-------|-------|------|
| 0.0 | 15.00 | 66.50 | 81.00 | 91.50 | 97.50 | 0.00 |

IPSEC COMPUTED BY THE PROGRAM IS 0.912

LOSS DATA

| SIRAR | DLIKR | RIUCL | URAIN | SIRSL | RTICK | SIRIL | CESL | ALSNX | RTIMP |
|-------|-------|-------|-------|-------|-------|-------|------|-------|-------|
| 0.0 | 0.0 | 1.00 | 0.0 | 0.0 | 1.00 | 1.00 | 0.07 | 0.0 | 0.0 |

UNIT HYDROGRAPH DATA

TC 21.40 R 26.10 NTA 0

RECESSION DATA

SIRIO 745.00 QRCN 5200.00 RTIOR 1.30

| UNIT HYDROGRAPH 51 END-OF-PERIOD ORIGINATES, EAG 22.08 HOURS, CP 0.55 VOL 1.00 | | | | | | | | | |
|--|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 269. | 999. | 2017. | 5167. | 4561. | 5305. | 5859. | 6078. | 5742. | 5151. |
| 4573. | 4076. | 3633. | 3239. | 2886. | 2572. | 2293. | 2043. | 1821. | 1623. |
| 1447. | 1290. | 1142. | 1025. | 915. | 814. | 723. | 647. | 576. | 514. |
| 458. | 408. | 364. | 324. | 283. | 258. | 230. | 205. | 182. | 162. |
| 145. | 129. | 115. | 103. | 91. | 81. | 72. | 55. | 52. | 51. |

EAD-OF-PERIOD FLOW

| TIME | RAIN | EXCS | COMP C |
|------|------|------|--------|
| 1 | 0.02 | 0.00 | 725. |
| 2 | 0.02 | 0.00 | 707. |
| 3 | 0.08 | 0.00 | 689. |
| 4 | 0.08 | 0.00 | 671. |
| 5 | 0.24 | 0.00 | 552. |
| 6 | 0.25 | 0.00 | 526. |
| 7 | 0.03 | 0.00 | 620. |
| 8 | 0.03 | 0.00 | 504. |
| 9 | 0.34 | 0.11 | 619. |

| | | | |
|----|------|------|-------|
| 10 | 0.34 | 0.12 | 720. |
| 11 | 1.19 | 0.97 | 1158. |
| 12 | 1.19 | 0.97 | 2516. |
| 13 | 5.60 | 5.58 | 5229. |
| 14 | 7.32 | 7.01 | 1191. |
| 15 | 0.52 | 0.29 | 2362. |
| 16 | 0.52 | 0.29 | 2657. |
| 17 | 0.0 | 0.0 | 5091. |
| 18 | 0.0 | 0.0 | 5361. |
| 19 | 0.0 | 0.0 | 7265. |
| 20 | 0.0 | 0.0 | 7712. |
| 21 | 0.0 | 0.0 | 7637. |
| 22 | 0.0 | 0.0 | 7113. |
| 23 | 0.0 | 0.0 | 6364. |
| 24 | 0.0 | 0.0 | 5724. |
| 25 | 0.0 | 0.0 | 5059. |
| 26 | 0.0 | 0.0 | 4539. |
| 27 | 0.0 | 0.0 | 4083. |
| 28 | 0.0 | 0.0 | 3617. |
| 29 | 0.0 | 0.0 | 3221. |
| 30 | 0.0 | 0.0 | 2871. |
| 31 | 0.0 | 0.0 | 2502. |
| 32 | 0.0 | 0.0 | 2231. |
| 33 | 0.0 | 0.0 | 2049. |
| 34 | 0.0 | 0.0 | 1834. |
| 35 | 0.0 | 0.0 | 1627. |
| 36 | 0.0 | 0.0 | 1453. |
| 37 | 0.0 | 0.0 | 1297. |
| 38 | 0.0 | 0.0 | 1152. |
| 39 | 0.0 | 0.0 | 1039. |
| 40 | 0.0 | 0.0 | 925. |
| 41 | 0.0 | 0.0 | 826. |
| 42 | 0.0 | 0.0 | 738. |
| 43 | 0.0 | 0.0 | 606. |
| 44 | 0.0 | 0.0 | 509. |
| 45 | 0.0 | 0.0 | 529. |

SUN 16.00 13.22 1049653.

| | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|--------|--------|--------|---------|---------|--------------|
| CFS | 77125. | 76898. | 56527. | 40399. | 1049651. |
| INCHES | | 1.90 | 6.53 | 11.56 | 12.95 |
| AC-FT | | 38106. | 132220. | 240514. | 260378. |

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

AAAAAXLXL

DATA

STATION 7

20000 40000 60000 80000 100000 120000 140000 0.

XXXXXLO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

XXXXXALO.

| | |
|-----|--------|
| 23 | XXXXXX |
| 24 | XXXXXX |
| 25 | XXXXXX |
| 26 | XXXXXX |
| 27 | XXXXXX |
| 28 | XXXXXX |
| 29 | XXXXXX |
| 30 | XXXXXX |
| 31 | XXXXXX |
| 32 | XXXXXX |
| 33 | XXXXXX |
| 34 | XXXXXX |
| 35 | XXXXXX |
| 36 | XXXXXX |
| 37 | XXXXXX |
| 38 | XXXXXX |
| 39 | XXXXXX |
| 40 | XXXXXX |
| 41 | XXXXXX |
| 42 | XXXXXX |
| 43 | XXXXXX |
| 44 | XXXXXX |
| 45 | XXXXXX |
| 46 | XXXXXX |
| 47 | XXXXXX |
| 48 | XXXXXX |
| 49 | XXXXXX |
| 50 | XXXXXX |
| 51 | XXXXXX |
| 52 | XXXXXX |
| 53 | XXXXXX |
| 54 | XXXXXX |
| 55 | XXXXXX |
| 56 | XXXXXX |
| 57 | XXXXXX |
| 58 | XXXXXX |
| 59 | XXXXXX |
| 60 | XXXXXX |
| 61 | XXXXXX |
| 62 | XXXXXX |
| 63 | XXXXXX |
| 64 | XXXXXX |
| 65 | XXXXXX |
| 66 | XXXXXX |
| 67 | XXXXXX |
| 68 | XXXXXX |
| 69 | XXXXXX |
| 70 | XXXXXX |
| 71 | XXXXXX |
| 72 | XXXXXX |
| 73 | XXXXXX |
| 74 | XXXXXX |
| 75 | XXXXXX |
| 76 | XXXXXX |
| 77 | XXXXXX |
| 78 | XXXXXX |
| 79 | XXXXXX |
| 80 | XXXXXX |
| 81 | XXXXXX |
| 82 | XXXXXX |
| 83 | XXXXXX |
| 84 | XXXXXX |
| 85 | XXXXXX |
| 86 | XXXXXX |
| 87 | XXXXXX |
| 88 | XXXXXX |
| 89 | XXXXXX |
| 90 | XXXXXX |
| 91 | XXXXXX |
| 92 | XXXXXX |
| 93 | XXXXXX |
| 94 | XXXXXX |
| 95 | XXXXXX |
| 96 | XXXXXX |
| 97 | XXXXXX |
| 98 | XXXXXX |
| 99 | XXXXXX |
| 100 | XXXXXX |

| | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|-------|---------|---------|---------|---------|--------------|
| CFS | 220756. | 220309. | 201044. | 56275. | 1440910. |
| INAGS | | 7.28 | 1.66 | 22.79 | 15.35 |
| ACFT | | 59688. | 206522. | 335023. | 357436. |

[illegible]

OVN

SUB-AREA RUNOFF COMPUTATION

SURAREA 47

| STAD | ICOMP | TECON | ITAPE | JPLT | JPRT | INAME |
|------|-------|-------|-------|------|------|-------|
| 2 | 0 | 0 | 0 | 0 | 0 | 1 |

HYDROGRAPH DATA

| IHYD | IUNG | TAKEA | SNAP | TRSPD | TRSPC | RATIO | ISNOW | ISAME | LOCAL |
|------|------|--------|------|---------|-------|-------|-------|-------|-------|
| 1 | 0 | 564.00 | 0.0 | 1055.00 | 0.0 | 0.0 | 0 | 0 | 0 |

PRECIP DATA

| SPFE | PMS | R6 | R12 | R24 | R48 | R72 | R96 |
|------|-------|-------|-------|-------|-------|-----|-----|
| 0.0 | 18.00 | 60.50 | 75.00 | 86.00 | 92.50 | 0.0 | 0.0 |

LOSS DATA

| STKR | DLTKR | RTIOL | ERAIN | SINKS | RTIOK | SIRTL | CNSTL | ALSMX | RTIMP |
|------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 0.0 | 0.0 | 1.00 | 0.0 | 0.0 | 1.00 | 1.00 | 0.07 | 0.0 | 0.0 |

UNIT HYDROGRAPH DATA

TC 2.20 R 14.70 N/A 0

RECESSION DATA

STRTO 1200.00 CRCSN 7600.00 RTIOK 1.20

UNIT HYDROGRAPH 31 END-OF-PERIOD COORDINATES, LAG 20.62 HOURS, CP 0.71 VOL 1.00

| | | | | | | | | | |
|-------|-------|-------|-------|--------|--------|--------|--------|--------|-------|
| 592. | 2525. | 4906. | 7230. | 10122. | 11572. | 12532. | 12340. | 13413. | 3927. |
| 7192. | 5830. | 4775. | 3891. | 317. | 2553. | 2103. | 1719. | 1397. | 1139. |
| 928. | 756. | 515. | 502. | 409. | 323. | 272. | 221. | 180. | 147. |

END-OF-PERIOD FLOW

| TIME | RAIN | LACS | COMP C |
|------|------|------|--------|
| 1 | 0.03 | 0.00 | 1189. |
| 2 | 0.03 | 0.00 | 1189. |
| 3 | 0.03 | 0.00 | 1189. |
| 4 | 0.03 | 0.00 | 1080. |
| 5 | 0.25 | 0.00 | 1052. |
| 6 | 0.50 | 0.00 | 1025. |
| 7 | 0.04 | 0.00 | 992. |
| 8 | 0.04 | 0.00 | 972. |
| 9 | 0.06 | 0.14 | 1042. |
| 10 | 0.30 | 0.17 | 1362. |
| 11 | 1.19 | 0.97 | 2529. |

| | | | | |
|----|------|------|------|------|
| 12 | 1.19 | 1.19 | 1.19 | 1.19 |
| 13 | 0.00 | 0.00 | 0.00 | 0.00 |
| 14 | 0.00 | 0.00 | 0.00 | 0.00 |
| 15 | 0.00 | 0.00 | 0.00 | 0.00 |
| 16 | 0.00 | 0.00 | 0.00 | 0.00 |
| 17 | 0.00 | 0.00 | 0.00 | 0.00 |
| 18 | 0.00 | 0.00 | 0.00 | 0.00 |
| 19 | 0.00 | 0.00 | 0.00 | 0.00 |
| 20 | 0.00 | 0.00 | 0.00 | 0.00 |
| 21 | 0.00 | 0.00 | 0.00 | 0.00 |
| 22 | 0.00 | 0.00 | 0.00 | 0.00 |
| 23 | 0.00 | 0.00 | 0.00 | 0.00 |
| 24 | 0.00 | 0.00 | 0.00 | 0.00 |
| 25 | 0.00 | 0.00 | 0.00 | 0.00 |
| 26 | 0.00 | 0.00 | 0.00 | 0.00 |
| 27 | 0.00 | 0.00 | 0.00 | 0.00 |
| 28 | 0.00 | 0.00 | 0.00 | 0.00 |
| 29 | 0.00 | 0.00 | 0.00 | 0.00 |
| 30 | 0.00 | 0.00 | 0.00 | 0.00 |
| 31 | 0.00 | 0.00 | 0.00 | 0.00 |
| 32 | 0.00 | 0.00 | 0.00 | 0.00 |
| 33 | 0.00 | 0.00 | 0.00 | 0.00 |
| 34 | 0.00 | 0.00 | 0.00 | 0.00 |
| 35 | 0.00 | 0.00 | 0.00 | 0.00 |
| 36 | 0.00 | 0.00 | 0.00 | 0.00 |
| 37 | 0.00 | 0.00 | 0.00 | 0.00 |
| 38 | 0.00 | 0.00 | 0.00 | 0.00 |
| 39 | 0.00 | 0.00 | 0.00 | 0.00 |
| 40 | 0.00 | 0.00 | 0.00 | 0.00 |
| 41 | 0.00 | 0.00 | 0.00 | 0.00 |
| 42 | 0.00 | 0.00 | 0.00 | 0.00 |
| 43 | 0.00 | 0.00 | 0.00 | 0.00 |
| 44 | 0.00 | 0.00 | 0.00 | 0.00 |
| 45 | 0.00 | 0.00 | 0.00 | 0.00 |

SUM 15.19 12.37 1992.19.

| PEAK | Q-TOUR | 247.00R | 707.00R | TOTAL |
|-------|---------|---------|---------|---------|
| CFC | 14.355. | 100.00. | 0.00. | 100.00. |
| INGR0 | 2.44 | 0.02 | 12.15 | 12.17 |
| AC-11 | 7.723. | 24.107. | 33.394. | 33.501. |

[illegible]

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

| ISIAQ | ICOMP | IECON | ITAPE | JPLT | JRRT | NAME |
|-------|-------|-------|-------|------|------|------|
| 5 | 2 | 0 | 0 | 0 | 0 | 0 |

| | SUM OF 2 HYDROGRAPHS AT | | | | 3 | |
|---------|-------------------------|---------|---------|---------|---------|---------|
| 2070. | 2036. | 1972. | 1897. | 1840. | 1793. | 1802. |
| 3567. | 3374. | 1624.2 | 3664. | 11902. | 173617. | 259376. |
| 227639. | 227725. | 196066. | 185397. | 116935. | 980210. | 111779. |
| 51284. | 51284. | 33131. | 32907. | 28493. | 23139. | 19900. |
| 17040. | 15838. | 14780. | 12805. | 12922. | 21616. | 18354. |

| | | | | | | |
|--------|--------|--------|--------|---------|---------|--------------|
| INCHES | CFE | PEAR | 5-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
| AC-FI | 265116 | 262577 | 24193 | 117189 | 2992590 | 7922441 |
| | | 2532 | 780 | 1243 | 1323 | |
| | | 120420 | 439256 | 597585 | | |

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

XXXXXX

NOV 1964

HYDROGRAPH ROUTING

ISIAO ICOM2 IECOM IIAPE JPLI JPAI IMAVE
4 1 0 0 0 0 0

ROUTING DATA

CLOSS CLOSS AVG IRES ISANL
0.0 0.0 0.0 1 0

MSIPS MSIDL LAG ANSKK X ISK STORA
1 0 0 0.0 0.0 0.0 -1

STORAGE 0. 23446. 154716. 207910. 261872. 216256. 271315. 426734. 519498. 595980.
CUTFLW 0. 7940. 23130. 25910. 13270. 74720. 91100. 108800. 137350. 160250.

| TIME | EQP STICK | AVG IN | EQP OUT |
|------|-----------|---------|---------|
| 1 | 19530. | 2070. | 2070. |
| 2 | 19025. | 2052. | 2070. |
| 3 | 19012. | 2014. | 2068. |
| 4 | 18887. | 1956. | 2065. |
| 5 | 19030. | 1714. | 2062. |
| 6 | 19811. | 1965. | 2057. |
| 7 | 19742. | 1816. | 2051. |
| 8 | 19674. | 1769. | 2043. |
| 9 | 19558. | 1774. | 2037. |
| 10 | 19492. | 1975. | 2051. |
| 11 | 19734. | 2858. | 2055. |
| 12 | 20030. | 5470. | 2143. |
| 13 | 20997. | 11112. | 2199. |
| 14 | 20865. | 26546. | 3006. |
| 15 | 41467. | 54397. | 4507. |
| 16 | 63616. | 56526. | 6639. |
| 17 | 97579. | 145760. | 12124. |
| 18 | 145336. | 198234. | 20350. |
| 19 | 195760. | 230113. | 33817. |
| 20 | 253795. | 262248. | 47571. |
| 21 | 30612. | 262248. | 66186. |
| 22 | 34322. | 243717. | 82137. |
| 23 | 374427. | 212925. | 92190. |
| 24 | 399018. | 185616. | 98861. |
| 25 | 405176. | 151922. | 132889. |
| 26 | 41152. | 127658. | 104784. |
| 27 | 414873. | 107891. | 105020. |
| 28 | 41593. | 91290. | 107780. |
| 29 | 405274. | 77559. | 101939. |
| 30 | 395676. | 65920. | 99229. |

| | | | |
|----|---------|--------|--------|
| 31 | 386,224 | 54,224 | 35,360 |
| 32 | 377,120 | 42,120 | 34,000 |
| 33 | 361,920 | 41,920 | 31,200 |
| 34 | 350,134 | 31,134 | 34,820 |
| 35 | 321,190 | 30,190 | 39,540 |
| 36 | 324,250 | 21,250 | 77,520 |
| 37 | 311,081 | 24,100 | 72,640 |
| 38 | 292,490 | 22,300 | 51,400 |
| 39 | 283,211 | 20,610 | 52,520 |
| 40 | 273,630 | 19,070 | 58,000 |
| 41 | 269,160 | 17,090 | 53,800 |
| 42 | 253,350 | 16,480 | 50,150 |
| 43 | 251,097 | 15,317 | 47,898 |
| 44 | 243,936 | 14,292 | 45,717 |
| 45 | 236,174 | 13,265 | 43,617 |

SUM 2,136,112

| | | | | | | |
|--------|--------|------|--------|---------|---------|--------------|
| CEC | 105020 | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
| INCHES | | | 104902 | 101557 | 80218 | 2136112 |
| AC-FI | | | 0.92 | 3.55 | 8.95 | 9.42 |
| | | | 52044 | 201598 | 481149 | 529888 |

2017-215

INFLOW 1, OUTFLOW 2 AND UNRESERVED FLOW 4

XXXXXXXXXX

XXXXXXXXXX

2000

2000

XXXXXXXXXX

WISCONSIN

10

• 5 1/2 •

•••XXXXXX

7:2

100

C7XVZVZV

XXXXXX

U
U
U

[illegible]

••XxXxXxXx

• XXXXX

100

• C78Y8V9X0Y

• X X X X X •

15.0

16

[illegible]

● ●
- ()
- J
· ·
X X
· ·

24

•
•
•
•
•
•

•••
•••
•••

22

21.

• • L X X X X X X X

7

DOI: 10.1002/for

THE UNIVERSITY OF CHICAGO

© 2004 Blackwell Publishing Ltd, *Journal of Internal Medicine* 255: 103–111

1990

1000

XXXXXLC.

22

XXXXXALC.

24

XXXXXALC.

25

XXXXXALC.

26

XXXXXALC.

27

XXXXXALC.

28

XXXXXALC.

29

XXXXXALC.

30

XXXXXALC.

31

XXXXXALC.

32

XXXXXALC.

33

XXXXXALC.

34

XXXXXALC.

35

XXXXXALC.

36

XXXXXALC.

37

XXXXXALC.

38

XXXXXALC.

39

XXXXXALC.

40

XXXXXALC.

41

XXXXXALC.

42

XXXXXALC.

43

XXXXXALC.

44

XXXXXALC.

45

XXXXXALC.

46

XXXXXALC.

47

XXXXXALC.

RUNOFF SUMMARY, AVAILABLE FLOW

| | | PLAN | 6-HOUR | 24-HOUR | 72-HOUR | AREA |
|-----------------------------|---|---------|---------|---------|---------|---------|
| HYDROGRAPH AT
ROUTED TO | 1 | 49930. | 49349. | 56459. | 19996. | 114.00 |
| | 2 | 49930. | 48639. | 56222. | 19939. | 114.00 |
| HYDROGRAPH AT
2 COMBINED | 1 | 71230. | 76800. | 86827. | 40353. | 371.00 |
| | 2 | 121554. | 121139. | 101437. | 56339. | 491.00 |
| HYDROGRAPH AT
ROUTED TO | 3 | 123750. | 120300. | 101044. | 56273. | 491.00 |
| | 2 | 147510. | 140500. | 121042. | 61375. | 500.00 |
| HYDROGRAPH AT
2 COMBINED | 3 | 293216. | 294677. | 251172. | 117149. | 1050.00 |
| | 2 | 132020. | 124992. | 101557. | 80415. | 1022.00 |

 HEC-1 VERSION DATED JAN 1973
 UPDATED AUG 74
 CHANGE NO. 01

SACANDAGA RESERVOIR - NEW YORK
 RESERVOIR AT TOP OF FLOOD CONTROL POOL
 TEST SPF

JOB SPECIFICATION
 NO NHR NMIN IDAY IHR IMIN WEIRC IPLT IPRT NSTAN
 45 3 0 0 0 0 2 0 0
 JOPER NWI
 3 0

SUB-AREA RUNOFF COMPUTATION

SUBAREA 45

ISTAQ ICUMP IECON ITAPE JPLT JPAT INAME
 1 0 0 0 0 0 1

HYDROGRAPH DATA
 IHYDG IUNG TAREA SNAP TRSDA TRSPC KATIO ISNOW ISAME LOCAL
 1 0 114.00 0.0 1055.00 0.0 0.0 0 0 0

PRECIP DATA
 SPFE PMS R6 R12 R24 R48 R72 R96
 12.20 0.1 0.0 0.0 0.0 0.0 0.0 0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.912

LOSS DATA
 STKR DLKR RTIOL ERAIN STKRS RTICK STIRL CNSFL ALSMX RTIMP
 0.0 3.0 1.00 0.0 0.0 0.0 1.00 0.00 0.0 0.0

UNIT HYDROGRAPH DATA
 IC 16.20 S 11.50 NTA 0

RECESSION DATA
 SIXTY 180.00 SACSX 130000 RTICR 1.30

UNIT HYDROGRAPH 24 END-OF-PERIOD ORDINATES, LAG 15.00 HOURS, CP 3.65 VOL 1.00
 312. 1122. 2164. 3043. 3436. 3817. 2535. 1988. 1523. 1179.
 913. 707. 548. 424. 254. 197. 153. 118. 92.
 71. 55. 43. 33.

| TIME | ENC-OF-PIPED FLOW | RAIN | SACS | COMP Q |
|------|-------------------|------|--------|--------|
| 1 | 0.01 | 0.00 | 175. | |
| 2 | 0.01 | 0.00 | 171. | |
| 3 | 0.03 | 0.00 | 166. | |
| 4 | 0.03 | 0.00 | 162. | |
| 5 | 0.09 | 0.00 | 155. | |
| 6 | 0.19 | 0.00 | 154. | |
| 7 | 0.03 | 0.00 | 150. | |
| 8 | 0.02 | 0.00 | 145. | |
| 9 | 0.02 | 0.00 | 142. | |
| 10 | 0.05 | 0.00 | 138. | |
| 11 | 0.12 | 0.00 | 135. | |
| 12 | 0.12 | 0.00 | 131. | |
| 13 | 0.41 | 0.00 | 147. | |
| 14 | 0.03 | 0.00 | 141. | |
| 15 | 0.07 | 0.00 | 134. | |
| 16 | 0.07 | 0.00 | 131. | |
| 17 | 0.24 | 0.02 | 2177. | |
| 18 | 0.24 | 0.02 | 2416. | |
| 19 | 0.03 | 0.41 | 2373. | |
| 20 | 0.63 | 0.41 | 2423. | |
| 21 | 2.15 | 1.92 | 3-26. | |
| 22 | 4.35 | 4.24 | 6753. | |
| 23 | 0.39 | 0.17 | 12448. | |
| 24 | 0.39 | 0.17 | 18-94. | |
| 25 | 0.02 | 0.00 | 22678. | |
| 26 | 0.02 | 0.00 | 23514. | |
| 27 | 0.05 | 0.00 | 26520. | |
| 28 | 0.05 | 0.00 | 16905. | |
| 29 | 0.16 | 0.00 | 13132. | |
| 30 | 0.32 | 0.00 | 10230. | |
| 31 | 0.03 | 0.00 | 9045. | |
| 32 | 0.03 | 0.00 | 6937. | |
| 33 | 0.00 | 0.00 | 5672. | |
| 34 | 0.00 | 0.00 | 4648. | |
| 35 | 0.00 | 0.00 | 3200. | |
| 36 | 0.00 | 0.00 | 2500. | |
| 37 | 0.00 | 0.00 | 1949. | |
| 38 | 0.00 | 0.00 | 1507. | |
| 39 | 0.00 | 0.00 | 1332. | |
| 40 | 0.00 | 0.00 | 1297. | |
| 41 | 0.00 | 0.00 | 1254. | |
| 42 | 0.00 | 0.00 | 1131. | |
| 43 | 0.00 | 0.00 | 1159. | |
| 44 | 0.00 | 0.00 | 1168. | |
| 45 | 0.00 | 0.00 | 1138. | |
| SUM | 11.83 | 8.03 | 20400. | |

PEAK
235.4

6-HOUR
220.6

24-HOUR
172.8

72-HOUR
83.0

TOTAL VOLUME
204006

8.32

50006

CFE
INCHES
AC-FT

11458

5.88

5.84

47900

REVIEWS

4005. 8000. 12000. 16000. 20000. 24000. 28000. 32000. 36000. 40000. 44000. 48000. 52000. 56000. 60000. 64000. 68000. 72000. 76000. 80000. 84000. 88000. 92000. 96000. 100000. 104000. 108000. 112000. 116000. 120000. 124000. 128000. 132000. 136000. 140000. 144000. 148000. 152000. 156000. 160000. 164000. 168000. 172000. 176000. 180000. 184000. 188000. 192000. 196000. 200000. 204000. 208000. 212000. 216000. 220000. 224000. 228000. 232000. 236000. 240000. 244000. 248000. 252000. 256000. 260000. 264000. 268000. 272000. 276000. 280000. 284000. 288000. 292000. 296000. 300000. 304000. 308000. 312000. 316000. 320000. 324000. 328000. 332000. 336000. 340000. 344000. 348000. 352000. 356000. 360000. 364000. 368000. 372000. 376000. 380000. 384000. 388000. 392000. 396000. 400000. 404000. 408000. 412000. 416000. 420000. 424000. 428000. 432000. 436000. 440000. 444000. 448000. 452000. 456000. 460000. 464000. 468000. 472000. 476000. 480000. 484000. 488000. 492000. 496000. 500000. 504000. 508000. 512000. 516000. 520000. 524000. 528000. 532000. 536000. 540000. 544000. 548000. 552000. 556000. 560000. 564000. 568000. 572000. 576000. 580000. 584000. 588000. 592000. 596000. 600000. 604000. 608000. 612000. 616000. 620000. 624000. 628000. 632000. 636000. 640000. 644000. 648000. 652000. 656000. 660000. 664000. 668000. 672000. 676000. 680000. 684000. 688000. 692000. 696000. 700000. 704000. 708000. 712000. 716000. 720000. 724000. 728000. 732000. 736000. 740000. 744000. 748000. 752000. 756000. 760000. 764000. 768000. 772000. 776000. 780000. 784000. 788000. 792000. 796000. 800000. 804000. 808000. 812000. 816000. 820000. 824000. 828000. 832000. 836000. 840000. 844000. 848000. 852000. 856000. 860000. 864000. 868000. 872000. 876000. 880000. 884000. 888000. 892000. 896000. 900000. 904000. 908000. 912000. 916000. 920000. 924000. 928000. 932000. 936000. 940000. 944000. 948000. 952000. 956000. 960000. 964000. 968000. 972000. 976000. 980000. 984000. 988000. 992000. 996000. 1000000. 1004000. 1008000. 1012000. 1016000. 1020000. 1024000. 1028000. 1032000. 1036000. 1040000. 1044000. 1048000. 1052000. 1056000. 1060000. 1064000. 1068000. 1072000. 1076000. 1080000. 1084000. 1088000. 1092000. 1096000. 1100000. 1104000. 1108000. 1112000. 1116000. 1120000. 1124000. 1128000. 1132000. 1136000. 1140000. 1144000. 1148000. 1152000. 1156000. 1160000. 1164000. 1168000. 1172000. 1176000. 1180000. 1184000. 1188000. 1192000. 1196000. 1200000. 1204000. 1208000. 1212000. 1216000. 1220000. 1224000. 1228000. 1232000. 1236000. 1240000. 1244000. 1248000. 1252000. 1256000. 1260000. 1264000. 1268000. 1272000. 1276000. 1280000. 1284000. 1288000. 1292000. 1296000. 1300000. 1304000. 1308000. 1312000. 1316000. 1320000. 1324000. 1328000. 1332000. 1336000. 1340000. 1344000. 1348000. 1352000. 1356000. 1360000. 1364000. 1368000. 1372000. 1376000. 1380000. 1384000. 1388000. 1392000. 1396000. 1400000. 1404000. 1408000. 1412000. 1416000. 1420000. 1424000. 1428000. 1432000. 1436000. 1440000. 1444000. 1448000. 1452000. 1456000. 1460000. 1464000. 1468000. 1472000. 1476000. 1480000. 1484000. 1488000. 1492000. 1496000. 1500000. 1504000. 1508000. 1512000. 1516000. 1520000. 1524000. 1528000. 1532000. 1536000. 1540000. 1544000. 1548000. 1552000. 1556000. 1560000. 1564000. 1568000. 1572000. 1576000. 1580000. 1584000. 1588000. 1592000. 1596000. 1600000. 1604000. 1608000. 1612000. 1616000. 1620000. 1624000. 1628000. 1632000. 1636000. 1640000. 1644000. 1648000. 1652000. 1656000. 1660000. 1664000. 1668000. 1672000. 1676000. 1680000. 1684000. 1688000. 1692000. 1696000. 1700000. 1704000. 1708000. 1712000. 1716000. 1720000. 1724000. 1728000. 1732000. 1736000. 1740000. 1744000. 1748000. 1752000. 1756000. 1760000. 1764000. 1768000. 1772000. 1776000. 1780000. 1784000. 1788000. 1792000. 1796000. 1800000. 1804000. 1808000. 1812000. 1816000. 1820000. 1824000. 1828000. 1832000. 1836000. 1840000. 1844000. 1848000. 1852000. 1856000. 1860000. 1864000. 1868000. 1872000. 1876000. 1880000. 1884000. 1888000. 1892000. 1896000. 1900000. 1904000. 1908000. 1912000. 1916000. 1920000. 1924000. 1928000. 1932000. 1936000. 1940000. 1944

* XXXXX

PRECIPITATION AND EXC.

SSX

553 X 05

1

ESS X XÖ.L

2

ESS x %D

330

47

ESS X X

[illegible]

SS7
X
6X

○ ○
×
○○

100

770X X 55R

1

X
X

110X X 523

100

710X X 553

100

257 X 70X 12

SS3 X 70X X 77

4. *Explain the importance of the following factors in the development of a country's economy:*

553 X 77X

1000

Y Y Y Y Y Y Y Y

SS 7X XX 7X

2

SS 7X7X7X

100

81
XYYYYY

SS 7X7X

67

ESS XLX XX

20

10

10

NOVA*

HYDROGRAPH ROUTING

ISIAO ICOMP 1
15000 ITAPE 0
JULI 0
NAME 0

ROUTING DATA

CLASS. CLOS. AVG. IRES. ISAME
1.0 0.0 0.0 0 0

NSIPS NSTOL 2
LAG 0
ASKK 1.000
IS 0.0
STORA 0

| | | ROUTED FLOWS AT | 2 | | |
|-------|-------|-----------------|--------|--------|--------|
| 175. | 174. | 166. | 162. | 152. | 142. |
| 180. | 134. | 194. | 181. | 168. | 241. |
| 2022. | 2978. | 13151. | 18936. | 23844. | 2424. |
| 9948. | 7803. | 6187. | 3930. | 2430. | 16393. |
| 1290. | 1262. | 1195. | 1164. | 1300. | 1499. |
| | | | | | 1317. |

PEAK 23120. 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
CFS 24937. 7150. 6057. 205171.
INCHES 2.07 2.61 7.59 8.29
AC-F 11'00. 54393. 47906. 50349.

2014-15

•

1

1

100

2

—

1

Abstract

•

1

1

1

1

2

1000

1

the authors

10/10/10

5

Topic:

1

1

10. *Staphylococcus aureus*

72

100

9

•

1

2

[illegible]

OVR

SUB-AREA RUNOFF COMPUTATION

SUBAREA 46
 IHYDQ IUNG TAREA SWAP TRSPC RATIO ISADJ ISAME LOCAL
 1 0 377.00 0.0 1055.00 0.0 0.0 0 0 0
 2 0 0 0 0 0 0 0 0 0

HYDROGRAPH DATA

PRECIP DATA
 SPFE PXS R6 R12 R48 R72 R96
 11.20 0.0 0.0 0.0 0.0 0.0 0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.912

LOSS DATA
 STRK DLTKR RILOL LRAIN STRKS WTKCK STRIL CNSTL ALGNX RIJMP
 0.0 0.0 1.00 0.0 0.0 1.00 1.00 0.07 0.0 0.0

UNIT HYDROGRAPH DATA
 TC 24.40 F 46.10 NTA 0

RECESSION DATA
 SRTG 745.00 WKCSA 2300.00 RTIOR 1.30

UNIT HYDROGRAPH 51 END-OF-PERIOD ORDINATES, LAG 22.00 HOURS, CP 0.25 VOL 1.00
 269. 999. 2017. 3187. 4361. 5306. 5895. 6078. 5762. 5131.
 4573. 4076. 3632. 3238. 2880. 2572. 2293. 2043. 1823. 1623.
 1447. 1290. 1149. 1025. 913. 814. 725. 647. 576. 514.
 458. 408. 364. 324. 289. 258. 230. 205. 182. 163.
 145. 129. 115. 103. 91. 81. 73. 65. 58. 51.
 46.

END-OF-PERIOD FLOW
 TIME RAIN EXCS COMP Q
 1 0.01 0.00 726.
 2 0.01 0.00 737.
 3 0.02 0.00 689.
 4 0.02 0.00 671.
 5 0.03 0.00 653.
 6 0.18 0.00 530.
 7 0.01 0.00 520.
 8 0.01 0.00 604.
 9 0.04 0.00 588.

| | | | |
|----|------|------|--------|
| 10 | 0.04 | 0.00 | 572. |
| 11 | 0.10 | 0.00 | 539. |
| 12 | 0.10 | 0.00 | 540. |
| 13 | 0.39 | 0.01 | 512. |
| 14 | 0.80 | 0.37 | 679. |
| 15 | 0.06 | 0.00 | 1093. |
| 16 | 0.05 | 0.00 | 1674. |
| 17 | 0.18 | 0.00 | 2341. |
| 18 | 0.18 | 0.00 | 3009. |
| 19 | 0.53 | 0.00 | 3625. |
| 20 | 0.53 | 0.30 | 4255. |
| 21 | 2.06 | 1.53 | 7269. |
| 22 | 4.17 | 3.95 | 8242. |
| 23 | 0.32 | 0.10 | 13343. |
| 24 | 0.32 | 0.10 | 15912. |
| 25 | 0.01 | 0.00 | 27014. |
| 26 | 0.01 | 0.00 | 33550. |
| 27 | 0.04 | 0.00 | 38206. |
| 28 | 0.04 | 0.00 | 40667. |
| 29 | 0.15 | 0.00 | 40373. |
| 30 | 0.31 | 0.03 | 37530. |
| 31 | 0.02 | 0.00 | 33715. |
| 32 | 0.02 | 0.00 | 30193. |
| 33 | 0.00 | 0.00 | 27059. |
| 34 | 0.00 | 0.00 | 24267. |
| 35 | 0.00 | 0.00 | 21773. |
| 36 | 0.00 | 0.00 | 19529. |
| 37 | 0.00 | 0.00 | 17499. |
| 38 | 0.00 | 0.00 | 15647. |
| 39 | 0.00 | 0.00 | 13970. |
| 40 | 0.00 | 0.00 | 12474. |
| 41 | 0.00 | 0.00 | 11100. |
| 42 | 0.00 | 0.00 | 9950. |
| 43 | 0.00 | 0.00 | 8889. |
| 44 | 0.00 | 0.00 | 7943. |
| 45 | 0.00 | 0.00 | 7099. |

SUM 10.82 7.24 55020.

| PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|--------|--------|---------|---------|--------------|
| 40667. | 40520. | 35173. | 21669. | 550200. |
| CFS | 1.00 | 3.47 | 6.42 | 5.79 |
| INCHES | 20103. | 69800. | 129005. | 136484. |
| AC-FT | | | | |

OVF

STATION 2

INFLOW I, OUTFLOW O, AND OBSERVED FLOW S

5000. 10000. 15000. 20000. 25000. 30000. 35000. 40000. 45000. 50000.

PRECIP. L. AND EXC. Z.

XXXXXXXO.

ESS X

ESS X XO.

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS X XO.L

ESS XLXXXX

21 •

XXXXXXXXXX

22 •

XXXXXXXXXX

23 •

XXXXXXLLX

24 •

XXXXXXXXLLX

25 •

XXXXXXXXLL

26 •

XXXXXXXXLL

27 •

XXXXXXXXLL

28 •

XXXXXXXXLL

29 •

XXXXXXXXLLX

30 •

XXXXXXXXLLX

31 •

XXXXXXXXLL

32 •

XXXXXXXXLL

33 •

XXXXXXXXLL

34 •

XXXXXXXXLL

35 •

XXXXXXXXLL

36 •

XXXXXXXXLL

37 •

XXXXXXXXLL

38 •

XXXXXXXXLL

39 •

XXXXXXXXLL

40 •

XXXXXXXXLL

41 •

XXXXXXXXLL

42 •

XXXXXXXXLL

43 •

XXXXXXXXLL

44 •

XXXXXXXXLL

45 •

XXXXXXXXXX


OVN

COMBINE HYDROGRAPHICS

ISTAQ ICOMP 2
 IESON ITAPE JULI 0
 JPMI IIRAME 0


| | | SUM OF 2 HYDROGRAPHS AT | | 2 | |
|--------|--------|-------------------------|--------|--------|--------|
| 901. | 881. | 836. | 815. | 794. | 773. |
| 696. | 678. | 573. | 1554. | 2689. | 5205. |
| 7991. | 12206. | 33062. | 45950. | 56245. | 61122. |
| 43651. | 37996. | 33242. | 29203. | 25709. | 19228. |
| 12429. | 11211. | 10119. | 9138. | 8263. | 17537. |
| | | | | | 15470. |
| | | | | | 13791. |

| | | PEAK | | 6-HOUR | | 24-HOUR | | 72-HOUR | | TOTAL VOLUME | |
|--------|--------|--------|---------|---------|--|---------|--|---------|--|--------------|--|
| CFS | 61436. | 61279. | 51679. | 29510. | | | | | | 753372. | |
| INCHES | | 1.16 | 3.92 | 6.71 | | | | | | 7.14 | |
| AC-FT | | 30402. | 102557. | 175087. | | | | | | 186853. | |



NEW YORK

SARATOGA COUNTY



Portion of Conklingville, New York, 7.5 minute U.S.G.S. quadrangle

CONKLINGVILLE DAM

SITE LOCATION MAP

SCALE : 1"=2000'

OVF

STATION 2

INFLOW I, OUTFLOW O, AND OBSERVED FLOW #

0. 10000. 20000. 30000. 40000. 50000. 60000. 70000. 80000. 90000.

XXXXXX0.

1. I

XXXXXX0.

2. I

XXXXXX0.

3. I

XXXXXX0.

4. I

XXXXXX0.

5. I

XXXXXX0.

6. I

XXXXXX0.

7. I

XXXXXX0.

8. I

XXXXXX0.

9. I

XXXXXX0.

10. I

XXXXXX0.

11. I

XXXXXX0.

12. I

XXXXXX0.

13. I

XXXXXX0.

14. I

XXXXXX0.

15. I

XXXXXX0.

16. I

XXXXXX0.

17. I

XXXXXX0.

18. I

XXXXXX0.

19. I

XXXXXX0.

20. I

XXXXXX0.

21. I

XXXXXX0.

22. I

XXXXXXXXC.

23.

XXXXXXXXX0.

24.

XXXXXXXXX0.

25.

XXXXXXXXX0.

26.

XXXXXXXXX0.

27.

XXXXXXXXX0.

28.

XXXXXXXXXC.

29.

XXXXXXXXX0.

30.

XXXXXXXXX0.

31.

XXXXXXXXXC.

32.

XXXXXXXXX0.

33.

XXXXXXXXX0.

34.

XXXXXXXXX0.

35.

XXXXXXXXX0.

36.

XXXXXXXXX0.

37.

XXXXXXXXX0.

38.

XXXXXXXXX0.

39.

XXXXXXXXXC.

40.

XXXXXXXXX0.

41.

XXXXXXXXX0.

42.

XXXXXXXXX0.

43.

XXXXXXXXX0.

44.

XXXXXXXXX0.

45.

XXXXXXXXX0.

NOVN*

HYDROGRAPH ROUTING

ISTAC ICOMP 1 IRECON IIAPE JPLI JPMI INAME

ROUTING DATA
QLOSS CLOSS AVG IRES ISAME

NSIPS NSTOL LAG ANSKK X TSK STORA

ROUTED FLOWS AT

| | | | | | | | | | |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 901. | 898. | 889. | 859. | 837. | 815. | 794. | 773. | 753. | 739. |
| 715. | 696. | 679. | 703. | 934. | 1593. | 2692. | 3987. | 5162. | 5025. |
| 6790. | 8411. | 12715. | 21134. | 32962. | 45515. | 55614. | 60895. | 60819. | 56523. |
| 50366. | 43789. | 38057. | 33306. | 29248. | 25746. | 22672. | 19958. | 17570. | 15513. |
| 13816. | 12434. | 11225. | 10126. | 9147. | | | | | |

| PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|--------------|---------|---------|---------|--------------|
| CFS. 60895. | 60857. | 51465. | 29488. | 745928. |
| INCHES. 1.15 | 1.15 | 2.90 | 6.70 | 7.07 |
| AC-FT 30192. | 102132. | 175554. | | 185036. |

NOTES

[illegible][illegible]

OVN

SUB-AREA RUNOFF COMPUTATION

SUBAREA 47

1STAO 2 ICOMP 0 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1

HYDROGRAPH DATA
1 IHDG 0 IUNG 0 TAKEA 0 SMAP 0 TRSDA 0 TRSPC 0 RATIO 0 ISADK 0 ISAME 0 LOCAL 0

PRECIP DATA
SPEE 10.90 PNS 0.0 R6 0.0 R12 0.0 R24 0.0 R48 0.0 R72 0.0 R96 0.0

TRSPC COMPUTED BY THE PROGRAM IS 0.917

LOSS DATA
STKR DLTKR RTIOL ERATN STRKS RTIOL STIRL CNSTL ALSMX RTIMP
0.0 0.0 1.00 0.0 0.0 1.00 1.00 0.07 0.0 0.0

UNIT HYDROGRAPH DATA
IC 24.20 K 14.70 NTA 0

RECESSION DATA
STRTQ 1200.00 CACSN 7600.00 RTIOR 1.20

UNIT HYDROGRAPH 31 END-OF-PERIOD ORIGINATES, LAG 20.52 HOURS, CP 0.71 VOL 1.00
693. 2525. 4966. 7630. 10122. 11872. 12032. 12360. 12818. 8827.
7192. 5860. 4775. 3891. 3170. 2583. 2105. 1749. 1387. 1139.
928. 756. 616. 502. 409. 333. 272. 241. 180. 147.
120.

| END-OF-PERIOD FLOW | | |
|--------------------|------|--------|
| TIME | RAIN | COMP Q |
| 1 | 0.01 | 1169. |
| 2 | 0.01 | 1139. |
| 3 | 0.02 | 1109. |
| 4 | 0.02 | 1085. |
| 5 | 0.09 | 1052. |
| 6 | 0.16 | 1025. |
| 7 | 0.01 | 989. |
| 8 | 0.01 | 973. |
| 9 | 0.03 | 942. |
| 10 | 0.03 | 923. |
| 11 | 0.09 | 899. |

| | | | |
|----|------|------|--------|
| 12 | 0.09 | 0.00 | 516. |
| 13 | 0.08 | 0.00 | 851. |
| 14 | 0.71 | 0.00 | 1208. |
| 15 | 0.06 | 0.00 | 2173. |
| 16 | 0.06 | 0.00 | 5676. |
| 17 | 0.16 | 0.00 | 4598. |
| 18 | 0.16 | 0.00 | 6327. |
| 19 | 0.48 | 0.26 | 7323. |
| 20 | 0.49 | 0.26 | 8359. |
| 21 | 2.02 | 1.79 | 10504. |
| 22 | 4.09 | 3.87 | 17026. |
| 23 | 0.75 | 0.07 | 3231. |
| 24 | 0.29 | 0.07 | 4250. |
| 25 | 0.51 | 0.00 | 5541. |
| 26 | 0.01 | 0.00 | 71084. |
| 27 | 0.04 | 0.00 | 78194. |
| 28 | 0.04 | 0.00 | 7997. |
| 29 | 0.15 | 0.00 | 74902. |
| 30 | 0.30 | 0.00 | 54565. |
| 31 | 0.02 | 0.00 | 5327. |
| 32 | 0.02 | 0.00 | 4550. |
| 33 | 0.00 | 0.00 | 25933. |
| 34 | 0.00 | 0.00 | 29638. |
| 35 | 0.00 | 0.00 | 24504. |
| 36 | 0.00 | 0.00 | 26278. |
| 37 | 0.00 | 0.00 | 16754. |
| 38 | 0.00 | 0.00 | 15703. |
| 39 | 0.00 | 0.00 | 11322. |
| 40 | 0.00 | 0.00 | 2278. |
| 41 | 0.00 | 0.00 | 7627. |
| 42 | 0.00 | 0.00 | 7497. |
| 43 | 0.00 | 0.00 | 7215. |
| 44 | 0.00 | 0.00 | 1028. |
| 45 | 0.00 | 0.00 | 5845. |

SUN 10.45 6.54 849133.

| PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|--------|--------|---------|---------|--------------|
| 79967. | 79281. | 55244. | 34521. | 866525. |
| CFS | 1.31 | 7.32 | 6.73 | 7.16 |
| INCHES | 39233. | 130071. | 292445. | 215475. |
| AC-FT | | | | |

STATION 3

INFLOW I, OUTFLOW O AND OBSERVED FLOW *

| | | | | | | | | |
|-----------|--------|--------|--------|--------|--------|--------|--------|--------|
| 0. | 10000. | 20000. | 30000. | 40000. | 50000. | 60000. | 70000. | 80000. |
| XXXXXXXXX | | | | | | | | |

Principles and Exc

ESS. X

XS3

SSX

ESS-X

SSS

SSX

SECRET

ESS. X.

CSX

22

100

500

1.

4411075

12

—

100

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

11

1

100

100

4-10-62

ESS XLXLX

21 •

XXXXXXXXXX

22 •

XXXXXXXXXX

23 •

XXXXXXXXXX

24 •

XXXXXXXXXX

25 •

XXXXXXXXXX

26 •

XXXXXXXXXX

27 •

XXXXXXXXXX

28 •

XXXXXXXXXX

29 •

XXXXXXXXXX

30 •

XXXXXXXXXX

31 •

XXXXXXXXXX

32 •

XXXXXXXXXX

33 •

XXXXXXXXXX

34 •

XXXXXXXXXX

35 •

XXXXXXXXXX

36 •

XXXXXXXXXX

37 •

XXXXXXXXXX

38 •

XXXXXXXXXX

39 •

XXXXXXXXXX

40 •

XXXXXXXXXX

41 •

XXXXXXXXXX

42 •

XXXXXXXXXX

43 •

XXXXXXXXXX

44 •

XXXXXXXXXX

45 •

XXXXXXXXXX

XXXXXXXXXX

NOVNS

COMBINE HYDROGRAPHS

ISTAO 3 COMP 1ECON 1720L 301 1NAME 0

| SUM OF 2 HYDROGRAPHS AT 3 | | | | | | | | | |
|--|---------|---------|---------|--------|---------|---------|---------|---------|---------|
| 2070. | 1992. | 2036. | 1939. | 1889. | 1540. | 1792. | 1764. | 1701. | 1657. |
| 1614. | 1533. | 1572. | 1909. | 3110. | 5070. | 7591. | 10214. | 12500. | 12427. |
| 17284. | 41556. | 25477. | 64584. | 91403. | 116503. | 134218. | 140862. | 135811. | 131219. |
| 103453. | 87409. | 73971. | 62944. | 53751. | 46021. | 39425. | 33741. | 28872. | 24700. |
| 21443. | 19841. | 18441. | 17153. | 15993. | | | | | |
| PEAK 9-HOUR 24-HOUR 72-HOUR TOTAL VOLUME | | | | | | | | | |
| CFS 140962. | 128235. | 116371. | 53368. | | | | | | |
| INCHES 1.22 | 6.10 | 1.79 | | | | | | | |
| AC-FT 68632. | 220937. | 347141. | 430510. | | | | | | |

#OVF*

STATION 3

INFLOW 1.1 SAIFLO 3. ANN 08582429 FLOW 2
C. 2000J. 4000J. 6000J. 8000J. 10000J. 12000J. 14000J. 16000J. 18000J.

XXXXXX0.

1. 1

XXXXXX0.

2. 1

XXXXXX0.

3. 1

XXXXXX0.

4. 1

XXXXXX0.

5. 1

XXXXXX0.

6. 1

XXXXXX0.

7. 1

XXXXXX0.

8. 1

XXXXXX0.

9. 1

XXXXXX0.

10. 1

XXXXXX0.

11. 1

XXXXXX0.

12. 1

XXXXXX0.

13. 1

XXXXXX0.

14. 1

XXXXXX0.

15. 1

XXXXXX0.

16. 1

XXXXXX0.

17. 1

XXXXXX0.

18. 1

XXXXXX0.

19. 1

XXXXXX0.

20. 1

XXXXXX0.

21. 1

XXXXXX0.

22. 1

XXXXXXXXX0..

23 .

XXXXXXXXX0..

24 .

XXXXXXXXX0..

25 .

XXXXXXXXXC..

26 .

XXXXXXXXX0..

27 .

XXXXXXXXX0..

28 .

XXXXXXXXX0..

29 .

XXXXXXXXX0..

30 .

XXXXXXXXX0..

31 .

XXXXXXXXXC..

32 .

XXXXXXXXX0..

33 .

XXXXXXXXX0..

34 .

XXXXXXXXX0..

35 .

XXXXXXXXXC..

36 .

XXXXXXXXX0..

37 .

XXXXXXXXX0..

38 .

XXXXXXXXX0..

39 .

XXXXXXXXX0..

40 .

XXXXXXXXX0..

41 .

XXXXXXXXXC..

42 .

XXXXXXXXX0..

43 .

XXXXXXXXX0..

44 .

XXXXXXXXX0..

45 .

XXXXXXXXX0..

46 .

www.elsevier.com/locate/jmb

JPLI JPT HAVE

100

TSK STORA

| | 0. | 76446. | 154716. | 207510. | 261872. | 316354. | 371375. | 426754. | 483006. | 5295234. |
|---------|----|--------|---------|---------|---------|---------|---------|---------|---------|----------|
| STORAGE | 0. | 76446. | 154716. | 207510. | 261872. | 316354. | 371375. | 426754. | 483006. | 5295234. |
| OUTFLOW | 0. | 7940. | 23150. | 35570. | 50574. | 74724. | 97420. | 119801. | 142240. | 164220. |

207
EOP 3.1

372
020
970

7997
7998
7999

[illegible]

2043.
2035.

| | |
|--|--------|
| | 2020. |
| | 2021c. |

7-26159

1957.
2009.

2362

[illegible][illegible][illegible]

11678
11677
11676
11675
11674
11673
11672
11671
11670
11669
11668
11667
11666
11665
11664
11663
11662
11661
11660
11659
11658
11657
11656
11655
11654
11653
11652
11651
11650
11649
11648
11647
11646
11645
11644
11643
11642
11641
11640
11639
11638
11637
11636
11635
11634
11633
11632
11631
11630
11629
11628
11627
11626
11625
11624
11623
11622
11621
11620
11619
11618
11617
11616
11615
11614
11613
11612
11611
11610
11609
11608
11607
11606
11605
11604
11603
11602
11601
11600
11599
11598
11597
11596
11595
11594
11593
11592
11591
11590
11589
11588
11587
11586
11585
11584
11583
11582
11581
11580
11579
11578
11577
11576
11575
11574
11573
11572
11571
11570
11569
11568
11567
11566
11565
11564
11563
11562
11561
11560
11559
11558
11557
11556
11555
11554
11553
11552
11551
11550
11549
11548
11547
11546
11545
11544
11543
11542
11541
11540
11539
11538
11537
11536
11535
11534
11533
11532
11531
11530
11529
11528
11527
11526
11525
11524
11523
11522
11521
11520
11519
11518
11517
11516
11515
11514
11513
11512
11511
11510
11509
11508
11507
11506
11505
11504
11503
11502
11501
11500
11499
11498
11497
11496
11495
11494
11493
11492
11491
11490
11489
11488
11487
11486
11485
11484
11483
11482
11481
11480
11479
11478
11477
11476
11475
11474
11473
11472
11471
11470
11469
11468
11467
11466
11465
11464
11463
11462
11461
11460
11459
11458
11457
11456
11455
11454
11453
11452
11451
11450
11449
11448
11447
11446
11445
11444
11443
11442
11441
11440
11439
11438
11437
11436
11435
11434
11433
11432
11431
11430
11429
11428
11427
11426
11425
11424
11423
11422
11421
11420
11419
11418
11417
11416
11415
11414
11413
11412
11411
11410
11409
11408
11407
11406
11405
11404
11403
11402
11401
11400
11399
11398
11397
11396
11395
11394
11393
11392
11391
11390
11389
11388
11387
11386
11385
11384
11383
11382
11381
11380
11379
11378
11377
11376
11375
11374
11373
11372
11371
11370
11369
11368
11367
11366
11365
11364
11363
11362
11361
11360
11359
11358
11357
11356
11355
11354
11353
11352
11351
11350
11349
11348
11347
11346
11345
11344
11343
11342
11341
11340
11339
11338
11337
11336
11335
11334
11333
11332
11331
11330
11329
11328
11327
11326
11325
11324
11323
11322
11321
11320
11319
11318
11317
11316
11315
11314
11313
11312
11311
11310
11309
11308
11307
11306
11305
11304
11303
11302
11301
11300
11299
11298
11297
11296
11295
11294
11293
11292
11291
11290
11289
11288
11287
11286
11285
11284
11283
11282
11281
11280
11279
11278
11277
11276
11275
11274
11273
11272
11271
11270
11269
11268
11267
11266
11265
11264
11263
11262
11261
11260
11259
11258
11257
11256
11255
11254
11253
11252
11251
11250
11249
11248
11247
11246
11245
11244
11243
11242
11241
11240
11239
11238
11237
11236
11235
11234
11233
11232
11231
11230
11229
11228
11227
11226
11225
11224
11223
11222
11221
11220
11219
11218
11217
11216
11215
11214
11213
11212
11211
11210
11209
11208
11207
11206
11205
11204
11203
11202
11201
11200
11199
11198
11197
11196
11195
11194
11193
11192
11191
11190
11189
11188
11187
11186
11185
11184
11183
11182
11181
11180
11179
11178
11177
11176
11175
11174
11173
11172
11171
11170
11169
11168
11167
11166
11165
11164
11163
11162
11161
11160
11159
11158
11157
11156
11155
11154
11153
11152
11151
11150
11149
11148
11147
11146
11145
11144
11143
11142
11141
11140
11139
11138
11137
11136
11135
11134
11133
11132
11131
11130
11129
11128
11127
11126
11125
11124
11123
11122
11121
11120
11119
11118
11117
11116
11115
11114
11113
11112
11111
11110
11109
11108
11107
11106
11105
11104
11103
11102
11101
11100
11099
11098
11097
11096
11095
11094

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.

29235
34935

[illegible]

$\frac{d}{dt} \left(\frac{1}{\rho} \right) = - \frac{1}{\rho^2} \frac{d\rho}{dt}$

1. The first step in the process of identifying a problem is to define the problem. This involves identifying the symptoms of the problem and determining the scope of the problem. Once the problem has been defined, the next step is to identify the causes of the problem. This involves identifying the factors that are contributing to the problem and determining the underlying causes. Once the causes have been identified, the next step is to develop a plan to address the problem. This involves identifying the actions that need to be taken to address the problem and determining the resources that will be needed to implement the plan. Finally, the last step in the process is to implement the plan and monitor the results. This involves putting the plan into action and tracking the progress of the plan to ensure that the problem is being addressed effectively.

4
 1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 5

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

| | | | |
|----|--------|--------|-------|
| 31 | 22442. | 11236. | 3992. |
| 32 | 22576. | 3541. | 3203. |
| 33 | 24252. | 5050. | 4515. |
| 34 | 25089. | 6271. | 4782. |
| 35 | 25272. | 5823. | 5007. |
| 36 | 25351. | 5889. | 5420. |
| 37 | 25185. | 4272. | 4754. |
| 38 | 24931. | 3554. | 4723. |
| 39 | 24537. | 5130. | 4608. |
| 40 | 24076. | 2691. | 4446. |
| 41 | 23503. | 2317. | 4336. |
| 42 | 23035. | 2042. | 4156. |
| 43 | 22452. | 1914. | 4042. |
| 44 | 21912. | 1775. | 3903. |
| 45 | 21371. | 1654. | 3754. |

SUM 843631.

| | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
|--------|--------|--------|---------|---------|--------------|
| CFS | 48210. | 48152. | 46841. | 33288. | 843631. |
| INCHES | | 0.42 | 1.66 | 3.52 | 3.72 |
| AC-FY | | 23889. | 93153. | 197942. | 202273. |

OVF

STATION 4

INFLOW I, OUTFLOW O, AND OBSERVED FLOW *

0. 20000. 40000. 60000. 80000. 100000. 120000. 140000. 0. 0. 0.

XXXXXXXXX.

1. I XXXXXXXX.

2. I XXXXXXXX.

3. I XXXXXXXX.

4. I XXXXXXXX.

5. I XXXXXXXX.

6. I XXXXXXXX.

7. I XXXXXXXX.

8. I XXXXXXXX.

9. I XXXXXXXX.

10. I XXXXXXXX.

11. I XXXXXXXX.

12. I XXXXXXXX.

13. I XXXXXXXX.

14. I XXXXXXXX.

15. I XXXXXXXX.

16. I XXXXXXXX.

17. I XXXXXXXX.

18. I XXXXXXXX.

19. I XXXXXXXX.

20. I XXXXXXXX.

21. I XXXXXXXX.

22. I XXXXXXXX.

XXXXXX0.

23

XXXXXX0.

24

XXXXXX0.

25

XXXXXX0.

26

XXXXXX0.

27

XXXXXX0.

28

XXXXXX0.

29

XXXXXX0.

30

XXXXXX0.

31

XXXXXX0.

32

XXXXXX0.

33

XXXXXX0.

34

XXXXXX0.

35

XXXXXX0.

36

XXXXXX0.

37

XXXXXX0.

38

XXXXXX0.

39

XXXXXX0.

40

XXXXXX0.

41

XXXXXX0.

42

XXXXXX0.

43

XXXXXX0.

44

XXXXXX0.

45

XXXXXX0.

46

RUNOFF SUMMARY, AVERAGE FLOW

| | | PEAK | 6-1-00R | 24-HOUR | 72-HOUR | AREA |
|---------------|---|---------|---------|---------|---------|---------|
| HYDROGRAPH AT | 1 | 23514. | 22096. | 17278. | 8059. | 114.00 |
| ROUTED TO | 2 | 23130. | 22907. | 17184. | 8037. | 114.00 |
| HYDROGRAPH AT | 2 | 40667. | 40520. | 35175. | 21669. | 377.00 |
| 2 COMBINED | 2 | 61436. | 61279. | 51679. | 29510. | 441.00 |
| ROUTED TO | 3 | 60899. | 50857. | 51465. | 29488. | 491.00 |
| HYDROGRAPH AT | 3 | 79967. | 79281. | 65544. | 34621. | 504.00 |
| 2 COMBINED | 3 | 140862. | 138336. | 116371. | 63248. | 1055.00 |
| ROUTED TO | 4 | 48210. | 48152. | 43941. | 33248. | 1055.00 |

APPENDIX C
PHOTOGRAPHS

Photograph Index

1. Upstream slope from left abutment.
2. Downstream slope and left abutment. Note control and intake buildings, emergency spillway weir, and power house.
3. Emergency spillway approach channel and weir looking upstream.
4. Emergency spillway approach channel weir and powerhouse.
5. Outlet end of Three 8 foot diameter outlet pipes and two siphons.
6. Downstream channel - tail water of Lake Luzerne.




PLATE 1



PLATE 2




PLATE 3



PLATE 5



PLATE 6

APPENDIX D

PERTINENT CORRESPONDENCE AND REPORTS

STATE OF NEW YORK—HUDSON RIVER REGULATING DISTRICT

SUBJECT

Stephen Spelling

FILE NO.

ACC. NO.

SHEET

WORK BY

*COOPER, J.C.**Sch*19 *21*

CHECKED BY

19

MADE IN CONNECTION WITH

REFERENCE

CONT'D FROM ACC.

Assume for 15' discharge 15' discharge 300 ft. $V = 11.6$ ft. per sec.
for $X = 20$ for 27' discharge

$$\begin{aligned}
 Y &= \left(11.6 \times 300 \times 37^\circ \times \frac{1}{11.6} \right) + 16.08 \left(\frac{2}{11.6 \times 300} \right)^2 \\
 &= \left(11.6 \times 5.57 \times \frac{2}{11.6 \times 300} \right) + 16.08 \left(\frac{2}{11.6 \times 300} \right)^2 \\
 &= (22.1 \times 0.58) + (16.08 \times 0.58) \\
 &= 1.317 + 0.5 = 1.817'
 \end{aligned}$$

For $X = 40$

$$\begin{aligned}
 Y &= 22.1 \times \frac{1}{11.6 \times 300} + 16.08 \left(\frac{4}{11.6 \times 300} \right)^2 \\
 &= 22.1 \times \frac{1}{11.6} + 16.08 \times \frac{1}{11.6^2} = 2.946
 \end{aligned}$$

For $X = 60$

$$\begin{aligned}
 Y &= (22.1 \times \frac{6}{11.6}) + 16.08 \left(\frac{6}{11.6} \right)^2 \\
 &= (22.1 \times 0.517) + (16.08 \times 0.25) = 1.15 + 0.40 = 1.55'
 \end{aligned}$$

For $X = 80$

$$\begin{aligned}
 Y &= (22.1 \times \frac{8}{11.6}) + 16.08 \left(\frac{8}{11.6} \right)^2 \\
 &= (22.1 \times 0.687) + 16.08 \times 0.47 = 15.26 + 7.62 = 22.88'
 \end{aligned}$$

Assume for 15' discharge 15' discharge 300 ft. $V = 11.6$ ft. per secondThen for $X = 80$

$$\begin{aligned}
 Y &= (13.9 \times 0.687) + (16.08 \times 0.47) \\
 &= 9.54 + 7.62 = 17.16'
 \end{aligned}$$

SUBJECT

Lipton Spillway

FILE NO.

ACC. NO.

SHEET 4

WORK BY

Wentfall

Sept.

1927

CHECKED BY

19

MADE IN CONNECTION WITH

REFERENCE

CONT'D FROM ACC.

Path of water after leaving jump in spillway

$$\text{Vertical drop} = (V \sin \theta) \left(t + \frac{1}{2} g t^2 \right)$$

V = velocity in feet per second

θ = angle velocity makes with curve at point where water leaves spillway with horizontal

t = time in sec.

Horizontal distance


X

V cos θ

V cos θ

X = Horizontal distance

Y = Vertical drop



BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY 7, N. Y.

TELEPHONE: 2-3491

WARD RUSSO, President

THOMAS MILLER

RAYMOND I. BORST

Members of the Board

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Council

Hadley, N.Y.

May 1, 1947.

Mr. E. H. Sargent, Chief Engineer,
Hudson River Regulating District,
11 North Pearl St.,
Albany, N.Y.

Dear Mr. Sargent:

I have made the annual measurement of the
settlement of the Conklingville Dam this morning with the following
results.

ELEVATION OF SETTLEMENT PIPES AT CONKLINGVILLE DAM

| Date | 105 - 00 | | 109 - 00 | | Remarks |
|---------|----------|--------|----------|--------|----------------|
| | 17.15' | 17.94' | 15.42' | 17.28' | |
| | Left | Right | Left | Right | |
| 5/21/30 | 794.91 | 794.83 | 794.77 | 794.90 | Original Elev. |
| 5/1/46 | 794.16 | 793.92 | 793.93 | 793.86 | Last year |
| 5/1/47 | 794.16 | 793.99 | 793.90 | 793.85 | This year |

ELEVATION DIFFERENCES

| | | | | |
|------|------|------|------|---------------|
| 0.00 | 0.00 | 0.02 | 0.01 | Last year |
| 0.75 | 0.84 | 0.87 | 1.03 | Total to date |

Average settlement to date - 0.872 ft.

Very truly yours,

Senior Assistant Engineer

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

TELEPHONE: 4-3491

J. WARD RUSSELL, President

THOMAS MILLER

JOHN M. MOONEY

Members of the Board

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Counsel

Hadley, N.Y.

May 1, 1945.

Mr. E. H. Sargent, Chief Engineer,
Hudson River Regulating District,
11 North Pearl St.,
Albany, N.Y.

Dear Mr. Sargent:

I have made the annual measurement of the settlement of the Conklingville Dam this morning with the following results.

ELEVATION OF SETTLEMENT PIPES AT CONKLINGVILLE DAM.

| Date | 105 - 00 | | 109 - 00 | | Remarks |
|---------|----------|--------|----------|--------|----------------|
| | Left | Right | Left | Right | |
| 5/21/30 | 794.91 | 794.83 | 794.77 | 794.90 | Original Elev. |
| 5/ 2/44 | 794.18 | 794.00 | 793.94 | 793.89 | Last year |
| 5/ 1/45 | 794.17 | 794.00 | 793.93 | 793.88 | This year |

ELEVATION DIFFERENCES

| | | | | |
|------|-------|-------|------|---------------|
| 0.01 | 0.005 | 0.015 | 0.01 | Last year |
| 0.74 | 0.83 | 0.84 | 1.02 | Total to date |

Average settlement to date 0.86 feet.

Very truly yours,

Assistant Engineer.

Davidson

BOARD OF HUDSON RIVER REGULATING DISTRICT
11 NORTH PEARL STREET

ALBANY, N. Y.

TELEPHONES { 4-2628
 2-4623

J. WARD RUSSELL, President
WILLIAM E. FITZSIMMONS
THOMAS MILLER
Members of the Board

JOHN J. MURPHY
Secretary-Treasurer
EDWARD H. SARGENT
Chief Engineer
ROSCOE INWIN
Captain

Hedley, N.Y.
May 8, 1942.

Mr. E. H. Sargent, Chief Engineer,
Hudson River Regulating District,
11 North Pearl St.,
Albany, N.Y.

Dear Mr. Sargent:

I made the annual measurement of the settlement
of the Conklingville Dam this afternoon with the following results.

ELEVATION OF SETTLEMENT PIPES AT CONKLINGVILLE DAM.

| Date | 105-00 | | 109-00 | | Remarks |
|---------|----------------|-----------------|----------------|-----------------|--------------|
| | 17.15'
Left | 17.94'
Right | 15.42'
Left | 17.28'
Right | |
| 5/21/30 | 794.91 | 794.83 | 794.77 | 794.90 | Original El. |
| 5/1/41 | 794.21 | 794.06 | 794.00 | 793.95 | Last year |
| 5/8/42 | 794.21 | 794.04 | 793.99 | 793.94 | This year |

ELEVATION DIFFERENCES

| | | | | |
|------|------|------|------|---------------|
| 0.00 | 0.02 | 0.01 | 0.01 | Last year |
| 0.70 | 0.79 | 0.78 | 0.95 | Total to date |

Average settlement to date 0.81 feet.

Very truly yours,

H. B. Davidson
Assistant Engineer.

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

TELEPHONES { 4-2625
3-4633

J. WARD RUSSELL, President
WILLIAM E. FITZSIMMONS
THOMAS MILLER
Members of the Board

JOHN J. MURPHY
Secretary-Treasurer
EDWARD H. SARGENT
Chief Engineer
ROSCOE IRWIN
Council

Hadley, N.Y.
May 1, 1941.

Mr. E. H. Sargent, Chief Engineer,
Hudson River Regulating District,
11 North Pearl St.,
Albany, N.Y.

Dear Mr. Sargent:

I made the annual measurement of the settlement
of the Conklingville Dam this morning with the following results.

ELEVATION OF SETTLEMENT PIPES AT CONKLINGVILLE DAM.

| Date | 105-00 | | 109-00 | | Remarks |
|---------|----------------|-----------------|----------------|-----------------|--------------|
| | 17.15'
Left | 17.94'
Right | 18.42'
Left | 17.28'
Right | |
| 5/21/30 | 794.91 | 794.83 | 794.77 | 794.90 | Original El. |
| 5/2/40 | 794.23 | 794.06 | 794.02 | 793.97 | Last year |
| 5/1/41 | 794.21 | 794.06 | 794.00 | 793.93 | This year |

ELEVATION DIFFERENCES

| | | | | |
|------|------|------|------|---------------|
| 0.02 | 0.00 | 0.02 | 0.02 | Last year |
| 0.70 | 0.77 | 0.77 | 0.95 | Total to date |

Average settlement to date 0.80 feet.

Very truly yours,

H. B. Davidson
Assistant Engineer.

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

TELEPHONES { 4-2625
3-4623

JAMES C. McDONALD, President

J. WARD RUSSELL

WILLIAM E. FITZSIMMONS

Members of the Board

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Council

FIELD OFFICE

XXXXXXXXXXXX

Conklingville, N.Y.

August 2, 1938.

Mr. E. H. Sargent, Chief Engineer,
Hudson River Regulating District,
11 North Pearl St.,
Albany, N.Y.

Dear Mr. Sargent:

Enclosed, please find two pictures forming a
panorama of the Conklingville Dam Spillway and showing the normal
seepage during the month of May.

Water in the reservoir at this time varied from
Elevation 764.45 on May 1 to Elevation 766.63 on June 1.

- 1 Shows seepage between west concrete wall of logway and
underlying rock El. 751 approx.
- 2 Shows seepage through and under the stop logs in the
logway El. 756.0
- 3 Shows seepage through rock seams at Sta. 10+50 El. 749 approx.
- 4 Shows seepage through rock seams at Sta. 11+10 El. 751 approx.
- 5 Shows seepage through construction joint in spillway concrete
at Sta. 11+44.3 El. 754.0
- 6 Shows seepage through construction joint in spillway concrete
at Sta. 11+52.3 El. 759.4
- 7 Shows seepage from weep pipe at Sta. 11+99 El. 759.3
Flow estimated at 1 gal. per min.
- 8 Shows seepage from rock seam at Sta. 12+00 El. 756.5
- 9 Shows seepage from weep pipe at El. 764.5 Flow - 1 gal. per min.
- 10 Shows seepage from weep pipe at El. 760.5 Flow - 3 gal. per min.

- 11 Shows seepage from weep pipe at El. 733.8 Flow - 2 gal. per min.
- 12 Shows seepage from Ice Chute between and under stop logs at El. 735.0 Flow estimated at 6 gal. per min.

Very truly yours,

F. B. Davidson

Assistant Engineer,

BOARD OF HUDSON RIVER REGULATING DISTRICT

44 HOWARD STREET

ALBANY, N. Y.

TELEPHONES 3-1291
4-2625

HENRY M. SAGE, PRESIDENT
W. ELLISON MILLS
DAVID J. FITZGERALD, Jr.

G. WILLIAM McEWAN
Secretary-Treasurer
EDWARD H. SARGENT
Chief Engineer

Field Office
Sacandaga Reservoir
Conklingville, N. Y.
Post Office
Hadley, New York

December 2, 1930.

Mr. E. H. Sargent Chief Engineer
Hudson River Regulating District
44 Howard St.
Albany, N. Y.

Dear Sir:

Following is a record of the elevations of the settlement
pipes in the Conklingville Dam to date.

| Date | Elevations | | | |
|-------------------------|---------------|--------|---------------|--------|
| | 105+0
Left | Right | 109+0
Left | Right |
| May 21, 1930
5/21/30 | 794.91 | 794.83 | 794.77 | 794.80 |
| June 6/12/30 | 794.71 | 794.60 | 794.62 | 794.62 |
| July 7/16/30 | 794.66 | 794.34 | 794.53 | 794.57 |
| Dec. 12/2/30 | 794.56 | 794.46 | 794.49 | 794.49 |

| Days Difference | Settlement Elevations | | | | Average |
|-----------------|-----------------------|------|------|------|---------|
| 22 | 0.20 | 0.23 | 0.15 | 0.26 | 0.22 |
| 34 | 0.06 | 0.06 | 0.04 | 0.05 | 0.05 |
| 139 | 0.10 | 0.08 | 0.09 | 0.09 | 0.09 |

Depth of fill at 105+0 left 90'
Depth of fill at 105+0 right 91'
Depth of fill at 109+0 left 114'
Depth of fill at 109+0 right 113'

Very truly yours,

H. H. Davidson

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

**TELEPHONES 4-2625
3-4623**

**JAMES C. McDONALD
J. WARD RUSSELL**

Members of the Board

JOSIAH H. DANFORTH,

Member of the Board.

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Counsel

Conklingville, N.Y.

April 12, 1935.

Mr. L. B. Westfall Office Engineer
Hudson River Regulating District
11 North Pearl St.
Albany, N.Y.

Dear Mr. Westfall:

Enclosed, herewith, is the information requested by you on April 10 in regard to the Asphalt Grouting at the Conklingville Dam.

Sheet 1 was taken from the log of the well holes as driven on the center line of the dam and shows the total depths of holes below the ground surface at the time of drilling and the depths to the various seams encountered.

Sheet 2, the blueprint, is a profile on the center line of the dam showing the well holes as driven and the seams encountered. IN indicates drill water lost from hole. EW indicates ground water entering the drill hole. The pencil line shows the bottom of the cut off trench as excavated into the ledge.

Sheet 3 is a record of the quantity and grade of asphalt and pressures used in the deep well hole on the center line of the dam from information furnished by the American Asphalt Grouting Co.

Sheet 4 is taken from the field notes locating the jackhammer holes drilled for surface treatment with asphalt grout.

Sheet 5 shows the location of the field notes on sheet 4 and the numbering of the jackhammer holes.

Sheet 6 shows the approximate location of the jackhammer holes within the area under the bridge abutment concrete. I could find no field location notes for these but know they were spotted for drilling very close to where shown subject to some slight variation due to difficulty of starting the drill steel at the point indicated.

Sheet 7 is a copy of the reports turned in by the American Asphalt Grouting Co. operator on the surface grouting. I found from my own records that 15 holes were grouted in the bridge abutment face and 29 holes between the face and the water in the wall which checks both the operator's record and the field location of the holes.

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

**TELEPHONES 4-2623
3-4523**

**JAMES C. McDONALD
J. WARD RUSSELL**

Members of the Board

JOSIAH H. DAHNFORTH,

Member of the Board.

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Counsel

-2-

If this does not cover the information you need, let me know
as I have most of the correspondence concerning the job here as well as the proposal
for the work and the cost of the asphalt.

Very truly yours,

T. B. Davidson

Assistant Engineer

*VP
Rec'd 11/4/33
B. B. B.*

STATE OF NEW YORK-HUDSON RIVER REGULATING DISTRICT

SUBJECT

Record of Asphalt Grouting Done on Conklingville Dam
by American Asphalt Grouting Co., Chattanooga, Tenn.

FILE

ACC. NO.

SHEET 3

COMPUTER

19

CHECKED BY

MADE IN CONNECTION WITH

CONT'D FROM ACC.

REFERENCE

| Hole No. | Total Depth | Depth Grouted (Measured from bottom) | Soft Asphalt Injected Grade "E" Drums | Hard Asphalt Injected Grade "G" Drums | Total Asphalt Injected Drums | Maximum Pressure |
|----------|-------------|--------------------------------------|---------------------------------------|---------------------------------------|------------------------------|------------------|
| 1 | 62 | 47½ | 8 | | 8 | 50 |
| 2 | 57 | 49 | 4 | | 4 | 600 |
| 3 | 52 | 40½ | 10 | | 10 | 700 |
| 4 | 52 | 41½ | 1½ | | 1½ | 700 |
| 5 | 52 | 41 | 2½ | | 2½ | 700 |
| 6 | 55 | 46 | 6½ | 3 | 11½ | 300 |
| 7 | 53 | 39½ | 1½ | | 1½ | 700 |
| 8 | 52 | 37 | 5 | | 5 | 700 |
| 9 | 50 | 41½ | 2 | | 2 | 700 |
| 10 | 54 | 33 | 2 | | 2 | 700 |
| 11 | 71 | 40 | 2 | | 2 | 700 |
| 12 | 62½ | 54 | 1 | | 1 | 300 |
| 13 | 54 | 20 | | | 13 | 700 |
| 14 | 54 | 22½ | 2½ | 6 | 6½ | 700 |
| 15 | 54 | 30½ | 7 | 6½ | 13½ | 275 |
| 16 | 31 | 2½ | 6½ | 2½ | 9 | 700 |
| 17 | 38 | 26½ | 2 | | 2 | 700 |
| 18 | 36 | 20 | 2 | | 2 | 700 |
| 19 | 39 | 15½ | 4 | 7 | 11 | 150 |
| 20 | 31½ | 12½ | 2 | 3 | 5 | 350 |
| 21 | | No Attempt. | | | | |
| | | | 72 | 20 | 113 | |

COMPLETE FILING SYMBOL

Remarks:

Hole No. 1 Pressure limited on account of proximity to edge of spillway.

Hole No. 2 Pressure limited by easy opening to overburden.

Hole No. 15, 19, 20 Pressure limited by easy opening to overburden.

One drum equals approximately 7 cu. ft.

Hole No. 15 There was no record of the kind of asphalt used at the amount used above, in the Total or any which explains the discrepancy in totals, the hard and soft asphalt columns.

Cont'd on P. 4

STATE OF NEW YORK-HUDSON RIVER REGULATING DISTRICT

SUBJECT

Log of Deep Well Holes for Asphalt Grouting
Conklingville Dam

FILE

ACC. NO.

SHEET 1

COMPUTER

19

CHECKED BY

MADE IN CONNECTION WITH

REFERENCE

Bk. 89 Pg. 25 & Well Hole Log

CONT'D FROM ACC.

COMPLETE FILING SYMBOLS:

| Well Hole No. | Elev. of Grouting at top of hole. | Total Depth | Depths to seams. |
|---------------|-----------------------------------|-------------|--|
| 1 | 750.5 | 59 | 7-11-21 |
| 2 | 756.0 | 58 | 7 broken to 9-12-22 |
| 3 | 751.1 | 56 | 4-11-13 broken to 17-24-30-47 |
| 4 | 749.2 | 53½ | 2 broken to 14-20-49 |
| 5 | 748.6 | 51 | 32-49 |
| 6 | 746.2 | 52 | Earth & rock to 3-6-19-27-40-47-49 |
| 7 | 746.0 | 53 | Earth & rock to 5½-7-19-29-38-51½ |
| 8 | 745.9 | 55 | Earth & rock to 7-14-19-36-49½-53½ broken to 55 |
| 9 | 745.6 | 55 | Earth & rock to 8-22½-39-47 broken to 49-51 |
| 10 | 745.7 | 52½ | Earth & rock to 13-20-45-50 |
| 11 | 745.3 | 61 | Earth & rock to 13-14½ broken to 17½-21-30 broken to 32-50-53-54-57 broken to 59 |
| 12 | 745.3 | 60 | Earth & rock to 19-30-43-50 broken to 58 |
| 13 | 745.1 | 60 | Earth & rock to 25-45 |
| 14 | 741.0 | 54 | Earth & rock to 18-46 broken to 47 |
| 15 | 736.0 | 54 | Earth & rock to 15-17 broken to 19-25 broken to 29-37 |
| 16 | 731.3 | 35 | Earth & rock to 12½-25 broken to 29 |
| 17 | 717.2 | 47 | Earth & rock to 6-19-21 |
| 18 | 714.0 | 16 | Earth & rock to 8 |
| 19 | 710.6 | 39 | Earth & rock to 10-14-19-24 |
| 20 | 705.9 | 34 | Earth & rock to 17 |
| 21 | 704.2 | 33 | Earth & rock to 23-26 |

STATE OF NEW YORK-HUDSON RIVER REGULATING DISTRICT

SUBJECT

Location of Jackhammer Holes for Asphalt Grouting at
Conklingville Dam.

FILE

ACC. NO.

SHEET 4

COMPUTER

19

CHECKED BY

19

MADE IN CONNECTION WITH

REFERENCE Bk.111 Pg.25-26

Cont'd from Acc.

Instrument at 7+00 at 74.65' Right

0+00' south on center line of Dam

Hor.Angle

Hor.Dist.

Elev.

240-20

11.7

729.8

188-06

7.7

727.8

122-30

10.8

727.3

141-39

13.8

729.2

189-50

10.0

731.9

Well Hole

185-55

12.6

733.4

225-14

15.2

736.4

211-48

18.9

738.3

185-24

15.0

734.2

Well Hole

182-33

17.1

734.2

152-13

17.8

732.2

162-02

22.0

732.8

162-24

22.2

736.4

168-44

20.0

735.2

Well Hole

203-34

23.0

738.7

198-38

27.3

741.3

181-00

25.0

739.1

Well hole

181-00

25.6

739.7

161-02

26.6

737.1

548-37

10.1

717.2

Well hole

381-08

1.6

728.2

Well Hole

353-40

18.8

709.7

Well Hole

32-15

18.6

709.3

355-19

18.9

707.8

329-23

23.1

707.1

322-46

19.1

710.1

351-25

15.0

712.6

61-00

14.1

715.6

64-21

10.2

721.0

350-28

7.7

719.3

311-41

14.8

715.7

293-45

11.8

722.9

342-48

5.7

721.3

Well Hole

344-47

3.0

724.1

94-11

9.3

723.3

190-17

4.2

727.2

Well Hole

210-12

2.1

727.0

259-15

10.2

733.9

COMPLETE FILING SYMBOLS

Cont'd from Acc.

STATE OF NEW YORK-HUDSON RIVER REGULATING DISTRICT

SUBJECT

Copy of Field Reports Submitted by American Asphalt
Grouting Co. Operator.

FILE

Acc. No.

SHEET 7

COMPUTER

19

CHECKED BY

19

MADE IN CONNECTION WITH Surface Grouting at Conklingville Dam

CONT'D FROM Acc.

REFERENCE

May 25 1929

Kettle placed - 12 holes drilled - 6 pipe installed as per sketch.

Upstream No. 4

Center Line No. 4 & 5

Downstream No. 3, 4, 5

All holes 10 feet in rock except Upstream No. 4 which had broken drill steel in it.

All pipe perforated 4 feet at bottom.

June 2 1929

All holes in each line from No. 1 to 5 inclusive grouted.

Used 9 drums of asphalt filling practically all cracks.

Used 600 lbs. pressure.

Hole No. 2 in downstream line took 3 drums of asphalt. Asphalt came out about 15 feet away from hole also filled big crack back by other holes.

Some of the holes took hardly any asphalt except enough to fill the pipe.

June 3 1929

All holes from No. 6 to 12 inclusive in each line were grouted.

Due to water and dirt being in the way and rock being more solid, grouting was stopped here.

Used 3 drums of asphalt for concrete form as far as grouted that is in Holes 3 to 12 inclusive.

None of the holes took very much of the asphalt.

Holes are numbered with the well holes that had been previously grouted beginning with No. 1 between No. 1 and 2 in the old well hole line.

COMPLETE FILING SYMBOL:

ELEVATION OF SETTLEMENT PIPES AT CONKLINGVILLE DAM.

| Date | 105.00 | | 109.00 | | Reference | Page |
|----------|--------|--------|--------|--------|-----------|------|
| | Left | Right | Left | Right | | |
| 5/21/30 | 794.91 | 794.83 | 794.77 | 794.90 | 111 | 62 |
| 6/12/30 | 794.71 | 794.60 | 794.62 | 794.52 | 111 | 68 |
| 7/16/30 | 794.66 | 794.54 | 794.58 | 794.57 | 111 | 71 |
| 12/ 2/30 | 794.56 | 794.46 | 794.49 | 794.48 | 111 | 74 |
| 6/ 4/31 | 794.49 | 794.33 | 794.35 | 794.33 | 107 | 32 |
| 10/21/31 | 794.48 | 794.33 | 794.35 | 794.33 | 113 | 7 |
| 4/ 9/32 | 794.44 | 794.31 | 794.31 | 794.28 | 113 | 8 |
| 6/10/32 | 794.44 | 794.30 | 794.26 | 794.29 | 113 | 17 |

| Days Diff. | Difference of elevation between tests | | | | Avg. | Rate |
|-------------|---------------------------------------|------|------|------|--------|---------|
| 22 | 0.20 | 0.23 | 0.16 | 0.23 | 0.22 | 0.01000 |
| 34 | 0.05 | 0.06 | 0.04 | 0.05 | 0.05 | 0.00147 |
| 139 | 0.10 | 0.08 | 0.09 | 0.09 | 0.09 | 0.00065 |
| 164 | 0.07 | 0.13 | 0.14 | 0.15 | 0.12 | 0.00065 |
| 139 | 0.01 | 0.00 | 0.03 | 0.00 | 0.0025 | 0.00002 |
| 171 | 0.04 | 0.02 | 0.04 | 0.05 | 0.04 | 0.00023 |
| 123 | 0.00 | 0.01 | 0.01 | 0.00 | 0.005 | 0.00004 |
| Total Diff. | 0.47 | 0.53 | 0.47 | 0.62 | 0.52 | |

BOARD OF HUDSON RIVER REGULATING DISTRICT

11 NORTH PEARL STREET

ALBANY, N. Y.

TELEPHONES 4-2425
3-4423

JAMES C. McDONALD
J. WARD RUSSELL

Members of the Board

JOSIAH H. DANFORTH,

Member of the Board.

JOHN J. MURPHY

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

ROSCOE IRWIN

Counsel

Conklingville, N. Y.
May 1, 1933.

Mr. E. H. Sargent Chief Engineer
Hudson River Regulating District
11 North Pearl St.
Albany, N. Y.

Dear Mr. Sargent:

Below are the results of the elevations taken on
the settlement pipes at the Conklingville Dam on May 1, 1933.

| Date | 108.00 | | 109.00. | | Reference | |
|--|--|--------|----------------|--------|-----------|---------|
| | Left | Right | Left | Right | Book | Page |
| 5/1/33 | 794.21 | 794.27 | 794.25 | 794.23 | 113 | 51 |
| Days Diff. | Diff. of Elev. | | Diff. of Elev. | | Av. | Rate |
| 265 | 0.03 | 0.03 | 0.05 | 0.05 | 0.04 | 0.00015 |
| Total days
Diff. since
first meas. | Total Diff. of Elev. since first meas. | | | | Av. | |
| 1075 | 0.50 | 0.53 | 0.52 | 0.47 | 0.50 | |

Very truly yours,

H. B. Davidson
Assistant Engineer

LOCATION OF

ASPHALT GROUT HOLES

CONKLINGVILLE DAM

SCALE 1" = 4'-0" APRIL 1933 RBD

SHEET 6

WH2

WH1

WH3

Macrostasis
10'

Macrostasis
10'

Center Line

Upstream Line

Downstream Line

7400

2. 1000000

7381-11111
7381

7381

7415

W.H. 6 Sta III + 100 Match line

1-6

W.H. 5

W.H. 5

W.H. 4

W.H. 3

W.H. 4

W.H. 3

W.H. 2

W.H. 3

W.H. 2

W.H. 1

E. H. Sargent

REPORT ON THE NORTH ABUTMENT OF THE CONKLINGVILLE DAM

OF

THE SACANDAGA DEVELOPMENT OF

THE HUDSON RIVER REGULATING DISTRICT.

BY

IRVING B. GOSBY, GEOLOGIST.

APRIL, 1923.

REPORT ON THE NORTH ABUTMENT OF THE CONKLINGVILLE DAM
OF THE SACANDAGA DEVELOPMENT OF THE
HUDSON RIVER REGULATING DISTRICT.

By Irving B. Crosby, Geologist.

INTRODUCTION.

Previous geological and engineering reports and studies of this dam site have taken up the question of the origin and characteristics of the unconsolidated deposits along the banks and in the river bed, but have paid little attention to the bed rock in the north abutment, the only part of the dam where rock is at the surface.

This rock is a granite gneiss and although cracks could be seen in the natural ledges it had been supposed that the rock would be more solid below the surface. However, excavation for the spillway channel has disclosed the disturbing fact that the shattered condition of the rock continues to some depth and therefore it was decided to have a geological investigation made of this condition.

On account of the above mentioned reason this report is almost entirely confined to the bed rock of the north abutment.

SUMMARY.

The bluff which will form the north abutment of the Conklingville Dam on the Sacandaga River is composed of gneissic granite with a fairly well developed foliation which dips into the bluff. The continuity of the rock is broken by numerous joint cracks most of which can be referred to one of three systems. The joints of one of these systems dip towards the river at an angle of approximately 50° to 55° . These joints form sliding planes along which slides may occur if the rock is undermined.

The joint cracks extend downward indefinitely and although the crack may be less open at considerable depths the continuity of the rock is broken and planes of weakness exist.

At the depth to which it is proposed to carry the excavation for the spillway channel it is probable that the rock will still be much broken although it is possible that the sliding planes will be farther apart and the masses will be larger.

The excavation of the spillway channel, with the north wall much steeper than the dip of the sliding planes the strike of which is nearly parallel to it, will leave a large triangular shaped mass of rock without any support except the friction on the sliding planes. If this condition is brought about slides may be expected in the near future.

It is recommended that the north wall of the channel should not be steeper than the slope of the sliding planes which for the purposes of estimates may be considered as 55° .

Well developed joint planes at the right position should be chosen to form the wall of the channel and all rock above these should be removed.

It will be necessary to carry the foundations for the retaining wall down to a depth where the rock appears fairly solid and if this is done the sliding planes will probably cause no trouble as there will be no danger of the rock being undermined. As the sliding planes under the retaining wall will dip away from the spillway channel the presence of the latter will not render the rock under the retaining wall unstable.

GENERAL GEOLOGY OF THE DAM SITE.

The bed rock of the dam site is a granite in which a foliation or gneissic structure has been produced to a varying degree. This granite was intruded into limestone which accounts for the fact that there are occasional inclusions of limestone in the granite. These conditions are much more pronounced to the west and northwest of Conklingville. The rock at the dam site has the composition of granite and has a gneissic structure-- therefore it is properly designated as a gneissic granite. It is composed of feldspar, quartz, biotite or black mica and hornblende. From an engineering point of view this rock is not as desirable as a granite without the gneissic structure because it is somewhat liable to break into platy pieces but this tendency is not marked and will probably not interfere with its use as concrete aggregate.

The structure of the granite is variable but at the dam site the dip of the foliation averages 45° to the N. E. More important in relation to the stability of the dam is the jointing which divides the rock into blocks of varying size. These joint cracks may be referred to three systems of fairly uniform dip and strike and there are other joints which do not belong to any of these systems. In fact it is the jointing which has made this investigation necessary. These joint systems will be described more fully in the

next section.

Most of the surface rocks of the earth are broken up by joint cracks but here, at the north abutment of the dam, the rocks as exposed by excavations, present an unusually shattered appearance and this condition requires an explanation.

The profile of the mountain above the dam shows that there is a nearly flat bench at an elevation of about 1000'. One set of joint cracks is parallel with the surface of the bluff above the river and also with the face of the bluff between the above mentioned bench and the top of the mountain. These joints act as sliding planes and if the bluff is undermined great rock slides will occur. During the glacial period the ice removed a great amount of rock from the base of the mountain slope, forming steep cliffs and leaving a large mass of rock unsupported except for friction along the joint planes. It appears probable that when the ice melted away a section of the mountain slid down into the valley. The mass which slid was so large that it was not broken into separate blocks although it was much cracked. This explanation of the shattered condition of the bluff at the dam site cannot be absolutely proved but the known facts strongly suggest that the spur of the mountain against which the dam will abut has been much disturbed and shattered, and in any case the observable facts show that the rock at the north abutment of the dam is not sound but is much more cracked and broken than would normally be expected in a

rock of this character.

The valley bottom and much of the hillsides are covered with various types of glacial drift which were deposited at the end of the ice age; but the investigation and description of these deposits is outside the scope of this report.

GEOLOGY OF THE NORTH ABUTMENT.

The gneissic granite bed rock of the north abutment is cut and divided into blocks of varying sizes by joint cracks which run in several directions. The direction or strike, and inclination to the horizontal or dip of these joint cracks are very important factors which directly control the stability of the abutment. If the joint cracks were all horizontal or vertical with none inclined then the hillside would be comparable with a wall of masonry laid up dry and would be stable except in the case of severe earth movements but such is not the case here as the cracks are not horizontal but are inclined towards the river.

Numerous observations were made on the strike and dip of these joints and on the foliation, using a Brunton Compass, and the directions as given are all referred to the Magnetic North. For convenience in comparing these directions with the course of the spillway channel and the center line of the dam it was determined that the direction of the center line of the spillway channel between stations 9 and 10 is $N 57^{\circ} W$.

The foliation of the granite is not perfect enough to greatly weaken the rock and it dips back into the bluff away from the river and is not a source of weakness in the abutment. The strike of the foliation is $N 60^{\circ} W$ and the dip $45^{\circ} N. E.$ Further consideration of it is not necessary in this problem except as it affects the use of the rock as concrete aggregate.

The joints fall into five groups three of which appear to be fairly well developed systems. For convenience these

will be numbered. System 1 has an average strike of N 65° W and an average dip of 50° to 55° to the S. W. The strike varies from 60° to 70° north of west and the dip from 42° to 68° to the southwest. This is the most important of the three joint systems in its relation to the dam and to the spillway channel because the joint planes are practically parallel to the surface of the bluff in the north abutment and they thus form sliding planes down which masses of rock will probably slide if they are undermined by the removal of the supporting rock.

The second system has a strike of 60° to 65° west of north and a dip of from 45° to 80° to the northeast. The average dip for this system is about 65° N. E. The strike is practically the same as for the first system but the dip is in the opposite direction. The effect of this system of joint planes is to break the continuity of the rock at right angles to the dip of the sliding planes and thus make it easier for separate blocks to slide out of place. The joints of this system seem to be the most regularly developed of any of the systems.

The third system is nearly at right angles with the first system having an average strike of N 20° E and a dip of 80° N. to vertical. This is the least well developed of the three systems but it is effective in further dividing up the rock into blocks which will slide easily when their support is removed.

Other joints were found with strikes of N 20° W and dips of 80° W and also with strikes of N 60° E and dips of 80° N. W. These stray joint cracks increase the lack of continuity in the rock and reduce its strength.

To add to the shattered and unstable condition many of these cracks are open thus permitting water to enter. When this water freezes it exerts a tremendous force on the blocks prying the cracks open wider and rendering the mass less stable.

The cores from ten drill holes, numbers 117, 118, 201, 203, 204, 205, 206, 207, 208 and 210 were examined and it was found that there were few long pieces of core, none over a foot long, and that most of it was in very short pieces. Despite this the core recovery was fairly high for most of the holes which indicates that the rock where unbroken is sound but that there are many cracks which cause the cores to break into small pieces.

The north abutment of the dam is on the convex side of a sharp curve in the river and the water has been actively cutting into the bluff and undermining the layers of rock thus allowing blocks to slide down from time to time. When the dam is built this undercutting by the river will cease and the bluff would be more stable than it has been in the past but the proposed spillway channel will undermine the bluff more than the river would in hun-

dreds of years and will thus bring about a very unstable and dangerous condition.

The spillway channel as first planned would have a north wall about a hundred feet high with a slope of approximately 80° , while the sliding planes dip in the same direction on an average of 50° to 55° . This would leave a triangular shaped mass of rock unsupported except for friction along the sliding planes and water seeping through these joint cracks would act as a lubricant to reduce the friction. In addition every time water froze in the cracks there would be a strong force pushing the blocks down hill. Under these conditions it is certain that large blocks would repeatedly break away and plunge into the spillway channel if, indeed, the entire undermined mass did not slide down in one grand and disastrous rush.

Earthquake shocks of moderate intensity are known to occur occasionally in this region and even a mild shock might act as the trigger to let loose the unstable mass perched on its sliding planes.

It may be argued that these joint cracks will die out at a moderate depth and that the rock will be more solid but such a view is supported neither by accepted geologic theory nor by observation in mines and quarries. The joints of the second and third systems undoubtedly extend downwards to the region where the rocks are plastic and

cracks can not exist. It is believed to be many miles down before such a condition is reached, which means that as far as this problem is concerned the depth of these joint cracks is indefinite. The joints of the first system are practically parallel to the surface of the bluff and these may become more widely spaced and die out with depth but observations in deep quarries prove that at depths of one to two hundred feet and more these joints are well developed but not so closely spaced as at the surface. These facts prove that the most that can be hoped for is that the layers of rock between the sliding planes will be somewhat thicker at the depth of the bottom of the spillway channel.

If the layers of rock in the north abutment are undermined, as will be the case if the spillway channel is excavated as originally planned, slides of a greater or less extent are almost a certainty and probably trouble will begin in a short time, that is, in a few years.

Slides along joint planes or bedding planes where the rocks have been undermined are not rare occurrences. A recent and somewhat similar one occurred during the collapse of the St. Francis Dam in California.* There the planes of schistosity or foliation in the schist were parallel with the slope of the eastern wall of the canyon and furnished sliding planes upon which a great slide occurred when the

* "Geological Formations at the St. Francis Dam Site" by Hyde Forbes. Engineering News-Record, Vol. 100, No. 15, pp 20-22, 1929.

dam broke and the saturated mass of the east bank was undermined by the rushing waters from the break in the west end of the dam. Of course there is little similarity between the weak schist at the St. Francis Dam with the very pronounced foliation and the strong granite at the Conklingville Dam but there is apparently great similarity between the structures of the two rocks. In one case the sliding planes were formed by the foliation of the schist and in the other case by the joints of the granite.

To sum up the situation in the north abutment: The rock is much divided by joints some of which are practically parallel with the bluff and form sliding planes dipping towards the river. This situation is not dangerous if the base of the bluff is not undermined but the river has been slowly cutting into the base of the bluff and from time to time small slides have undoubtedly occurred. This condition will be stopped by the building of the dam but a much more dangerous condition will be produced by the excavation of the deep spillway channel which will undermine a large mass of rock and leave it without support except friction along the sliding planes.

The measures which are desirable to avoid the dangerous condition above described will be taken up in the next section of this report.

CONCLUSIONS AND RECOMMENDATIONS.

To avoid trouble from the unstable conditions in the north abutment certain precautionary measures and changes of plan are desirable. The most complete remedy for the situation would be to leave the bluff undisturbed and not excavate the spillway channel but there are good engineering reasons why this cannot be done.

When the spillway channel is excavated it will be necessary, in order to avoid the danger of slides, to reduce the slope of the north wall of the channel to that of the sliding planes, that is approximately 50° to 55° . For the purpose of estimating the amount of excavation necessary it is probably safe to call the slope 55° . These joint planes are not true planes but are somewhat wavy and are not exactly parallel to the spillway channel; therefore instead of excavating to a certain angle it will be better to choose a prominent joint plane and remove the rock above that, changing to other planes as the difference in strike between the planes and the spillway channel makes it necessary.

Care should be taken not to shatter the bed rock when excavating and it is recommended that when stripping off the rock above the sliding planes heavy charge of dynamite should be avoided. The joint cracks will facilitate the removal of the rock with less blasting than would otherwise be necessary.

There is a possibility that the joints will be sufficiently far apart at the bottom of the spillway channel so that it will not be necessary to choose a plane which leads to that depth. This should be decided when excavation has disclosed the conditions of the rock. ✓

It is possible to move the spillway channel towards the river and by so doing to decrease the amount of rock to be excavated. Of course such a change in the position of the channel will move the retaining wall nearer the river and will make it more difficult to obtain satisfactory foundations for that wall and will also necessitate more excavation for the foundations. The rock under the retaining wall will of course be broken by joint planes but it will be beyond danger of undermining in the future and if the foundations are carried down to a point where the rock is reasonably solid and has not been disturbed by the undermining action of the river satisfactory foundation conditions should be found.

The natural rock wall on the river side of the channel will not be endangered by the sliding planes as they dip away from it, but the steep joints of the second system nearly coincide with this wall and may well determine its slope.

The north wall of the spillway channel will be unstable and dangerous unless the following conditions are met: This

wall of the channel should not be steeper than the joint planes and all rock which does not have a solid support should be removed.

The changes of plan necessary to meet these conditions are engineering matters but it is urged that if the slope is anywhere made steeper than the sliding planes it should be done only after a very careful examination has been made of the rock at that point.

If the above conditions are provided for it is believed that the abutment will then be in a fairly stable condition and that there will probably be little danger from slides.

All of which is respectfully submitted.

Irving B. Garby

Consulting Geologist.

Boston, Massachusetts,

April 23, 1928.

37-15-4
Rev. 3/77

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
DAM INSPECTION REPORT
(By Visual Inspection)

| Dam Number | River Basin | Town | County | Hazard Class | Date & Inspector |
|------------|--------------|--------|----------|--------------|---------------------------------|
| 415 | Upper Hudson | Malley | SARATOGA | C. + | 1/12/77 G. K. L.
W. C. Jones |

Stream = SARATOGA RESERVOIR

Owner = Hudson-Black River Reservation District

Type of Construction

- ☒ Earth w/Concrete Spillway
☒ Earth w/Drop Inlet Pipe
☐ Earth w/Stone or Riprap Spillway
☐ Concrete
☐ Stone
☐ Timber
☐ Other _____

Use

- ☐ Water Supply
☒ Power
☒ Recreation - ☒ High Density
☐ Fish and Wildlife
☐ Farm Pond
☐ No Apparent Use-Abandoned
☒ Flood Control
☐ Other _____

Estimated Impoundment Size 27,000 Acres /// Estimated Height of Dam above Streambed 73 Ft.

Condition of Spillway

- ☐ Service satisfactory ☒ Auxiliary satisfactory
☒ In need of repair or maintenance ☐ In need of repair or maintenance

Explain: See Attached Memo

Condition of Non-Overflow Section

- ☒ Satisfactory ☐ In need of repair or maintenance

Explain: In good condition

Condition of Mechanical Equipment

- ☒ Satisfactory ☐ In need of repair or maintenance

Explain: _____

Siltation

☐ High

☐ Low

Explain: _____

Remarks: _____

Evaluation (From Visual Inspection)

- ☐ Repairs req'd. beyond normal maint. ☒ No defects observed beyond normal maint.

New York State Department of Environmental Conservation

M E M O R A N D U M

TO:

The Files

FROM:

G. Koch *G.K.*

SUBJECT:

Conklingville Dam #415 Upper Hudson Basin

DATE:

September 26, 1977

On September 22, 1977 I inspected the Conklingville Dam on the Sacandaga Reservoir with Wm. Coleman and Ken Harmer. We met with John Anderson the engineer with the Hudson-Black River Regulating District. Mr. Anderson described the operating procedure at the dam.

Operation

This dam provides flood protection and low flow augmentation to the downstream residents on the Hudson River. The average daily flow through the Niagara Mohawk power development at the dam (E. J. West) is 2000 cfs. From about the middle of March to the middle of April the outlet gates at the Conklingville dam are closed. Water is stored in the reservoir. During this period of high spring runoff virtually no flow enters the Hudson from the Sacandaga River. This reduces the flood threat to the downstream residents by storing water from a 1044 square mile drainage basin. During the summer when flows are low in the Hudson River, water is released at the dam in order to provide a minimum flow of 3000 cfs at the confluence of the Hudson and Sacandaga Rivers at Hadley, NY.

Inspection

The inspection indicated that the dam ^{is} in good condition.

The concrete on the downstream face of the ogee weir spillway has spalled. The concrete on the upstream face and crest of the spillway is in good condition. The regulating district feels that concrete repairs are not necessary unless the deterioration increases to a depth of around six inches. Since this is a massive concrete structure and appears structurally sound, we agree with that conclusion.

Submarine Res.

CONGRATS:

Good condition

STATE OF NEW YORK
DEPARTMENT OFState Engineer and Surveyor
ALBANYReceived Nov 20th 1929Dam No. 515 Hudson WatershedDisposition Approved by 54-1736Serial No. 7-1

Foundation inspected _____

Structure inspected _____

Application for the Construction or Reconstruction of a Dam

Application is hereby made to the State Engineer, Albany, N. Y., in compliance with the provisions of Chapter LXV of the Consolidated Laws and Chapter 647, Laws of 1911, Section 23 as amended, for the approval of specifications and detailed drawings, marked Conklinville Dam, Sacandaga Reservoir =

Accessions 2614, 2615, 2616 and 2617

herewith submitted for the {construction
reconstruction} of a dam located as stated below. All provisions of law will be complied with in the erection of the proposed dam. It is intended to complete the work covered by the application about November 1, 1929.
(Date)

1. The dam will be on Sacandaga River flowing into Hudson River in the town of Nadler, County of Saratoga and at the Head of Conklinville.
(Give exact distance and direction from a well-known bridge, dam, village, city, station, lake or mouth of a stream)

2. The name and address of the owner is State of New York, Hudson River Regulating Dist., Albany, N. Y.

3. The dam will be used for Storage Reservoir

4. Will any part of the dam be built upon or its pond flood any State lands No

5. The watershed at the proposed dam draining into the pond to be formed thereby is 1,000 square miles.

6. The proposed dam will have a pond area at the spillcrest elevation of 26,600 acres and will impound 32,600,000,000 cubic feet of water.

7. The lowest part of the natural shore of the pond is 30 feet vertically above the spillcrest, and everywhere else the shore will be at least 30 feet above the spillcrest.

8. The maximum known flow of the stream at the dam site was 35,500 cubic feet per second on Mar. 29, 1913.
(Date)

9. State if any damage to life or to any buildings, roads or other property could be caused by any possible failure of the proposed dam Yes.

10. The natural material of the bed on which the proposed dam will rest is (c. g., sand, gravel, boulders, granite, shale, slate, limestone, etc.) Granite & gneiss at on glacial deposits will rest on rock. {Granitic gneiss}

NOTE: For data required by 11 and 12, see accompanying maps.

11. The material of the right bank in the direction with the current, is at the spillcrest elevation this material has a top slope of inches vertical to a foot horizontal on the center line of the dam, a vertical thickness at this elevation of feet, and the top surface extends for a vertical height of feet above the spillcrest.

12. The material of the left bank is; has a top slope of inches to a foot horizontal, a thickness of feet, and a height of feet.

13. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing, effect of exposure to air and to water, uniformity, etc. See log of test pits and borings.

For answers to 14, 15 and 16, see geological section.

14. If the bed is in layers, are the layers horizontal or inclined? If inclined what is the direction of the horizontal outcropping relative to the axis of the main dam and the inclination and direction of the layers in a plane perpendicular to the horizontal outcropping.

15. What is the thickness of the layers?

16. Are there any porous seams or fissures?

* 17. WASTES. The spillway of the above proposed dam will be 400 feet long in the clear, the waters will be held at the right end by an earth dam the top of which will be 24 feet above the spillcrest, and have a top width of 40 feet; and at the left end by a spillway and fill and the top of which will be 97.50 feet above the spillcrest and have a top width of available.

* 18. There will be also for flood discharge 3 pipes 96 inches inside diameter and the bottom will be 72 feet below the spillcrest and the bottom will be 72 feet below the spillcrest.

19. APRON. Below the proposed dam there will be an apron built of feet long across the stream, feet wide and feet thick. The downstream side of the apron will have a thickness of feet for a width of feet.

20. PLANS. Each application for a permit of a dam over 12 feet in height must be accompanied by a location map and complete working drawings in triplicate of the proposed structure, one set of which will be returned if they are approved. Each drawing should have a title giving the parts shown, the name of the town and county in which the dam site is located, and the name of the owner and of the engineer.

The location map (U. S. C. Geographical Quadrangle or other map) should show the exact location of the proposed dam; of buildings below the dam which might be damaged by any failure of the dam, of roads adjacent to or crossing the stream below the dam, giving the lowest elevation of the roadway above the stream bed and giving the shape

the height and the width of stream openings; and of any embankments or steep slopes that any flood could pass over. Also indicate the character and use made of the ground below the dam.

The complete working drawings should give all the dimensions necessary for the calculations of the stability of the structure, and all the information asked for below under "Sketches." There may be attached to the application any written reports, calculations, investigations or opinions that may aid in showing the data and method used by the designer. State the assumed ice and uplift pressures and the conditions on which based.

21. **SKETCHES.** For small and unimportant structures, if plans have not been made, on the back of this application make a sketch to scale for each different cross-section at the highest point, giving the height and the depth from the surface of the foundation, the bottom width, the top width (for a concrete or masonry spill at 18 inches below the crest), the elevation of the top in reference to the spillcrest, the length of the section, and the material of which the section is to be constructed, on the spillway section show a cross section of the apron, giving its width, thickness and material, and show the abutment or wash wall at the end of the spillway, giving its height and thickness. Mark each section with a capital letter. Also sketch a plan; show the above sections by their top lines, giving the mark and the length of each; the openings by their horizontal dimensions; the abutments by their top width and top lengths from the upstream face of the spillcrest; and outline the apron. Also sketch an elevation of each end of the dam with a cross section of the banks, giving the depth and width excavated into the banks.

22. **ELEVATIONS.** Also give the elevations, if possible from the Mean Sea Level, of at least two permanent Bench Marks; of the spillcrest for any existing dam on the proposed dam site, at the middle and at the ends of the spill; of the spillcrest for the above proposed dam; and of the spillcrest of any adjacent dams.

23. **SAMPLES.** When so instructed, send samples of the materials to be used in the construction of the proposed dam, using shipping tags which will be furnished. For sand, one-half a cubic foot is desired (exclusive of any stone over $\frac{1}{2}$ inch in size mixed therewith); for cement, three pints; and for the natural bed, twenty cubic inches if of ledge and one-half a cubic foot if of soil.

24. **INSPECTION.** State how inspection is to be provided for during construction. ~~Give attention to...~~
~~be carried out under direction of Assistant Engineer, Chief Engineer and~~
~~Consulting Engineer.~~

25. **WATER SUPPLY.** Are the waters impounded by the above dam to be used for a public water supply? ~~How...~~
Has an application under the provisions of Article III of the Conservation Law for such use been made to the Water Control Commission, Albany, N. Y.?


* 17. In addition to the spillway there are incorporated in the plans, two 8 ft. by 18 ft. siphons pricing at elevation 774.

* 18. The discharging capacity of the spillway and siphons under the assumed maximum flood condition is shown on Computation Attachment W-344, submitted with application.

The above information is correct to the best of my knowledge and belief.

Albany, N. Y.
(Address of signer)

Novemb. 12, 1926.
(Date)



Chief Engineer, Hudson River Regulating Dist.
(If person signing for owner should indicate his title & authority)

STATE OF NEW YORK
DEPARTMENT OF

State Engineer and Surveyor
ALBANY

Received Jan 28th 1924
Disposition and Jan 28 1924
Site inspected
Foundation inspected
Structure inspected

Dam No. 415 Upper Hudson Watershed
Serial No. 549

Application for the Construction or Reconstruction of a Dam

Application is hereby made to the State Engineer, Albany, N. Y., in compliance with the provisions of Chapter LXV of the Consolidated Laws and Chapter 647, Laws of 1911, Section 22 as amended, for the approval of specifications and detailed plans, marked Conklingville Dam, Sacandaga Reservoir

herewith submitted for the { construction } of a dam located as stated below. All provisions of law will be complied with in the erection of the proposed dam.

1. The dam will be on Main branch of Sacandaga River in the town of Hagler County of Saratoga and at the hamlet of Conklingville

2. The name and address of the owner is State of New York, Hudson River Regulating District, Albany

3. The dam will be used for Storage Reservoir

4. Will any part of the dam be built upon or its pond flood any State lands? No

5. The watershed at the proposed dam draining into the pond to be formed thereby is 1,044 square miles.

6. The proposed dam will have a pond area at the spillcrest elevation of 26,600 acres and will impound 87,800,000,000 cubic feet of water.

7. The lowest part of the natural shore of the pond is 50 feet vertically above the spillcrest, and every where else the shore will be at least 50 feet above the spillcrest.

8. The maximum known flow of the stream at the dam site was 75 cubic feet per second on March 26, 1913 (Date)

9. State if any damage to life or to property, buildings, roads or other property could be caused by any possible failure of the proposed dam. Yes

10. The natural material of the bed on which the proposed dam will rest is (clay, sand, gravel, boulders, granite, shale, slate, limestone, etc.) Main Conklingville Dam will rest on glacial deposit. Spillway will rest on bed rock

The above information is correct to the best of my knowledge and belief.

Albany, New York
(Address of agent)

Albany, N.Y. 28-1921
(Date)

HUDSON RIVER INSPECTION DISTRICT

Samuel C. Carter

Secretary

(In case of an Agent, the Agent should indicate his title or authority.)

Note: For data required by 11 and 12 see accompanying maps.

11. The material of the right bank, in the direction with the current, is.....; at the spillcrest elevation this material has a top slope of.....inches vertical to a foot horizontal on the center line of the dam, a vertical thickness at this elevation of.....feet, and the top surface extends for a vertical height of.....feet above the spillcrest.

12. The material of the left bank is.....; has a top slope of.....inches to a foot horizontal, a thickness of.....feet, and a height of.....feet.

13. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing, effect of exposure to air and to water, uniformity, etc.....See log of test pits and borings

For answers to 14, 15, 16 see geological section

14. If the bed is in layers, are the layers horizontal or inclined?..... If inclined what is the direction of the slope relative to the center line of the dam and the inches vertical to a foot horizontal?.....

15. What is the thickness of the layers?.....

16. Are there any porous seams or fissures?.....

17. **VALUES.** The spillway of the above proposed dam will be 500' feet long in the clear; the waters will be held at the right end by an earth dam..... the top of which will be 24 feet above the spillcrest, and have a top width of 40 feet; and at the left end by x hillsides..... the top of which will be 50 feet above the spillcrest, and have a top width of xxxx feet.

18. There will be also for flood discharge a pipe.....inches in diameter and the bottom will be..... feet below the spillcrest, a sluice or gate..... feet wide in the clear by..... feet high, and the bottom will be..... feet below the spillcrest.

19. **APRON.** Below the proposed dam there will be an apron built of..... feet long..... feet wide and..... feet thick. The downstream side of the apron will have a thickness of..... feet for a width of..... feet.

20. **PLANS.** Each application for a permit of a dam over 12 feet in height must be accompanied by a location map and complete working drawings of the proposed structure. Each drawing should have a title giving the parts shown, the name of the town and county in which the dam site is located, and the names of the owner and of the engineer.

The location map (U. S. Geological Quadrangle or other map) should show the exact location of the proposed dam; of buildings below the dam which might be damaged by any failure of the dam; of roads adjacent to or crossing the stream below the dam, giving the lowest elevation of the roadway above the stream bed and giving the shape, the height and the width of stream openings, and of any embankments or steep slopes that any flood could pass over. Also indicate the character and use made of the ground.

The complete working drawings should give all the dimensions necessary for the calculations of the stability of the structure, and all the information asked for below under "Sketches." There may be attached to the plans any written reports, calculations, investigations or opinions that may aid in showing the data and method used by the designer.

21. SKETCHES. For small and unimportant structures, if plans have not been made, on the back sheet of this application make a sketch to scale for each different cross-section at the highest point; showing the height and the depth from the surface of the foundation; the bottom width, the top width (for a concrete or masonry spill at 18 inches below the crest), the elevation of the top in reference to the spillcrest, the length of the section, and the material of which the section is to be constructed. Mark each section with a capital letter. Also sketch a plan; show the above sections by their top lines, giving the mark and the length of each; the openings by their horizontal dimensions; and the abutments by their top width and top lengths from the upstream face of the spillcrest and give the elevation of the top in reference to the spillcrest.

22. ELEVATIONS. Also give the elevations, if possible from the Mean Sea Level, of at least two permanent Bench Marks; of the spillcrest for any existing dam on the proposed dam site, at the middle and at both ends of the spill; and of the spillcrest for the above proposed dam.

23. SAMPLES. When so instructed, send samples of the materials to be used in the construction of the proposed dam, using shipping tags which will be furnished. For sand one-half a cubic foot is desired; for cement, three pints; and for the natural bed, twenty cubic inches.

24. INSPECTION. State how inspection is to be provided for during construction.....
Construction to be carried out under careful inspection of resident engineer.....
chief engineer and consulting engineer.

1. 1. The first part of the report
 2. 2. The second part of the report
 3. 3. The third part of the report
 4. 4. The fourth part of the report
 5. 5. The fifth part of the report
 6. 6. The sixth part of the report
 7. 7. The seventh part of the report
 8. 8. The eighth part of the report
 9. 9. The ninth part of the report
 10. 10. The tenth part of the report
 11. 11. The eleventh part of the report
 12. 12. The twelfth part of the report
 13. 13. The thirteenth part of the report
 14. 14. The fourteenth part of the report
 15. 15. The fifteenth part of the report
 16. 16. The sixteenth part of the report
 17. 17. The seventeenth part of the report
 18. 18. The eighteenth part of the report
 19. 19. The nineteenth part of the report
 20. 20. The twentieth part of the report
 21. 21. The twenty-first part of the report
 22. 22. The twenty-second part of the report
 23. 23. The twenty-third part of the report
 24. 24. The twenty-fourth part of the report
 25. 25. The twenty-fifth part of the report
 26. 26. The twenty-sixth part of the report
 27. 27. The twenty-seventh part of the report
 28. 28. The twenty-eighth part of the report
 29. 29. The twenty-ninth part of the report
 30. 30. The thirtieth part of the report
 31. 31. The thirty-first part of the report
 32. 32. The thirty-second part of the report
 33. 33. The thirty-third part of the report
 34. 34. The thirty-fourth part of the report
 35. 35. The thirty-fifth part of the report
 36. 36. The thirty-sixth part of the report
 37. 37. The thirty-seventh part of the report
 38. 38. The thirty-eighth part of the report
 39. 39. The thirty-ninth part of the report
 40. 40. The fortieth part of the report
 41. 41. The forty-first part of the report
 42. 42. The forty-second part of the report
 43. 43. The forty-third part of the report
 44. 44. The forty-fourth part of the report
 45. 45. The forty-fifth part of the report
 46. 46. The forty-sixth part of the report
 47. 47. The forty-seventh part of the report
 48. 48. The forty-eighth part of the report
 49. 49. The forty-ninth part of the report
 50. 50. The fiftieth part of the report
 51. 51. The fifty-first part of the report
 52. 52. The fifty-second part of the report
 53. 53. The fifty-third part of the report
 54. 54. The fifty-fourth part of the report
 55. 55. The fifty-fifth part of the report
 56. 56. The fifty-sixth part of the report
 57. 57. The fifty-seventh part of the report
 58. 58. The fifty-eighth part of the report
 59. 59. The fifty-ninth part of the report
 60. 60. The sixtieth part of the report
 61. 61. The sixty-first part of the report
 62. 62. The sixty-second part of the report
 63. 63. The sixty-third part of the report
 64. 64. The sixty-fourth part of the report
 65. 65. The sixty-fifth part of the report
 66. 66. The sixty-sixth part of the report
 67. 67. The sixty-seventh part of the report
 68. 68. The sixty-eighth part of the report
 69. 69. The sixty-ninth part of the report
 70. 70. The seventieth part of the report
 71. 71. The seventy-first part of the report
 72. 72. The seventy-second part of the report
 73. 73. The seventy-third part of the report
 74. 74. The seventy-fourth part of the report
 75. 75. The seventy-fifth part of the report
 76. 76. The seventy-sixth part of the report
 77. 77. The seventy-seventh part of the report
 78. 78. The seventy-eighth part of the report
 79. 79. The seventy-ninth part of the report
 80. 80. The eightieth part of the report
 81. 81. The eighty-first part of the report
 82. 82. The eighty-second part of the report
 83. 83. The eighty-third part of the report
 84. 84. The eighty-fourth part of the report
 85. 85. The eighty-fifth part of the report
 86. 86. The eighty-sixth part of the report
 87. 87. The eighty-seventh part of the report
 88. 88. The eighty-eighth part of the report
 89. 89. The eighty-ninth part of the report
 90. 90. The ninetieth part of the report
 91. 91. The ninety-first part of the report
 92. 92. The ninety-second part of the report
 93. 93. The ninety-third part of the report
 94. 94. The ninety-fourth part of the report
 95. 95. The ninety-fifth part of the report
 96. 96. The ninety-sixth part of the report
 97. 97. The ninety-seventh part of the report
 98. 98. The ninety-eighth part of the report
 99. 99. The ninety-ninth part of the report
 100. 100. The hundredth part of the report



BOARD OF HUDSON RIVER REGULATING DISTRICT
23 SOUTH PEARL STREET
ALBANY, N. Y.

HENRY M. SAGE, PRESIDENT
EDGAR H. BETTS
ERSKINE C. ROGERS

TELEPHONE MAIN 4260

HARULF COMPTON
SECRETARY-TREASURER
EDWARD H. BARGENT
ENGINEER

Subject: Dam 415 Upper Hudson

February 14, 1934.

Honorable Dwight B. Ladd, State Engineer,
Telephone Building,
Albany, New York.

Dear Sir:

Attention: Hon. Arnold G. Chapman,
Deputy State Engineer.

In further reply to your letter of February 1st, requesting information in connection with the application of the Board for the approval of the plans of the Conklingville Dam, I beg to submit the following:

I believe that the specifications referred to as not having been received have since been received by you. Further, I have had delivered to Mr. McClim the additional prints desired by him.

Ice Pressure

The spillway dam is a part of the Conklingville dam which will create the Sacandaga Reservoir and varies in height from five feet at the westerly end to a maximum height of twenty-four feet at the easterly end. The maximum section is shown on the submitted plans and will be typical for the sections of lesser height. A careful study of the method of operating this reservoir shows that invariably the reservoir will be largely depleted during the winter and consequently no ice pressure will exist at the upper part of the spillway dam.

There has been provided at the spillway crest a bevel two feet vertically by 1.5 feet horizontally to cause the ice to slide up the dam in the remote cases where this ice condition might exist.

Further, an ice thrust of ten thousand pounds per linear foot exerted at a point two feet below the crest of the dam has been assumed.

BOARD OF HUDSON RIVER REGULATING DISTRICT

23 SOUTH PEARL STREET

ALBANY, N. Y.

HENRY M. SAGE, President
EDGAR H. BETTS
ERSKINE C. ROGERS

TELEPHONE MAIN 4260

MANUEL COMPTON
SECRETARY-TREASURER
EDWARD H. SARGENT
ENGINEER

Subject: Dam 415 Upper Hudson

State Engineer-Att: A.G.C.

#2


February 14, 1924.

Uplift

Uplift pressure has been assumed varying from two thirds that of the maximum head at the heel of the dam to zero at the toe of the dam. The resultants for the two extreme conditions assumed, namely maximum flood of 6.5 feet and corresponding uplift and water at crest of dam, corresponding uplift and ice pressure as above noted are shown on the section of the dam on the submitted plans.

"The size of all cut-off walls, core walls and dam section let into the natural bed," I believe are all shown in detail on the plans and sections of the dam. Regarding the permeability of the natural bed of the proposed dam, I think this may well be judged from the logs of the borings and test pits submitted with the application.

Yours very truly,



ENGINEER.

EFB:R

COPY
MEMORANDUM GIVING BASIS OF DESIGN OF SPILLWAY OF CONKLING-
VILLE DAM OF THE PROPOSED SACANDAGA RESERVOIR.

By

EDWARD H. SARGENT, ENGINEER,
HUDSON RIVER REGULATING DISTRICT.

The drainage area at the Conklingville dam site is 1,024 square miles. The flood of March 25th to 30th, 1913, was the greatest known in the history of the Sacandaga River, and fortunately an automatic recording gage was in operation at the stream gaging station maintained since 1907 by the U.S.G.S. a short distance below the dam site. A hydrograph of that flood which reached a maximum of 35,500 c.f.s. is shown on the attached photostat. The assumption in the design of the spillway capacity is a flood (outlined on the photostat) with a peak of 50,000 c.f.s., 40% greater than the peak of the 1913 flood. It has been assumed that the reservoir which has an area at the spillway crest of 1,160,000,000 square feet (26,600 acres) was full at the beginning of this flood. With these assumptions various length spillways of from 500 to 800 feet have been assumed and a study made of what the effect of storage in the reservoir above the spillway crest would have been on reducing the flood. Hydrographs have been computed and plotted showing the discharge and elevations reached during such a flood. From these studies it has been determined that the proper spillway length is 600 feet on which the maximum depth during the assumed maximum flood would be 6.45 feet. The proposed spillway elevation is at elevation 771 and the crest of the proposed earth dam is at elevation 795, a freeboard of 24 feet, which would give a clearance of over 17 feet above the maximum high water.

1. No line

HUDSON RIVER REGULATING DISTRICT

CONKLINGVILLE DAM

The Conklingville dam will be an earth structure approximately 100 feet high founded upon the glacial drift with which the ancient valley is filled. The top of the dam is to be at elevation 795.0 with a top width of 40 feet; the upstream slopes varying from 3 to 1 at the top of the dam to 4 to 1 at the base and the downstream slope being 2 1/2 to 1 with 8 foot berms at elevations 775 and 745. The above slopes give a maximum bottom width of the dam of 600 feet.

The dam is to be constructed by the semi-hydraulic fill process, that is, the earth will be excavated from the properly designated borrow pits, transported in dump cars to the dam site and deposited in dikes above and below and parallel with the axis of the dam. The fine part of this earth will then be sluiced into the center of the dam to form an impervious core. The foundation of the dam will be excavated to a depth of at least five feet, and more if warranted by the conditions revealed, for a width of 300 feet. A cut-off trench about 20 feet deep and 50 feet wide will be excavated at the base of the center of the dam and a cut-off trench will be excavated where the dam joins the side hill.

Several test pits have been excavated in the area in which it is proposed to locate the borrow pits out of which the material will come for the main dam. Analyses made of this material indicate that it is exceptionally well-fitted for earth dam construction and that there will be available ample material of an effective diameter of 0.01 millimeters for the core of the dam. The dam has been designed so that the core which will have a top width at elevation 750 of 30 feet and a bottom width of 140 feet is of sufficient cross-section to render the dam impermeable.

The upstream slope of the dam will be rip-rapped between elevations 730 and 795 and the downstream toe protected from erosion from any back wash of the spillway discharge by placing the rock spoil from the excavation of the spillway channel at the foot of the dam and up to elevation 730.

CONKLINGVILLE DAM - 2

Spillway The spillway will consist of a concrete gravity type dam 600 feet long extending upstream from the dam. The water will be led away from the spillway to the riverbed below the dam in a discharge channel cut in the ledge rock as shown on the plans. A memorandum giving the basis of design of the spillway has been submitted to and approved by the State Engineer. In brief this basis is as follows: The drainage area at Conklingsville dam site is 1,044 square miles. The flood of March 25th to 30th, 1913 was the greatest known in the history of the Sacandaga River and reached a peak of 35,500 cubic feet per second. The assumption in the design of the spillway capacity is a flood with a peak of 50,000 cubic feet per second and it was further assumed that the reservoir was full at the beginning of the flood. Under such assumptions the flood would have reached a maximum depth of the 600 foot spillway of 6.45 feet. It is pertinent to note that should a flood equal to the famous Miami River flood occur with the reservoir full, the water would reach a depth of less than 10 feet on the spillway crest, leaving a freeboard of over 14 feet.

Log-Way The plans of the dam and spillway provide for a log-way or chute for passing the logs from the reservoir to the river below the dam. The log-way is located in an extension of the spillway at its extreme westerly end.

Highways At Dam It is proposed to construct a highway on the dam connecting the existing highway routes on both sides of the river. The highway on the dam will cross the spillway channel on a concrete arch bridge.

CONKLINGVILLE DAM - 3

Outlet Works The regulated flow from the reservoir will be withdrawn through a gate-house located in the reservoir about 300 feet above the northerly end of the main dam and thence discharged through an outlet tunnel 24 feet in diameter by passing the main dam into the river below. This tunnel will also serve as a diversion tunnel to take care of the flow of the river during the construction period. The gate-house will include six caterpillar sluice gates 12 feet, 6 inches by 6 feet with a discharging capacity at the low flow line (elevation 740) of 3,000 cubic feet per second. A bridge will connect the gate-house to the mainland.

Both an automatic recording gage and a staff gage will be installed in the gate-house in order that a careful record can be kept of the fluctuation of the water surface of the reservoir.

E. H. Sargent
Engineer to the Board



STATE OF NEW YORK
STATE ENGINEER AND SURVEYOR
ALBANY

ROY G. FINCH
STATE ENGINEER
FRANK R. LANAGAN
DEPUTY
THOS. L. WATKINS
ASSISTANT DEPUTY

ADDRESS ALL COMMUNICATIONS TO
ROY G. FINCH, STATE ENGINEER

COPY FOR MR. McKIM

ERL-DW

July 14, 1926.

Mr. Edward H. Sargent, Chief Engineer,
Board of Hudson River Regulating District,
44 Howard Street,
Albany, New York.

Dear Sir:

Receipt is acknowledged of your letter of
July 12th, together with a sample from ledge rock
proposed as a quarry for crushed stone to be used
in first-class concrete in connection with the con-
struction of the Sacandaga Reservoir.

In reply to your inquiry as to whether this
stone, when properly crushed and screened, would be
suitable for use in such concrete, you are advised
that it should be satisfactory except in concrete
subject to high temperatures such as resulting from
exposure to fire.

The sample of rock submitted is of the
general type of Adirondack granite. It is composed
mainly of quartz, feldspar, hornblende and garnet.
because of the relatively large percentage of horn-
blende, it might be called a "hornblende-granite". The
rock sample is hard and dense with a specific gravity
indicating a weight of 163 pounds per cubic foot.

Very truly yours,

Roy G. Finch,
State Engineer.

By
Deputy State Engineer.

Copy for Mr. McKim

November 24, 1926.

Dam 415 U. Hudson
Canajoharie

The Board of Hudson River Regulating District,
44 Howard St.,
Albany, N. Y.

Gentlemen:

There has been submitted to the State Engineer by your Chief Engineer Edward H. Bargent, application and 4-drawings marked AOC 2314, 2315, 2316 and 2317, for a revised design of the Conalingville dam on the Sacandaga river, which dam is designated by this department as dam No. 415 Upper Hudson watershed.

You are hereby given permission to November 1st, 1929 insofar as the matter involves the jurisdiction conferred upon this office by chapter 647, laws of 1911, section 28, as amended, to construct the above dam according to the submitted drawings, under the following conditions:

(1) That our Albany Division Engineer Mr. R. D. Hendricks, be notified a week in advance of the date when any section of the bed will be excavated and ready for the construction of the puddled core or the concrete work.

(2) That your engineer submit a report to this department on each section of the bed and banks of the above dam as soon as a section is prepared for the foundation concerning the character of the natural bed upon or against which the section is to be constructed, the permeability and the methods taken to test same, and the dimensions of the excavations for the concrete sections and the cutoff. If the soil under core cutoff is not impervious steps must be taken to prevent the passage of water in the finished structure.

(3) That two samples of a part each of the hydraulic puddled core from the lowest 5 ft. thick section and from each subsequent 10 ft. section be forwarded the day following the completion of each section to the State Engineer's laboratory, Hamilton Street and Broadway, Albany, N.Y., one sample to be taken from the center and one from the outside 1/3 of the core. These samples to be numbered serially with odd numbers for the center and even

BOARD OF HUDSON RIVER REGULATING DISTRICT

44 HOWARD STREET

ALBANY, N. Y.

TELEPHONES (MAIN 4260)
(MAIN 2625)

HENRY M. SAGE, PRESIDENT

ERNEST C. ROGERS

ELLISON MILLS

WYATT FITZGERALD, JR.

RANULF COMPTON

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

November 16, 1926.

Hon. Roy G. Finch, State Engineer and Surveyor,
Journal Building,
Albany, N. Y.

Dear Sir:

On March 4, 1924, the State Engineer and Surveyor by Mr. Arnold C. Chapman, Deputy State Engineer, approved the plans for the Conklingville Dam of the Sacandaga Reservoir which were submitted in accordance with the provisions of Section 22 of the Conservation Law.

Since that time further studying has been made as a result of which revised plans for the Conklingville Dam and appurtenances have been made, which in our opinion, will considerably reduce the cost of the dam and at the same time make it of a more conservative design.

We accordingly submit to you the following drawings:

General Plan of the Conklingville Dam - Accession 2614.

Typical Sections of the Conklingville Dam - Accession 2615.

Outlet Works of the Conklingville Dam - Accession 2616.

Spillway Details of the Conklingville Dam - Accession 2617.

The principal difference between the original and revised plans is in regard to the spillway. In the plans as originally submitted, the spillway was located upstream from the dam and was 600 feet long, whereas the revised plans show a spillway downstream from the dam with a length of 400 feet together with a siphon spillway of a maximum capacity of over 8,000 cubic feet per second.

The drainage area at the Conklingville Dam site is 1,644 square miles. The flood of March 25th-30th, 1913 was the greatest known in the history of the Sacandaga River and fortunately an automatic recording gauge was in operation at the stream gauging station maintained since 1907 by the U. S. G. S., a short distance below the dam site. Computation made from a hydrograph of this flood which reached a 24-hour maximum of 33,500 c. f. s. and an average maximum of 35,500 c. f. s.

BOARD OF HUDSON RIVER REGULATING DISTRICT

44 HOWARD STREET

ALBANY, N. Y.

TELEPHONES (MAIN 4260)
(MAIN 2625)

HENRY M. PAGE, PRESIDENT

WILLIAM C. HARRIS

W. ELLISON MILLS

VICTOR J. FITZGERALD, Jr.

RANULF COMPTON

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

Hon. Roy G. Finch - Page Two.

11/16/26.

It may be pertinent to note that stream flow records have been kept on the Hudson River at Mechanicville since 1887 and the 1913 flood, which reached a maximum at Mechanicville of 120,000 c. f. s., was greater by 30,000 c. f. s. than any other flood during the period of the record. The 1913 flood reached an elevation in Albany greater than any other, records of flood heights having been kept at Albany for nearly a hundred years.

The assumption in the design of the spillway capacity is a flood (outlined on E-4005) with a peak of 50,000 c. f. s., forty percent greater than the peak of the 1913 flood. Moreover, it has been assumed that the Sacandaga Reservoir, which has an area at the spillway crest of 1,160,000,000 square feet (26,600 acres), was full at the beginning of this flood.

There is given below a table showing the maximum 24-hour floods for the Sacandaga River immediately below the dam site for the years 1908 to 1924:

| YEAR | MAXIMUM
24-hour FLOOD
c. f. s. |
|------|--------------------------------------|
| 1908 | 20,000 |
| 1909 | 19,700 |
| 1910 | 15,800 |
| 1911 | 9,000 |
| 1912 | 13,400 |
| 1913 | 53,500 |
| 1914 | 19,500 |
| 1915 | 10,300 |
| 1916 | 10,600 |
| 1917 | 12,600 |
| 1918 | 13,500 |
| 1919 | 11,500 |
| 1920 | 12,500 |
| 1921 | 11,500 |
| 1922 | 20,000 |
| 1923 | 14,000 |
| 1924 | 20,000 |

The average yearly flood over the period of 17 years is 16,200 c. f. s. (See full report (Transmittal No. 509).

BOARD OF HUDSON RIVER REGULATING DISTRICT

46 HOWARD STREET

ALBANY, N. Y.

TELEPHONES (MAIN 4268)
(MAIN 2625)

RANULF COMPTON

Secretary-Treasurer

EDWARD H. SARGENT

Chief Engineer

HENRY M. SAGE, PRESIDENT

JESKINE C. ROGERS

W. ELLISON MILLS

DAVID J. FITZGERALD, Jr.

Hon. Roy G. Finch - Page Three.

11/16/26.

Volume LXXVII, Page 567), it has been computed that the assumed maximum flood of 60,000 c. f. s. is one that may be expected to occur once in 888 years.


The rise of the reservoir under the conditions of the 1913 flood and the assumed maximum flood is shown on Accession E-4006. Blue-prints of both these computation sheets are enclosed. With a 600 foot spillway as shown on the original plans, the assumed maximum flood would have caused the reservoir to rise to elevation 777.45. On Accessions W-344 and W-347 are shown respectively the rise of the reservoir under the 1913 flood and the assumed maximum flood conditions with the plans as revised. Under the latter conditions the water would have risen to a maximum elevation of 778.95. It will be noted on the plans that the spillway crest is at elevation 771.0 and the top of the main earth dam is at elevation 795.0, -- a freeboard of 24 feet, so that under the assumed maximum flood conditions, the top of the reservoir would be over 16 feet above the elevation of the reservoir. It might be noted that on the revised plans the spillway is located entirely on rock whereas on the original plans, part of the spillway foundation was located on hard pan.

It is thought that another improvement in the revised plans is the elimination of the tunnel which was provided in the original plan under the spillway channel and around the north end of the dam to carry the river flow during construction and acted as the permanent reservoir outlet with regulating gates at the tunnel entrance. In the revised plan, this tunnel is replaced by an open channel excavated in the rock hillside at the north end of the dam. After the completion of the dam, the outlet end of this diversion channel is to be plugged with a concrete structure containing the regulating gates and also containing two 6 ft. by 18 ft. siphon sills. The upstream portion of this channel serves also as an approach channel to the spillway weir.

It is believed, also, that the revised plans show a much more economic design and location of the various appurtenances of the Conalingville Dam, particularly the gate house, logway, and the bridge over the spillway.

A further greater factor of safety is given in the revised plans in which we have provided for a rock fill at the downstream toe of the main dam to be carried up to elevation 745.0, which will furnish an even greater protection and stability than is shown on the original plans.

Respectfully submitted,



CHIEF ENGINEER

Encls.
ESE:G.P.

Copy for Mr. McKim

November 24, 1926.

Dam 415 U. Hudson
Corklingville

The Board of Hudson River Regulating District,
44 Howard St.,
Albany, N. Y.

Gentlemen:

There has been submitted to the State Engineer by your Chief Engineer Edward H. Bargent, application and 4-drawings marked ACC 2614, 2615, 2616 and 2617, for a revised design of the Corklingville dam on the Sacandaga River, which dam is designated by this department as dam No. 415 Upper Hudson watershed.

You are hereby given permission to November 1st, 1929 insofar as the matter involves the jurisdiction conferred upon this office by chapter 647, laws of 1911, section 28, as amended, to construct the above dam according to the submitted drawings, under the following conditions:

(1) That our Albany Division Engineer Mr. E. D. Hendricks, be notified a week in advance of the date when any section of the bed will be excavated and ready for the construction of the puddled core or the concrete work.

(2) That your engineer submit a report to this department on each section of the bed and banks of the above dam as soon as a section is prepared for the foundation concerning the character of the natural bed upon or against which the section is to be constructed, the permeability and the methods taken to test same, and the dimensions of the excavations for the concrete sections and the cutoff. If the soil under core cutoff is not impervious steps must be taken to prevent the passage of water in the finished structure.

(3) That two samples of a quart each of the hydraulic puddled core from the lowest 6 ft. thick section and from each subsequent 10 ft. section be forwarded the day following the completion of each section to the State Engineer's Laboratory, Hamilton Street and Broadway, Albany, N.Y., one sample to be taken from the center and one from the outside 1/3 of the core. These samples to be numbered serially with odd numbers for the center and even.

11-21-26

numbers for the nitello 1/5 samples.

This approval supersedes our approval of March 4, 1924 and shall not be deemed to authorize any invasion of property rights, either public or private in carrying out the above work nor to create any claim or demand against the State of New York; nor to authorize the flooding or use of State lands; nor to acquiesce in the flooding or use of such lands.

There is enclosed shipping tags numbered 200 to 206, inclusive, in order that you may ship to our laboratory for testing, besides the above samples of the ruddled core, 1/2 a cu. ft., exclusive of any stones over 1/4 inch in size mixed therewith, of the sand to be used in the concrete of the above dam.

There is also enclosed the above four drawings with the approval of this department thereon.

Kindly acknowledge the receipt of this letter and of the drawings.

Yours very truly,

Roy G. Finch,
State Engineer.

By *Frank P. L...*
Assistant Deputy.

Copy and 4 prints to
Div. Engr. W. D. Hendricks

Copy to Sr. Asst. Engr. Greenman

ARMOK/ECM

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100


100


100

100

100

100








1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100

Stability Computations - Conklingville Dam



Concrete - Moments about 'X'

$$\begin{aligned} a & 6.0 \times 24.0 \times 141' = 20304 \times 24.0 = 487296 \\ b & \frac{10.0}{2} \times 24.0 \times 141' = 30456 \times 15.0 = 456840 \\ c & \frac{3.0}{2} \times 27.0 \times 141' = 11431 \times 13.5 = 154318.5 \\ & \underline{62181} \quad \underline{1093350} \end{aligned}$$

Water

$$\begin{aligned} d & 6.0 \times 6.5 \times 62.5 = 2438 \times 24.0 = 58512 \\ e & \frac{2.5}{2} \times 6.5 \times 62.5 = 1524 \times 6.75 = 10263 \\ f & \frac{3.0}{2} \times 10.0 \times 62.5 = 1875 \times 1.5 = 2812.5 \\ & \underline{5837} \quad \underline{72627} \end{aligned}$$

Condition I - H.W. on crest - Uplift

$$\begin{aligned} \text{Concrete} & = 62181' & 1093350' \\ \text{Water} & = 5837 & 72627 \\ & \underline{68018} & \underline{1170977} \\ \text{Uppressure } \frac{1326 \times 27.0}{2} & = -18846 & \times 12.0 = -226152 \\ & \underline{49162} & \underline{831719} \end{aligned}$$

Water pressure - Overturning

$$62.5 \times 27' \left(\frac{27}{2} + \frac{6.5}{2} \right)$$

= 35310'

Water pressure - Resisting

$$62.5 \times 13'$$

$$= 81250'$$

$$F = \frac{50180}{49162} = 1.02 \text{ from } \dots$$

Computed by ...


Stability Computations - Conklingville Dam -


Condition II - Water at crest elev. Ice pressure - 100 ft.



| | | |
|---|-------------------------|--------------|
| Concrete - | 62181 | 1097380 |
| Uppressure $\frac{1125 \times 27.0}{2} =$ | $- 15188 \times 18.0 =$ | $- 273534$ |
| | 46993 | 814936 |
| Ice pressure 10000×2.5 | | $= - 250000$ |
| | | 564936 |
| Water pressure $64.5 \times \frac{27}{6}$ | | $= 205031$ |
| | | 359905 |
| $\gamma = \frac{359905}{46993} = 7.66'$ | | |

APPENDIX E

CONSTRUCTION DRAWINGS







PROPOSED

M. B. Carter
 DESIGNING ENGINEER


The complete working drawings should give all the dimensions necessary for the calculations of the stability of the structure, and all the information asked for below under "Sketches." There may be attached to the plans any written reports, calculations, investigations or opinions that may aid in showing the data and method used by the designer.

21. SKETCHES. For small and unimportant structures, if plans have not been made, on the back sheet of this application make a sketch to scale for each different cross-section at the highest point, showing the height and the depth from the surface of the foundation, the bottom width, the top width (for a concrete or masonry spill at 18 inches below the crest), the elevation of the top in reference to the spillcrest, the length of the section, and the material of which the section is to be constructed. Mark each section with a capital letter. Also sketch a plan, show the above sections by their top lines, giving the mark and the length of each; the openings by their horizontal dimensions; and the abutments by their top width and top lengths from the upstream face of the spillcrest and give the elevation of the top in reference to the spillcrest.


22. ELEVATIONS. Also give the elevations, if possible from the Mean Sea Level, of at least two permanent Bench Marks; of the spillcrest for any existing dam on the proposed dam site, at the middle and at both ends of the spill; and of the spillcrest for the above proposed dam.

23. SAMPLES. When so instructed, send samples of the materials to be used in the construction of the proposed dam, using shipping tags which will be furnished. For sand one-half a cubic foot is desired; for cement, three pints; and for the natural bed, twenty cubic inches.

24. INSPECTION. State how inspection is to be provided for during construction.....
Construction to be carried out under careful inspection of resident engineer;.....
chief engineer and consulting engineer.



TYPICAL SECTION



PROPOSED CONSTRUCTION METHOD

2

CONTRACT A

SHEETS 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100

Notes

As stated in the specifications, modification of the proposed method of depositing material in the dikes may be used if approved by the Engineer.


The location of the core and the dimensions of the areas of the washed and unwashed material shown on this plan may be changed to suit borrow pit conditions.


STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
CONKLINGVILLE DAM
TYPICAL SECTIONS

3

SEPT 1927

W. H. Smith





CENTRAL

AREA

This is a
map of the

800

700

760

740

720

700

680

660

Elevation in Feet Above Sea Level

300

500


1 on 250



Malvin B. Carter
DESIGNING ENGINEER



Alvin P. Brown
CONSULTING ENGINEER



STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
CONKLINGVILLE DAM
GENERAL LAYOUT

100 0 1000

SEPT. 1927

CHIEF ENGINEER

STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
CONKLINGVILLE DAM

CONTRACT DRAWINGS FOR CONTRACT 4
CONSISTING OF 32 SHEETS NUMBERED ACC. 2687 TO ACC. 2718 INCLUSIVE

HENRY M. SAGE, PRESIDENT

DAVID J. FITZGERALD JR., W. ELLISON MILLS,
MEMBERS OF THE BOARD.


RANULF COMPTON, SECRETARY.


EDWARD H. SARGENT, CHIEF ENGINEER.

CHARLES W. WALTON, COUNSEL.

ALBERT S. CRANE. FRANK M. WILLIAMS, CONSULTING ENGINEERS.

APPROVED BY RESOLUTION OF THE BOARD OF HUDSON RIVER REGULATING DISTRICT SECRETARY.
W. E. Ellison





S
304

Oliver & Son
Consulting Engineers

Oliver & Son
Consulting Engineers

2.



1953-54




founder's excavations now but by the drawings
and app. make only brief notations to be determined
by the engineer on the map progress.

Handwritten signature

FILE

ACC. 2694




MAURICE E. COSTER
DIRECTOR OF INVESTIGATION

DRAWN: *Letty*
 TOOK: *Letty*
 CURED: *not before*

CONTRACT 4 SHEET 17
SHEETS IN SET 32

2



The bases of the structures shown on this plan shall be assumed to be within the dry and not to be ordered by the Engineer and to be at the discretion and of any dimension necessary to give a proper foundation.

STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
CONKLINGVILLE DAM
OUTLET CHANNEL AND OUTLET STRUCTURE

SEPT 1927

Edw. L. Loring
CHIEF ENGINEER


SECTIONS
(CONTROL HOUSE AND PIPE RAILING OMITTED)

Albert C. Carr
CONSULTING ENGINEER

FILE

ACC. 2703

CONTRACT 4 SHEET 20
SHEETS IN SET 32



UPSTREAM ELEVATION

The scale of this drawing is given on the title sheet and on the sheet of notes. It is to be used for all dimensions unless otherwise indicated. The scale of this drawing is 1" = 100'.

For Notes, See Sheet 2000
For Scale, See Sheet 2000






ALVIN B. BROWN
CONSULTING ENGINEER

STATE OF NEW YORK
HUDSON RIVER REGULATING DISTRICT
SACANDAGA RESERVOIR
OUTLET STRUCTURE
PLAN AND ELEVATIONS


SEPTEMBER


FILE

ACC 2706






CONTRACT 4 SHEET 21
SHEETS IN SET 32





SECTION G-G

1/4" = 10' - 0"



SECTION K-K

1/4" = 10' - 0"

APPENDIX F
VISUAL CHECK LIST

CHECK LIST
VISUAL INSPECTION
PHASE I

NAME DAM Conklingville Dam COUNTY Saratoga STATE New York ID# NY 146

TYPE OF DAM Earthfill HAZARD CATEGORY High

DATE(S) INSPECTION 6/16/78 WEATHER warm, clear TEMPERATURE 75°

POOL ELEVATION AT TIME OF INSPECTION 766.15 M.S.L. TAILWATER AT TIME OF INSPECTION 704.0 M.S.L.

INSPECTION PERSONNEL:

R. Jeffrey Kimball, P.E. - LRK

John Anderson - Engineer HRBRD

James T. Hockensmith - LRK

Bob Allen - HRBRD

James T. Hockensmith RECORDER

EMBANKMENT

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|---|----------------------------|
| SURFACE CRACKS | None noted | |
| UNUSUAL MOVEMENT OR
CRACKING AT OR BEYOND
THE TOE | None noted | |
| SLOUGHING OR EROSION
OF EMBANKMENT AND
ABUTMENT SLOPES | None noted | |
| VERTICAL AND HORIZONTAL
ALIGNMENT OF THE CREST | Appears to be good and stable. Settlement
gauge readings discontinued after no
movement recorded. | |
| RIPRAP FAILURES | None noted | |

EMBANKMENT

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|---|------------------------------------|----------------------------|
| JUNCTION OF EMBANKMENT
AND ABUTMENT, SPILLWAY
AND DAM | Appears to be good and stable. | |
| ANY NOTICEABLE SEEPAGE | None noted | |
| STAFF GAGE AND RECORDER | Pool level read daily and recorded | |
| DRAINS | None | |

CONCRETE/MASONRY DAMS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|--------------|----------------------------|
| ANY NOTICEABLE SEEPAGE | N/A | |
| STRUCTURE TO
ABUTMENT/EMBANKMENT
JUNCTIONS | N/A | |
| DRAINS | N/A | |
| WATER PASSAGES | N/A | |
| FOUNDATION | N/A | |

CONCRETE/MASONRY DAMS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-------------------------------------|--------------|----------------------------|
| SURFACE CRACKS
CONCRETE SURFACES | N/A | |
| STRUCTURAL CRACKING | N/A | |
| VERTICAL AND HORIZONTAL ALIGNMENT | N/A | |
| MONOLITH JOINTS | N/A | |
| CONSTRUCTION JOINTS | N/A | |
| STAFF GAGE OF RECORDER: | N/A | |

OUTLET WORKS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|---|----------------------------|
| CRACKING AND SPALLING OF
CONCRETE SURFACES IN
OUTLET CONDUIT | Not observed - Three 8 foot diameter
steel flanged pipes - not normally
operated. | |
| INTAKE STRUCTURE | Intake control house operating three
valves invert at 699.0. | |
| OUTLET STRUCTURE | Three 8 foot pipes discharge directly
into Stewart Bridge Reservoir. | |
| OUTLET CHANNEL | Outlet channel is 100' long with
concrete walls. Channel discharges
directly into Stewart Bridge Reservoir. | |
| EMERGENCY GATE | No emergency gates on structures,
dowell valves only. | |

OUTLET WORKS - Through Power House

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|---|----------------------------|
| CRACKING AND SPALLING OF
CONCRETE SURFACES IN
OUTLET CONDUIT | Not observed - Normal discharge is through spillway approach channel and into power house through gates. Power house operated by Niagara-Mohawk Power Company. Facilities unobserved. | |
| INTAKE STRUCTURE | Through gates adjacent to spillway approach channel. Normal discharge is 4,000 cfs. | |
| OUTLET STRUCTURE | Through power house and into Stewarts Bridge Reservoir. | |
| OUTLET CHANNEL | Stewarts Bridge Reservoir to Hudson - Fairly wide channel with steep hillside. | |
| EMERGENCY GATE | None | |

UNGATED SPILLWAY

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-----------------------|---|----------------------------|
| CONCRETE WEIR | 400 foot concrete weir in good condition. Several weep holes below weir are producing water through joints in rock. | |
| APPROACH CHANNEL | Approximately 400 feet long and 20 foot wide cut into rock and concrete retaining walls. Water flowing in channel and bottom unobserved. Appears to be in good condition. | |
| DISCHARGE CHANNEL | Discharge over weir and down rock cut (about 80' vertical) and discharges in Sacramento River and Stewart Bridge Reinforced. | |
| BRIDGE AND PIERS | None | |
| | | |

UNGATED SPILLWAY - Siphon

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-----------------------|---|----------------------------|
| CONCRETE WEIR | Unobserved - in control house concrete weir at elevation 773 feet - Self priming at elevation 773 feet. Siphon inlets two 8 x 18' openings. | |
| APPROACH CHANNEL | Approach channel same as other spillways - rock cut with a concrete retaining wall. | |
| DISCHARGE CHANNEL | 30 feet wide outlet channel - concrete lined with retaining walls - in good condition. Same as pipe outlet channel. | |
| BRIDGE AND PIERS | None | |
| | | |

OUTLET WORKS - Outlet Structure

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|---|----------------------------|
| CRACKING AND SPALLING OF
CONCRETE SURFACES IN
OUTLET CONDUIT | Three 8 foot steel pipes. Exit and
entrance inverts at 699.0'. | |
| INTAKE STRUCTURE | Sluice gate over end of 8 foot pipe. | |
| OUTLET STRUCTURE | 8 foot pipe discharges directly to
outlet channel. | |
| OUTLET CHANNEL | 30 foot wide concrete channel with
retaining walls. | |
| EMERGENCY GATE | None | |

DOWNSTREAM CHANNEL

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|---|---|----------------------------|
| CONDITION
(OBSTRUCTIONS,
DEBRIS, ETC.) | Sacandaga River and Stewarts Bridge
Reservoir.
wide and flat. | |
| SLOPES | Side slopes moderately steep but stable. | |
| APPROXIMATE NO.
OF HOMES AND
POPULATION | Several thousand people. | |
| | | |
| | | |

RESERVOIR

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-----------------------|---|----------------------------|
| SLOPES | Gently rolling to moderately steep - stable. | |
| SEDIMENTATION | Sedimentation has not been a problem nor is expected to be. | |
| | | |
| | | |
| | | |

INSTRUMENTATION

| VISUAL EXAMINATION | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-----------------------|---|----------------------------|
| MONUMENTATION/SURVEYS | None | |
| OBSERVATION WELLS | None | |
| WEIRS | None | |
| PIEZOMETERS | None | |
| Settlement plates | Very little settlement in past. Not currently read. | |

APPENDIX G

ENGINEERING DATA CHECK LIST

| ITEM | REMARKS | item held by |
|---|--|---|
| DESIGN REPORTS | Unknown | |
| GEOLOGY REPORTS | "Report on the north abutment of the Conklingville Dam" by Irving B. Crosby, Geologist, April, 1928. | Owner |
| DESIGN COMPUTATIONS
HYDROLOGY & HYDRAULICS
DAM STABILITY
SEEPAGE STUDIES | Sipon spillway computations | Owner |
| MATERIALS INVESTIGATIONS
BORING RECORDS
LABORATORY
FIELD | Soil test pits and borings logs
Grain size (blue prints) | New York State
Department of
Environmental
Conservations |
| POST-CONSTRUCTION SURVEYS OF DAM | Unknown | |
| BORROW SOURCES | Mostly on right abutment - details unknown | |

| ITEM | REMARKS | item held by |
|---|---|--------------|
| MONITORING SYSTEMS | Settlement pipes | Owner |
| MODIFICATIONS | None | |
| HIGH POOL RECORDS | Yearly hydrograph of Hudson River at
Spier Falls - Daily Reservoir Records | Owner |
| POST CONSTRUCTION ENGINEERING
STUDIES AND REPORTS | Asphalt grouting
Brief report on design changes | Owner |
| PRIOR ACCIDENTS OR FAILURE OF DAM
DESCRIPTION
REPORTS | None | |
| MAINTENANCE
OPERATION
RECORDS | Complete records of dam | Owner |

REMARKS

item held by

SPILLWAY PLAN

Contract Drawings

Owner

SECTIONS

Contract Drawings

Owner

DETAILS

Contract Drawings

Owner

OPERATING EQUIPMENT
PLANS & DETAILS

Contract Drawings

Owner

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 1,050 square miles - gently rolling, wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): variable high (771)- 1.16 mill. ac-ft
low (740)- est. 3 mill. ac-ft

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 771' - 1.16 million acre-feet

ELEVATION MAXIMUM DESIGN POOL: 778.95'

ELEVATION TOP DAM: 795.0'

CREST: Spillway

- | | |
|-----------------------------|--|
| a. Elevation | <u>771.0'</u> |
| b. Type | <u>Concrete ogee</u> |
| c. Width | <u>ogee section - see drawings for details</u> |
| d. Length | <u>400'</u> |
| e. Location Spillover | <u>Left abutment</u> |
| f. Number and Type of Gates | <u>None</u> |

OUTLET WORKS:

- | | <u>Through Power House</u> | <u>Outlet Structure</u> |
|-----------------------------------|--------------------------------|------------------------------|
| a. Type | <u>Three sluice gates</u> | <u>Three 8' pipes</u> |
| b. Location | <u>end of approach channel</u> | <u>base of control house</u> |
| c. Entrance inverts | <u>approximately 761'</u> | <u>699'</u> |
| d. Exit inverts | <u>approximately 700'</u> | <u>699'</u> |
| e. Emergency draindown facilities | <u>None</u> | <u>Yes</u> |

HYDROMETEOROLOGICAL GAGES:

- | | | |
|-------------|--|-----------------------|
| a. Type | <u>Rainfall & snow sur- Continuous pool level record</u> | <u>Gaging Station</u> |
| b. Location | <u>Control house</u> | <u>Downstream</u> |
| c. Records | <u>Continuous</u> | <u>Daily</u> |

MAXIMUM NON-DAMAGING DISCHARGE Elevation 770.75' discharge 10,000 cfs
maximum to date

APPENDIX G

ENGINEERING DATA CHECK LIST

| ITEM | REMARKS | Item Held by |
|---|--|---|
| DESIGN REPORTS | Unknown | |
| GEOLOGY REPORTS | "Report on the north abutment of the Conklingville Dam" by Irving B. Crosby, Geologist, April, 1928. | Owner |
| DESIGN COMPUTATIONS
HYDROLOGY & HYDRAULICS
DAM STABILITY
SEEPAGE STUDIES | Sipon spillway computations | Owner |
| MATERIALS INVESTIGATIONS
BORING RECORDS
LABORATORY
FIELD | Soil test pits and borings logs
Grain size (blue prints) | New York State
Department of
Environmental
Conservations |
| POST-CONSTRUCTION SURVEYS OF DAM | Unknown | |
| BORROW SOURCES | Mostly on right abutment - details unknown | |

| ITEM | REMARKS | item held by |
|---|---|--------------|
| MONITORING SYSTEMS | Settlement pipes | Owner |
| MODIFICATIONS | None | |
| HIGH POOL RECORDS | Yearly hydrograph of Hudson River at
Spier Falls - Daily Reservoir Records | Owner |
| POST CONSTRUCTION ENGINEERING
STUDIES AND REPORTS | Asphalt grouting
Brief report on design changes | Owner |
| PRIOR ACCIDENTS OR FAILURE OF DAM
DESCRIPTION
REPORTS | None | |
| MAINTENANCE
OPERATION
RECORDS | Complete records of dam | Owner |

| | REMARKS | item held by |
|--|-------------------|--------------|
| SPILLWAY PLAN | Contract Drawings | Owner |
| SECTIONS | Contract Drawings | Owner |
| DETAILS | Contract Drawings | Owner |
| OPERATING EQUIPMENT
PLANS & DETAILS | Contract Drawings | Owner |

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 1,050 square miles - gently rolling, wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): variable high (771)- 1.16 mill. ac-ft
low (740)- est. 3 mill. ac-ft

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 771' - 1.16 million acre-feet

ELEVATION MAXIMUM DESIGN POOL: 778.95'

ELEVATION TOP DAM: 795.0'

CREST: Spillway

| | |
|-----------------------------|--|
| a. Elevation | <u>771.0'</u> |
| b. Type | <u>Concrete ogee</u> |
| c. Width | <u>ogee section - see drawings for details</u> |
| d. Length | <u>400'</u> |
| e. Location Spillover | <u>Left abutment</u> |
| f. Number and Type of Gates | <u>None</u> |

OUTLET WORKS:

| | <u>Through Power House</u> | <u>Outlet Structure</u> |
|-----------------------------------|--------------------------------|------------------------------|
| a. Type | <u>Three sluice gates</u> | <u>Three 8' pipes</u> |
| b. Location | <u>end of approach channel</u> | <u>base of control house</u> |
| c. Entrance inverts | <u>approximately 761'</u> | <u>699'</u> |
| d. Exit inverts | <u>approximately 700'</u> | <u>699'</u> |
| e. Emergency draindown facilities | <u>None</u> | <u>Yes</u> |

HYDROMETEOROLOGICAL GAGES:

| | | | |
|-------------|-----------------------------------|-------------------------------------|-----------------------|
| a. Type | <u>Rainfall & snow survey</u> | <u>Continuous pool level record</u> | <u>Gaging Station</u> |
| b. Location | <u>Control house</u> | | <u>Downstream</u> |
| c. Records | <u>Continuous</u> | | <u>Daily</u> |

MAXIMUM NON-DAMAGING DISCHARGE Elevation 770.75' discharge 10,000 cfs
maximum to date